

Power and productivity
for a better world™

ABB drives - Technical guide book

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AFE64514482 REV F 17.6.2011

Contents

1. **Direct torque control** explains what DTC is; why and how it has evolved; the basic theory behind its success; and the features and benefits of this new technology.

2. **EU Council Directives and adjustable speed electrical power drive systems** is to give a straightforward explanation of how the various EU Council Directives relate to Power Drive Systems.

3. **EMC compliant installation and configuration for a power drive system** assists design and installation personnel when trying to ensure compliance with the requirements of the EMC Directive in the user's systems and installations when using AC drives.

4. **Guide to variable speed drives** describes basics of different variable speed drives (VSD) and how they are used in industrial processes.

5. **Bearing currents in modern AC drive systems** explains how to avoid damages.

6. **Guide to harmonics with AC drives** describes harmonic distortion, its sources and effect, and also distortion calculation and evaluation with special attention to the methods for reducing harmonics with AC drives.

7. **Dimensioning of a drive system**. Making dimensioning correctly is the fastest way of saving money. Biggest savings can be achieved by avoiding very basic mistakes. These dimensioning basics and beyond can be found in this guide.

8. **Electrical braking** describes the practical solutions available in reducing stored energy and transferring stored energy back into electrical energy.

9. **Guide to motion control drives** gives an overview of high performance drives and motion control.

10. **Functional safety** guide introduces the Machinery Directive and the standards that must be taken into account when designing a machine, in order to ensure operational safely.

ABB drives

Technical guide No. 1
Direct torque control - the world’s most advanced AC drive technology

Power and productivity
for a better world™

Chapter 1 - Introduction

General

Direct torque control - or DTC - is the most advanced AC drive technology developed by any manufacturer in the world.

This technical guide's purpose

The purpose of this technical guide is to explain what DTC is; why and how it has evolved; the basic theory behind its success; and the features and benefits of this new technology.

While trying to be as practical as possible, this guide does require a basic understanding of AC motor control principles.

It is aimed at decision makers including designers, specifiers, purchasing managers, OEMs and end-users; in all markets such as the water, chemical, pulp and paper, power generation, material handling, air conditioning and other industries.

In fact, anyone using variable speed drives (VSD) and who would like to benefit from VSD technology will find this technical guide essential reading.

Using this guide

This guide has been designed to give a logical build up as to why and how DTC was developed.

Readers wanting to know the evolution of drives from early DC techniques through AC to DTC should start at chapter 2 (page 8).

For those readers wanting answers about DTC's performance, operation and application potential, please go straight to chapter 3 (page 17) Questions and answers.

For an understanding of DTC's basic control theory, turn to page 28.

Chapter 2 - Evolution of direct torque control

What is a variable speed drive?

To understand the answer to this question we have to understand that the basic function of a variable speed drive (VSD) is to control the flow of energy from the mains to the process.

Energy is supplied to the process through the motor shaft. Two physical quantities describe the state of the shaft: torque and speed. To control the flow of energy we must therefore, ultimately, control these quantities.

In practice, either one of them is controlled and we speak of "torque control" or "speed control". When the VSD operates in torque control mode, the speed is determined by the load. Likewise, when operated in speed control, the torque is determined by the load.

Initially, DC motors were used as VSDs because they could easily achieve the required speed and torque without the need for sophisticated electronics.

However, the evolution of AC variable speed drive technology has been driven partly by the desire to emulate the excellent performance of the DC motor, such as fast torque response and speed accuracy, while using rugged, inexpensive and maintenance free AC motors.

Summary

In this section we look at the evolution of DTC, charting the four milestones of variable speed drives, namely:

– DC motor drives 9
– AC drives, frequency control, PWM 11
– AC drives, flux vector control, PWM 12
– AC drives, direct torque control 14

We examine each in turn, leading to a total picture that identifies the key differences between each.

DC motor drives



Figure 1: Control loop of a DC motor drive

Features

- Field orientation via mechanical commutator
- Controlling variables are armature current and field current, measured DIRECTLY from the motor
- Torque control is direct

In a DC motor, the magnetic field is created by the current through the field winding in the stator. This field is always at right angles to the field created by the armature winding. This condition, known as field orientation, is needed to generate maximum torque. The commutator-brush assembly ensures this condition is maintained regardless of the rotor position.

Once field orientation is achieved, the DC motor's torque is easily controlled by varying the armature current and by keeping the magnetising current constant.

The advantage of DC drives is that speed and torque - the two main concerns of the end-user - are controlled directly through armature current: that is the torque is the inner control loop and the speed is the outer control loop (see Figure 1).

Advantages

- Accurate and fast torque control
- High dynamic speed response
- Simple to control

Initially, DC drives were used for variable speed control because they could easily achieve a good torque and speed response with high accuracy.

A DC machine is able to produce a torque that is:

- **Direct** - the motor torque is proportional to the armture current: the torque can thus be controlled directly and accurately.
- **Rapid** - torque control is fast; the drive system can have a very high dynamic speed response. Torque can be changed instantaneously if the motor is fed from an ideal current source. A voltage fed drive still has a fast response, since this is determined only by the rotor's electrical time constant (ie, the total inductance and resistance in the armature circuit)
- **Simple** - field orientation is achieved using a simple mechanical device called a commutator/brush assembly. Hence, there is no need for complex electronic control circuitry, which would increase the cost of the motor controller.

Drawbacks

- Reduced motor reliability
- Regular maintenance
- Motor costly to purchase
- Needs encoder for feedback

The main drawback of this technique is the reduced reliability of the DC motor; the fact that brushes and commutators wear down and need regular servicing; that DC motors can be costly to purchase; and that they require encoders for speed and position feedback.

While a DC drive produces an easily controlled torque from zero to base speed and beyond, the motor's mechanics are more complex and require regular maintenance.

AC drives - Introduction

- Small size
- Robust
- Simple in design
- Light and compact
- Low maintenance
- Low cost

The evolution of AC variable speed drive technology has been partly driven by the desire to emulate the performance of the DC drive, such as fast torque response and speed accuracy, while utilising the advantages offered by the standard AC motor.


Frequency control
Freq.
Ref.
V/f
ratio
V
f
Modu-
lator
M
3 ~

To emulate the magnetic operating conditions of a DC motor, ie, to perform the field orientation process, the flux-vector drive needs to know the spatial angular position of the rotor flux inside the AC induction motor.

With flux vector PWM drives, field orientation is achieved by electronic means rather than the mechanical commutator/brush assembly of the DC motor.

Firstly, information about the rotor status is obtained by feeding back rotor speed and angular position relative to the stator field by means of a pulse encoder. A drive that uses speed encoders is referred to as a "closed-loop drive".

Also the motor's electrical characteristics are mathematically modelled with microprocessors used to process the data.

The electronic controller of a flux-vector drive creates electrical quantities such as voltage, current and frequency, which are the controlling variables, and feeds these through a modulator to the AC induction motor. Torque, therefore, is controlled INDIRECTLY.

Advantages

- Good torque response
- Accurate speed control
- Full torque at zero speed
- Performance approaching DC drive

Flux vector control achieves full torque at zero speed, giving it a performance very close to that of a DC drive.

Drawbacks

- Feedback is needed
- Costly
- Modulator needed

To achieve a high level of torque response and speed accuracy, a feedback device is required. This can be costly and also adds complexity to the traditional simple AC induction motor.

Also, a modulator is used, which slows down communication between the incoming voltage and frequency signals and the need for the motor to respond to this changing signal.

Although the motor is mechanically simple, the drive is electrically complex.


Direct t
c


RIVE
CO
DC DRIVES
Ar
M
AC DRIVES (PWM)
Direct Torque Control

As can be seen from table 1, both DC drives and DTC drives use actual motor parameters to control torque and speed. Thus, the dynamic performance is fast and easy. Also with DTC, for most applications, no tachometer or encoder is needed to feed back a speed or position signal.

Comparing DTC (Figure 4) with the two other AC drive control blocks (Figures 2 & 3) shows up several differences, the main one being that no modulator is required with DTC.

With PWM AC drives, the controlling variables are frequency and voltage which need to go through several stages before being applied to the motor. Thus, with PWM drives control is handled inside the electronic controller and not inside the motor.

Chapter 3 - Questions and answers

General

What is direct control?

Direct torque control - or DTC as it is called - is the very latest AC drive technology developed by ABB and is set to replace traditional PWM drives of the open- and closed-loop type in the near future.

Why is it called direct torque control?

Direct torque control describes the way in which the control of torque and speed are directly based on the electromagnetic state of the motor, similar to a DC motor, but contrary to the way in which traditional PWM drives use input frequency and voltage. DTC is the first technology to control the “real” motor control variables of torque and flux.

What is the advantage of this?

Because torque and flux are motor parameters that are being directly controlled, there is no need for a modulator, as used in PWM drives, to control the frequency and voltage. This, in effect, cuts out the middle man and dramatically speeds up the response of the drive to changes in required torque. DTC also provides precise torque control without the need for a feedback device.

Why is there a need for another AC drive technology?

DTC is not just another AC drive technology. Industry is demanding more and existing drive technology cannot meet these demands.

For example, industry wants:

- Better product quality which can be partly achieved with improved speed accuracy and faster torque control.
- Less down time which means a drive that will not trip unnecessarily; a drive that is not complicated by expensive feedback devices; and a drive which is not greatly affected by interferences like harmonics and RFI.
- Fewer products. One drive capable of meeting all appliction needs whether AC, DC or servo. That is a truly “universal” drive.
- A comfortable working environment with a drive that produces much lower audible noise.

These are just some of the demands from industry. DTC can deliver solutions to all these demands as well as bringing new benefits to many standard applications.

Who invented DTC?

ABB has been carrying out research into DTC since 1988 following the publication of the theory in 1971 and 1985 by German doctor Blaschke and his colleague Depenbrock. DTC leans on the theory of field oriented control of induction machines and the theory of direct self control. ABB has spent over 100 man years developing the technology.

Performance

What are the main benefits of DTC technology over traditional AC drive technology?

There are many benefits of DTC technology. But most significantly, drives using DTC technology have the following exceptional dynamic performance features, many of which are obtained without the need for an encoder or tachometer to monitor shaft position or speed:

- **Torque response:** - How quickly the drive output can reach the specified value when a nominal 100 percent torque reference step is applied.
  For DTC, a typical torque response is **1 to 2 ms** below 40 Hz compared to between 10-20 ms for both flux vector and DC drives fitted with an encoder. With open loop PWM drives (see page 11) the response time is typically well over 100 ms. In fact, with its torque response, DTC has achieved the natural limit. With the voltage and current available, response time cannot be any shorter. Even in the newer “sensorless” drives the torque response is **hundreds of milliseconds.**

- Accurate **torque control at low frequencies**, as well as full load torque at zero speed without the need for a feedback device such as an encoder or tachometer. With DTC, speed can be controlled to frequencies below 0.5 Hz and still provide **100 percent torque** right the way through to zero speed.

- **Torque repeatability:** - How well the drive repeats its output torque with the same torque reference command. DTC, without an encoder, can provide 1 to 2 percent torque repeatability of the nominal torque across the speed range. This is half that of other open-loop AC drives and equal to that of closed-loop AC and DC drives.

– **Motor static speed accuracy:** - Error between speed reference and actual value at constant load. For DTC, speed accuracy is 10 percent of the motor slip, which with an 11 kW motor, equals 0.3 percent static speed accuracy. With a 110 kW motor, speed accuracy is 0.1 percent without encoder (open-loop). This satisfies the accuracy requirement or 95 percent of industrial drives applications. However, for the same accuracy from DC drives an encoder is needed.

  In contrast, with frequency controlled PWM drives, the static speed accuracy is typically between 1 to 3 percent. So the potential for customer process improvements is significantly higher with standard drives using DTC technology.

  A DTC drive using an encoder with 1024 pulses/revolution can achieve a speed accuracy of 0.01 percent.

– **Dynamic speed accuracy:** - Time integral of speed deviation when a nominal (100 percent) torque speed is applied. DTC open-loop dynamic speed accuracy is between 0.3 to 0.4%sec. This depends on the gain adjustment of the controller, which can be tuned to the process requirements.

  With other open-loop AC drives, the dynamic accuracy is eight times less and in practical terms around 3%sec.If we furnish the DTC controller with an encoder, the dynamicspeed accuracy will be 0.1%sec, which matches servo drive performance.

What are the practical benefits of these performance figures?

– **Fast torque response:** - This significantly reduces the speed drop time during a load transient, bringing much improved process control and a more consistent product quality.

– **Torque control at low frequencies: -** This is particularly-beneficial to cranes or elevators, where the load needs to be started and stopped regularly without any jerking. Also with a winder, tension control can be achieved from zero through to maximum speed. Compared to PWM flux vector drives, DTC brings the cost saving benefit that no tachometer is needed.

– **Torque linearity:** - This is important in precision applications like winders, used in the paper industry, where an accurate and consistent level of winding is critical.

– **Dynamic speed accuracy:** - After a sudden load change, the motor can recover to a stable state remarkably fast.

FEATURE	RESULT	BENEFIT
Good motor speed accuracy without tachometer.	Allows speed to be controlled better than 0.5 percent accuracy. No tachometer needed in 95 percent of all applications.	Investment cost savings. Increased reliability. Better process control. Higher product quality. Leads to a true universal drive.
Excellent torque control without tachometer.	Drive for demanding applications. Allows required torque at all times. Torque repeatability 1 percent. Torque response time less than 5ms.	Similar performance to DC but without tachometer. Reduced mechanical failures for machinery. Less downtime. Lower investment.
Full torque at zero speed with or without tachometer/encoder.	No mechanical brake needed. Smooth transition between drive and brake. Allows drive to be used in traditional DC drive applications.	Investment cost saving. Better load control. Can use AC drive and motor instead of DC. Standard AC motor means less maintenance and lower cost.
Control down to zero speed and position with encoder.	Servo drive performance.	Cost effective, high performance torque drive; provides position control and better static accuracy. High accuracy control with standard AC motor.

Table 2: Dynamic performance features and benefits offered by DTC technology

Apart from excellent dynamic performance figures, are there any other benefits of DTC drive technology?

Yes, there are many benefits. For example, DTC drives do not need a tachometer or encoder to monitor motor shaft speed or position in order to achieve the fastest torque response ever from an AC drive. This saves initial cost.

FEATURE	RESULT	BENEFIT
Rapid control DC link voltage.	Power loss ride through.	Drive will not trip. Less down time. Avoids process interruptions. Less waste in continuous process.
Automatic start (Direct restart).	Starting with motor residual inductance present. No restarting delay required.	Can start into a motor that is running without waiting for flux to decay. Can transfer motor from line to drive. No restart. No interruptions on process.
Automatic start (Flying start).	Synchronises to rotating motor.	No process interruptions. Smooth control of machinery. Resume control in all situations.
Flux braking.	Controlled braking between two speed points.	Investment cost savings. Better process control. No delay required as in DC braking. Can be used for decelerating to other than zero speed. Reduced need for brake chopper and resistor.
Flux optimization.	Motor losses minimised. Less motor noise.	Controlled motor.
Self identification/ Auto-tuning.	Tuning the motor to drive for top performance.	Easy and accurate set-up. No parameter tuning required. Less commissioning time. Guaranteed starting torque. Easy retrofit for any AC system.
No predetermined switching pattern of power devices.	Low noise. No fixed carrier, therefore acoustic noise reasonable due to “white” noise spectrum.	Cost savings in acoustic barriers in noise sensitive applications. No harmful mechanical resonances. Lower stresses in gearboxes, fans, pumps.
No limits on maximum acceleration and deceleration rate.	Can accelerate and decelerate in quickest time possible without mechanical constraints.	Better process control.

Table 3: User features and benefits offered by DTC technology

Also a DTC drive features rapid starting in all motor electromagnetic and mechanical states. The motor can be started immediately without delay.

It appears that DTC drives are most advantageous for high performance or demanding drive applications. What benefits does DTC bring to standard drives?

Standard applications account for 70 percent of all variable speed drives installed throughout industry. Two of the most common applications are in fans and pumps in industries like heating, ventilating and air conditioning (HVAC), water and food and drinks.

In these applications, DTC provides solutions to problems like harmonics and noise.

For example, DTC technology can provide control to the drive input line generating unit, where a conventional diode bridge is replaced with a controlled bridge.

This means that harmonics can be significantly reduced with a DTC controlled input bridge. The low level current distortion with a DTC controlled bridge will be less than a conventional 6-pulse or 12-pulse configuration and power factor can be as high as 0.99.

For standard applications, DTC drives easily withstand huge and sudden load torques caused by rapid changes in the process, without any overvoltage or overcurrent trip.

Also, if there is a loss of input power for a short time, the drive must remain energised. The DC link voltage must not drop below the lowest control level of 80 percent. To ensure this, DTC has a 25 microseconds control cycle.

What is the impact of DTC on pump control?

DTC has an impact on all types of pumps. Because DTC leads to a universal drive, all pumps, regardless of whether they are centrifugal or constant torque type (screw pumps) can now be controlled with one drive configuration, as can aerators and conveyors. DTC technology allows a drive to adjust itself to varying application needs.

For example, in screw pumps a drive using DTC technology will be able to adjust itself for sufficient starting torque for a guaranteed start.

Improved power loss ride through will improve pumping availability during short power breaks.

The inherent torque control facility for DTC technology allows the torque to be limited in order to avoid mechanical stress on pumps and pipelines.

What is the impact of DTC technology on energy savings?

A feature of DTC which contributes to energy efficiency is a development called motor flux optimization.

With this feature, the efficiency of the total drive (that is controller and motor) is greatly improved in fan and pump applications.

For example, with 25 percent load there is up to 10 percent total energy efficiency improvement. At 50 percent load there can be 2 percent total efficiency improvement.

This directly impacts on operating costs. This feature also significantly reduces the motor noise compared to that generated by the switching frequency of a traditional PWM drive.

Has DTC technology been used in many installations?

Yes, there are hundreds of thousands of installations in use. For example, one of the world's largest web machine manufacturers tested DTC technology for a winder in a film finishing process.

The Requirement:
Exact torque control in the winder so as to produce high quality film rolls.

The Solution:
Open-loop DTC drives have replaced traditional DC drives and latter flux vector controlled AC drives on the centre drives in the rewind station.

The Benefits:
Winder station construction simplified and reliability increased. The cost of one tachometer and associated wiring equals that of one 30 kW AC motor. This provides significant investment cost savings.

Operation

What is the difference between DTC and traditional PWM methods?

– **Frequency control PWM and flux vector PWM**

Traditional PWM drives use **output voltage** and **output frequency** as the primary control variables but these need to be pulse width modulated before being applied to the motor.

This modulator stage adds to the signal processing time and therefore limits the level of torque and speed response possible from the PWM drive.

Typically, a PWM modulator takes 10 times longer than DTC to respond to actual change.

– **DTC control**

DTC allows the motor's **torque** and **stator flux** to be used as primary control variables, both of which are obtained directly from the motor itself. Therefore, with DTC, there is no need for a separate voltage and frequency controlled PWM modulator. Another big advantage of a DTC drive is that no feedback device is needed for 95 percent of all drive applications.

Why does DTC not need a tachometer or position encoder to tell it precisely where the motor shaft is at all times?

There are four main reasons for this:

– The accuracy of the motor model (see page 29).
– Controlling variables are taken directly from the motor (see page 29).
– The fast processing speeds of the DSP and optimum pulse selector hardware (see page 30).
– No modulator is needed (see page 14).

When combined to form a DTC drive, the above features produce a drive capable of calculating the ideal switching voltages 40,000 times every second. It is fast enough to control individual switching pulses. Quite simply, it is the fastest ever achieved.

Once every 25 microseconds, the inverter's semiconductors are supplied with an optimum switching pattern to produce the required torque. This update rate is substantially less than any time constants in the motor. Thus, the motor is now the limiting component, not the inverter.

What is the difference between DTC and other sensorless drives on the market?

There are vast differences between DTC and many of the sensorless drives. But the main difference is that DTC provides accurate control even at low speeds and down to zero speed without encoder feedback. At low frequencies the nominal torque step can be increased in less than 1ms. This is the best available.

How does a DTC drive achieve the performance of a servo drive?

Quite simply because the motor is now the limit of performance and not the drive itself. A typical dynamic speed accuracy for a servo drive is 0.1%s. A DTC drive can reach this dynamic accuracy with the optional speed feedback from a tachometer.

How does DTC achieve these major improvements over traditional technology?

The most striking difference is the sheer speed by which DTC operates. As mentioned above, the torque response is the quickest available.

To achieve a fast torque loop, ABB has utilised the latest high speed signal processing technology and spent 100 man years developing the highly advanced motor model which precisely simulates the actual motor parameters within the controller.

For a clearer understanding of DTC control theory, see page 28.

Does a DTC drive use fuzzy logic within its control loop?

No. Fuzzy logic is used in some drives to maintain the acceleration current within current limits and therefore prevent the drive from tripping unnecessarily. As DTC is controlling the torque directly, current can be kept within these limits in all operating conditions.

A drive using DTC technology is said to be tripless. How has this been achieved?

Many manufacturers have spent years trying to avoid trips during acceleration and deceleration and have found it extraordinarily difficult. DTC achieves tripless operation by controlling the actual motor torque.

The speed and accuracy of a drive which relies on computed rather than measured control parameters can never be realistic. Unless you are looking at the shaft, you are not getting the full picture. Is this true with DTC?

DTC knows the full picture. As explained above, thanks to the sophistication of the motor model and the ability to carry out 40,000 calculations every second, a DTC drive knows precisely what the motor shaft is doing. There is never any doubt as to the motor's state. This is reflected in the exceptionally high torque response and speed accuracy figures quoted on pages 18 and 19.

Unlike traditional AC drives, where up to 30 percent of all switchings are wasted, a drive using DTC technology knows precisely where the shaft is and so does not waste any of its switchings.

DTC can cover 95 percent of all industrial applications. The exceptions, mainly applications where extremely precise speed control is needed, will be catered for by adding a feedback device to provide closed loop control. This device, however, can be simpler than the sensors needed for conventional closed loop drives.

Even with the fastest semiconductors some dead time is introduced. Therefore, how accurate is the auto-tuning of a DTC drive?

Auto-tuning is used in the initial identification run of a DTC drive (see page 29). The dead time is measured and is taken into account by the motor model when calculating the actual flux. If we compare to a PWM drive, the problem with PWM is in the range 20 to 30 Hz which causes torque ripple.

What kind of stability will a DTC drive have at light loads and low speeds?

The stability down to zero speed is good and both torque and speed accuracy can be maintained at very low speeds and light loads. We have defined the accuracies as follows:

Torque accuracy: Within a speed range of 2 to 100 percent and a load range of 10 to100 percent, the torque accuracy is 2 percent.

Speed accuracy: Within a speed range of 2 to 100 percent and a load range of 10 to 100 percent, the speed accuracy is 10 percent of the motor slip. Motor slip of a 37 kW motor is about 2 percent which means a speed accuracy of 0.2 percent.

What are the limitations of DTC?

If several motors are connected in parallel in a DTC-controlled inverter, the arrangement operates as one large motor. It has no information about the status of any single motor. If the number of motors varies or the motor power remains below 1/8 of the rated power, it would be best to select the scalar control macro.

Can DTC work with any type of induction motor?

Yes, any type of asynchronous, squirrel cage motor.

Chapter 4 - Basic control theory

How DTC works

Figure 5, below, shows the complete block diagram for direct torque control (DTC).

Walk around the block



Figure 5: DTC comprises two key blocks: Speed control and torque control

The block diagram shows that DTC has two fundamental sections: the torque control loop and the speed control loop. Now we will walk around the blocks exploring each stage and showing how they integrate together.

Let's start with DTC's torque control loop.

Torque control loop



Step 1 Voltage and current measurements

In normal operation, two motor phase currents and the DC bus voltage are simply measured, together with the inverter's switch positions.

Step 2 Adaptive motor model

The measured information from the motor is fed to the Adaptive motor model.

The sophistication of this motor model allows precise data about the motor to be calculated. Before operating the DTC drive, the motor model is fed information about the motor, which is collected during a motor identification run. This is called **auto-tuning** and data such as stator resistance, mutual inductance and saturation coefficients are determined along with the motor's inertia. The identification of motor model parameters can be done without rotating motor shaft. This makes it easy to apply DTC technology also in retrofits. The extremely fine tuning of motor model is achieved when the identification run also includes running the motor shaft for some seconds.

There is no need to feed back any shaft speed or position with tachometers or encoders if the static speed accuracy requirement is over 0.5 percent, as it is for most industrial applications.

This is a significant advance over all other AC drive technology. The motor model is, in fact, key to DTC's unrivalled low speed performance.

The motor model outputs control signals which directly represent actual motor torque and actual stator flux. Also shaft speed is calculated within the motor model.

Step 3 Torque comparator and flux comparator

The information to control power switches is produced in the torque and flux comparator.

Both actual torque and actual flux are fed to the comparators where they are compared, every 25 microseconds, to a torque and flux reference value. Torque and flux status signals are calculated using a two level hysteresis control method.

These signals are then fed to the optimum pulse selector.

Step 4 Optimum pulse selector

Within the optimum pulse selector is the latest 40 MHz digital signal processor (DSP) together with ASIC hardware to determine the switching logic of the inverter. Furthermore, all control signals are transmitted via optical links for high speed data transmission.

This configuration brings immense processing speed such that every 25 microseconds the inverter's semiconductor switching devices are supplied with an optimum pulse for reaching, or maintaining, an accurate motor torque.

The correct switch combination is determined every control cycle. There is no predetermined switching pattern. DTC has been referred to as "just-in-time" switching, because, unlike traditional PWM drives where up to 30 percent of all switch changes are unnecessary, with DTC each and every switching is needed and used.

This high speed of switching is fundamental to the success of DTC. The main motor control parameters are updated 40,000 times a second. This allows extremely rapid response on the shaft and is necessary so that the motor model (see step 2) can update this information.

It is this processing speed that brings the high performance figures including a static speed control accuracy, without encoder, of ±0.5 percent and the torque response of less than 2 ms.

Chapter 5 - Index

A
acceleration compensator 31
accuracy control 20
AC drive 1, 3, 7, 11, 12, 14, 15, 16, 17, 18, 19, 20, 23, 26, 30
AC drive using DTC 14, 15
AC drive with flux vector control 12
AC motor 20
aerators 22
air condition 22
ASIC 30
auto-tuning 21, 26, 29

B
Blaschke 18
braking 21, 31

C
closed-loop 12, 18
closed-loop drives 12
commissioning 21
control cycle 30
controlled input bridge 22
controlling variables 16
control loop 9, 11, 12, 14, 15, 26, 28, 29, 31
control variables 15, 24
conveyors 22
costs 20, 21, 23

D
DC bus voltage 29, 31
DC drive 9, 12, 15, 16, 20
DC link voltage 21, 22
DC motor 9
Depenbrock 18
diode bridge 22
direct torque control 8, 9, 10, 11, 12, 13, 14, 15, 16, 28
drive input line generating unit 22
DSP 24, 30
DTC 14, 15, 16, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30
dynamic speed accuracy 19, 25

E
electronic controller 16
elevators 19
encoders 16, 20, 24, 25, 29, 30
energy savings 23
external speed reference 31
external torque signal 31

F
fan 21, 22, 23
feedback device 18, 24, 26
field oriented control 18
film finishing 23
flux braking 21, 31
flux comparator 30, 31
flux optimization 21, 23, 31
flux reference controller 31
flux vector 12, 15, 18, 23, 24
flux vector control 12, 15
food 22
frequency control 11, 15, 24
fuzzy logic 26

G
gearbox 21

H
harmonics 22
heating 22
HVAC 22
hysteresis control 30

I
inertia 29
initial cost 20

L
load torque 18, 22
loss of input power 22
low frequencies 18, 19, 25

M
maintenance 20
mechanical brake 20
modulator 16, 24
motor flux optimization 23
motor model 12, 24, 25, 26, 29, 30, 31
motor noise 21, 23
motor static speed 19
motor torque 30
mutual inductance 29

N
noise 21, 22, 23
nominal torque step 25

O
operating cost 23
optical link 30
optimum pulse selector 30
output frequency 24
output voltage 24

P
paper industry 19
PID controller 31
pipelines 23
position control 20
position encoder 24
power factor 22
power loss ride through 21, 23

predetermined switching pattern 21, 30
pump 21, 22, 23
PWM 11, 12, 16, 18, 19, 23, 24, 26, 30
PWM AC drive 16, 23, 24, 26, 30

R
reliability 20
restart 21
retrofit 21

S
saturation coefficient 29
scalar control 27
sensorless 25
servo drive 20, 25
signal processing 24, 25
signal processing time 24
speed 8, 15, 16, 18, 19, 20, 21, 22, 24, 25, 26, 27, 28, 29, 30, 31
speed accuracy 19, 20, 25, 26, 27, 29
speed control 26, 28, 30, 31
speed controller 31
speed control loop 28
speed control output 31
speed response 24
stability 27
start 21, 22, 28
starting 21, 22
static accuracy 20
static speed accuracy 19, 29
stator 24, 29, 30, 31
stator flux 24, 30, 31
stator resistance 29
stress 21, 23
switching pattern 21, 25, 30
switching pulses 25

T
tacho 16, 20, 24, 29
tachometer 16, 18, 19, 20, 23, 24, 25, 29
time constant 25
torque 9, 10, 11, 12, 13, 14, 15, 16, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 30, 31
- control 9, 12, 14, 20, 23, 28
- loop 25
- repeatability 20
- response 20, 25, 26, 30
- ripple 26

torque and flux comparator 30
torque comparator 30, 31
torque control loop 28
torque reference controller 31
trip 21, 22, 26

U
universal 20, 22

V
variable speed drives 15, 22
ventilating 22
voltage 16, 18, 21, 22, 24, 25, 29, 31

W
water 22
web machine 23
winder 19, 23

Z
zero speed 18, 20, 21, 25, 27

Contact us

For more information contact
your local ABB representative or visit:

www.abb.com/drives
www.abb.com/drivespartners

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.

3AFE58056685 REV C EN 6.6.2011 #15700

Power and productivity
for a better world™



ABB drives

Technical guide No. 2
EU Council Directives and adjustable speed electrical power drive systems

Power and productivity
for a better world™

Technical guide No. 2
EU Council Directives and adjustable speed electrical power drive systems

2

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AFE61253980 REV D 29.4.2011

Contents

Chapter 1 - Introduction 9

This guide's purpose.....9
How to use this guide.....10
Responsibilities and actions 10
Tickboxes.....10
Cross-referencing 10

Chapter 2 - General questions and answers.....11

What are these EU Council Directives? 11
How does EMC affect me? 11
What is EMC? 11
What is an electromagnetic environment?.....12
How does electromagnetic interference show up? 12
What emissions can drives cause?.....12
How is this emission seen?.....13
How do I avoid electromagnetic interference?.....13
Drives manufacturers must comply with EMC standards then? 13
If a drive is CE marked, I need not worry. True?.....13

Chapter 3 - CE marking 15

What is CE marking and how relevant is it for drives?.....15
What is CE marking for?.....15
Is CE marking a quality mark? 16
What is the legal position regarding CE marking? 16
What is the importance of CE marking for purchasers of drives? 16
If I buy a CE marked drive, will I meet the technical requirements of the directives? 16
What happens if, as an end-user, I put together a system - do I have to put CE marking on? 17
What about spare parts that I buy for a drive? Do I negate the CE mark if I replace a component? 17
If drives are classed as components, on subassemlies they cannot be EMC certified or carry a CE mark. Is this true? 17
In summary 18
Components or subassemblies intended for incorporation into an apparatus by the end users.....18
Components or subassemblies intended for incorporation into an apparatus by the other manufacturer or assembler.....18
Finished appliance 19
Finished appliance intended for the end users.....19
Finished appliance intended for the other manufacturer or assembler 19
Systems (Combination of finished appliances) 19

All provisions of the EMC Directive, as defined for apparatus, apply to the combination as a whole....20
Apparatus....20
Fixed installation....20
Equipment....20

Chapter 4 - Purchasing decisionsfor PDSs....21

What you need to know and do....21
If you are a machine builder buying a PDS....25
Actions you must take....26
When buying a PDS....28
Path 1....29
Actions you must take....29
Path 2....30
Actions you must take....30
Path 3....30
Actions you must take....31
If you are an end-user buying a CDM/BDM or PDS....31
...You have the following responsibilities....31
Actions you must take....32
If you are a panel builder buying a CDM/BDM....32
Additional actions....34
If you are a distributor buying a CDM/BDM....35
If you are an installer buying a CDM/BDM or PDS....35

Chapter 5 - Terminology....36

Technical documentation (TD)....36
What is technical documentation?....36
Why is technical documentation deemed to be important?....36
Will customers always receive a copy of technical documentation? 37
What is the shelf life of technical documentation?....37
How do I ensure that tests are always carried out?....37
Can drive manufacturers help more?....37
How to make up a TD....38
1. Description of the product....38
2. Procedures used to ensure product conformity....38
3. If chosen a statement from notified body....39
4. Actions by the notified body....39
Technical file (for mechanical safety aspects)....40
What is a technical file?....40
How to make up a technical file....40
Drawings and diagrams....40
Health and safety....40
Machine design....40
Other certificates required....40
Certificate of Adequacy....41
What if standards cannot be wholly implemented?....41
How to obtain a Certificate of Adequacy....41

Statement 41
When the statement is needed 41
How to obtain a report 42
Declaration of conformity (for EMC and electrical safety aspects) ... 43
How to obtain a Declaration of conformity 43
What is a Declaration of incorporation? 44
Is there no way out of this type of declaration? 45
What a Declaration of incorporation contains 45
Type certification 46
How to obtain type certification 46

Chapter 6 - Authorities and bodies 47

Competent authority 47
Notified body 47

Chapter 7 - Standards and directives 48

Directive or standard? 48
Harmonised standards for PDSs 48
How to recognise a European standard 49
Your questions answered 50
Which standards directly relate to drives? 50
What are the issues of EN 61800-3 and drives? 50
What are the solutions to radiated emissions? 51
Do I have to conform to the standards? 51
Can I be fined for not conforming? 51
The Product Specific Standard EN 61800-3 51
PDS of category C1: 52
PDS of category C2: 52
PDS of category C3: 53
PDS of category C4: 53
Examples concerning applications of different approaches 54
Machinery Directive 98/37/EC 55
How does the Machinery Directive affect my drive? 55
Where can I obtain a Machinery Directive copy? 56
Low Voltage Directive 56
How does the LVD affect my drive? 56
Why is the Declaration of conformity important? 57
EMC Directive 57
How does the EMC Directive affect my drive? 57
Who has the responsibility to ensure CE marking? 58
Summary of responsibilities 59
Achieving conformity with EC Safety Directives 60

Index 61

2

Chapter 1 - Introduction

This guide's purpose

The aim of this Technical guide No. 2* is to give a straight-forward explanation of how the various EU Council Directives relate to power drive systems (PDSs). For an explanation of the terminology of PDSs, see pages 21 and 22.

While Electromagnetic Compatibility (EMC) is the subject of most concern within the industry, it must be realised that the EMC Directive is only part of the overall EU initiative on common safety standards.

It is the intention of this guide to offer users of AC or DC power drive systems - whether machine builders, system designers, distributors, OEMs, end-users or installers - some clear practical guidelines and courses of action.

***Notes**

1 The content of this technical guide is ABB Oy's, Drives interpretation of events as of July 2007. However, we reserve the right to develop and evolve these interpretations as more details become available from notified bodies (see chapter 6), competent authorities (see chapter 6), organisations and from our own tests.

2 Other technical guides available in this series include:

Technical guide No. 1 -
Direct torque control (3AFE58056685)

Technical guide No. 3 -
EMC compliant installation and configuration for a power drive system (3AFE61348280)

Technical guide No. 4 -
Guide to variable speed drives (3AFE61389211)

Technical guide No. 5 -
Bearing currents in modern AC drive systems (3AFE64230247)

Technical guide No. 6 -
Guide to harmonics with AC drives (3AFE64292714)

Technical guide No. 7 -
Dimensioning of a drive system (3AFE64362569)

Technical guide No. 8 -
Electrical braking (3AFE64362534)

Technical guide No. 9 -
Guide to motion control drives (3AFE68695201)

Technical guide No. 10 -
Functional safety (3AUA0000048753)

How to use this guide

The guide is divided into 7 sections.

Section 4 looks at purchasing decisions for PDSs. Please note the following about the structure of this section:

Responsibilities and actions

Each type of purchaser is offered an explanation of their responsibilities. This is for awareness. No action is needed.

Following the responsibilities is a set of actions. If the purchaser follows these actions, step-by-step, then conforming to the relevant directives will be straightforward.

Tickboxes

Alongside the actions are tickboxes. Purchasers can photocopy the relevant pages and use them as a checklist with each item being ticked off as it is achieved.

Cross-referencing

Because of the complexity of conforming to each directive, this guide inevitably carries a lot of cross-references to other sections. In the margin you will come across:

Defined on page XX

You are advised to turn to the page number reference.

You will also notice other references within the text. These can be referred to if the item is unclear but is not essential for achieving compliance.

Key point:

Within the text you will see:

Key point

These are key observations that must be observed.

Chapter 2 - General questions and answers

It is very important that users of PDSs fully understand all the various rules and regulations and how they apply to PDSs. That is the purpose of this guide.

What are these EU Council Directives?

It is important to realise that EMC cannot be divorced from other European legislation. So before answering this question, we need to look at the **other** legislation and how it affects the purchase and installation of drives.

Quite simply there are **three directives** that mainly affect a drive's safety against risks and hazards. These are:

Directive	Mandatory	Page
Machinery Directive	**1995-01-01**	**pg 55**
Low Voltage Directive	**1997-01-01**	**pg 56**
EMC Directive	**1996-01-01**	**pg 57**

But more on each of these directives later. Let us first explain EMC and look at some concerns of the industry.

How does EMC affect me?

From January 1, 1996 the EU Council's Electromagnetic Compatibility Directive (89/336/EEC and it's successor 2004/108/EC) has been compulsory. It applies to all electrical and electronic equipment sold within the EU and affects virtually all manufacturers and importers of electrical and electronic goods.

Key point:

Electrical equipment that does not conform to the regulations may not be sold anywhere in the EEA (European Economic Area).

What is EMC?

EMC stands for **E**lectro**m**agnetic **C**ompatibility. It is the ability of electrical/electronic equipment to operate problem-free within an electromagnetic environment. Likewise, the equipment must not disturb or interfere with any other products or systems within its locality.

What is an electromagnetic environment?

The electromagnetic environment is everywhere but it varies from place to place. The reason is that there are many different sources of disturbance which can be natural or man-made.

Natural sources consist of electrical discharge between clouds, lightning or other atmospheric disturbances. While we cannot influence these sources we can protect our products and systems from their effects.

Man-made disturbances are those generated by, for example, electrical contacts and semiconductors, digital systems like microprocessors, mobile radio transmitters, walkie-talkies, portable car telephones and power drive systems.

Such a variety of equipment, each with its own emission characteristics, is often used so near to other electrical equipment that the field strengths they create may cause interferences.

Key point:

It is important that all PDSs are immune to these natural and man-made disturbances. While drives manufacturers strive to make their products immune, the directive lays down minimum standards for immunity, thereby ensuring all manufacturers achieve the same basic level.

How does electromagnetic interference show up?

Electromagnetic interference shows up in a variety of ways. Typical examples of interference include a poorly suppressed automobile engine or dynamo; an electric drill causing patterning on the TV screen; or crackling from an AM radio.

The microprocessor and power electronic component, switch rapidly and therefore, can cause interference at high frequencies, unless proper precautions are taken.

What emissions can drives cause?

The normal operation of any drive involves rapid switching of high voltages and this can produce radio frequency emission. It is this radiation and emission that have been seen to have the potential to disturb other circuits at frequencies below 200 MHz.

Modern equipment contains considerable communications and other digital electronics. This can cause considerable emissions at frequencies above 200 MHz.

How is this emission seen?

The main emission is via conduction to the mains. Radiation from the converter and conducting cables is another type of emission and it is especially demanding to achieve the radiated emission limits.

How do I avoid electromagnetic interference?

You need to ensure two things:

- that the equipment generates minimum emission.
- that the equipment is immune to outside effects.

Key point:

In the case of power drive systems, a lot hinges on the quality of the installation.

Electromagnetic interference needs to be conducted to earth (ground potential) and no system can work unless it is properly connected.

Drives manufacturers must comply with EMC standards then?

Unfortunately, the process is not that simple. Virtually everyone in the supply chain has a responsibility to ensure a product, a system and an installation complies with the essential requirements of the EMC Directive.

The key is to clearly understand who has responsibility for what. In the forthcoming pages we take a look at various types of purchasers and examine the steps each should take to meet all three directives mentioned on page 11.

Everyone from manufacturer to installer to user has a responsibility in complying with EMC rules.

If a drive is CE marked, I need not worry. True?

Again this is a big misconception. Just because a drive has CE marking does not necessarily mean it meets the EMC Directive.

Key point:

This will all become clear by referring to the section **purchasing decisions for PDSs**, page 21.

CE marking according to the EMC Directive cannot normally be applied to a module that is no more than a chassis with exposed terminals.

Chapter 3 - CE marking

What is CE marking and how relevant is it for drives?

CE marking, shown below, is the official signature of the **Declaration of conformity** (see pages 43 and 44) as governed by the European Commission. It is a very specific graphic symbol and must be separated from other marks.

CE marking is a system of self certification to identify equipment that complies with the relevant applicable directives.

If a drive is the subject of several directives and, for example, conforms with the **Low Voltage Directive** (see page 56), then, from 1997, it is compulsory that it shows **CE marking**. That marking shall indicate that the drive also conforms to the **EMC Directive** (page 57). CE marking shall indicate conformity only to the directive(s) applied by the manufacturer.

Key point:

NOTE: There must be technical documentation supporting the **Declaration of conformity**.
For more on **technical documentation**, please refer to pages from 36 to 40.

What is CE marking for?

CE marking is mainly for the benefit of authorities throughout the EU and EEA countries who control the movement of goods. CE marking shows that the product complies with the essential requirements of all relevant directives, mainly in the area of technical safety, compatibility issues and conformity assessment. There are three directives that are relevant to drives, but CE marking may be attached to indicate compliance with one of them only (see the previous page).

Is CE marking a quality mark?

Most definitely not. As CE marking is self certification, you can be assured that certification has been carried out.

What is the legal position regarding CE marking?

Anyone applying CE marking is legally liable and must be able to prove the validity of his actions to the authorities. CE marking confirms compliance with the directives listed in the Declaration of conformity (see pages 43 and 44).

What is the importance of CE marking for purchasers of drives?

As far as a purchaser of a drive is concerned, anything that carries the CE mark must have a functional value to him.

Thus, a complete drive product, which can be safely cabled and powered up on its own, shall carry the CE marking.

If I buy a CE marked drive, will I meet the technical requirements of the directives?

In practice, you will see drive products with CE marking. But it is important to understand just why the product was given CE marking in the first place.

Basically a drive has no functional value. It is only of practical use when connected to, say, a motor which in turn is connected to a load.

Therefore, as far as the Machinery Directive is concerned a drive cannot have CE marking unless it is part of a “process” comprising the drive, motor and load.

As for the EMC Directive, the equipment that make up a “process” include cabling, drives and motor. CE marking can only be affixed if all items forming such a “process” conform to the requirements of the directive. Therefore, the drive manuals include detailed instructions for installation.

However, in the eyes of the Low Voltage Directive, a built drive does have functionality. That is, through the drive’s parameters you can program the drive and obtain an input and output signal. Thus, if a drive conforms to the Low Voltage Directive it can carry CE marking. Refer to pages from 58 to 60 for explanations of the three directives.

What happens if, as an end-user, I put together a system - do I have to put CE marking on?

Yes. Anyone putting together a system and commissioning it is responsible for the appropriate CE marking.

Key point:

Turn to page 31 for more details about the end-user's responsibilities.

What about spare parts that I buy for a drive? Do I negate the CE mark if I replace a component?

Equipment supplied before the application of the directives, can be repaired and supplied with spare parts to bring it back to the original specification. However, it cannot be enhanced or reinstalled without meeting the directives.

For equipment supplied after the application of the directives, the use of the manufacturer's spare parts should not negate the CE marking. However, the manufacturer or supplier should be consulted about upgrading, as some actions could affect the CE marking criteria.

If drives are classed as components, on subassemlies they cannot be EMC certified or carry a CE mark. Is this true?

You need to first understand the terminology now being applied to drives. See below and pages 21 and 22 for this.

A complete drive module (CDM) is normally a component in a system and as such has no functional value unless it is connected to the motor when it becomes a PDS.

The CDM shall be CE marked if it is to be installed with simple connections and adjustments that do not require any EMC-knowledge.

If awareness of the EMC implication is needed in order to install a CDM, it is not considered as an apparatus. Thus, it shall not be CE marked according to the EMC directives.

If a CDM or BDM is intended for incorporation in PDS by professional manufacturers only (panel builders, machine builders), it shall not be CE marked, nor is Declaration of conformity given by the CDM/BDM manufacturer. Instead installation instructions shall be supplied in order to help the professional manufacturers.

In summary

The EMC Directive defines equipment as any apparatus or fixed installation. As there are separate provisions for apparatus and fixed installations, it is important that the correct category of the equipment is determined.

In technical-commercial classifications the following terminology is frequently used: components, sub-assemblies, finished appliances (ie, finished products), a combination of finished appliances (ie, a system), apparatus, fixed installations and equipment.

The key issue here is whether the item to be considered is for end users or not:
- If it meant for end users, the EMC directive applies
- If it meant for manufacturers or assemblers, the EMC directive does not apply

Components or subassemblies intended for incorporation into an apparatus by the end users

A manufacturer may place components or sub-assemblies on the market which are:
- For incorporation into an apparatus by the end-user,
- Available to end users and likely to be used by them.

These components or sub-assemblies are to be considered as apparatus with regard to the application of the EMC. The instructions for use accompanying the component or sub-assembly should include all relevant information, and should assume that adjustments or connections can be performed by an end-user not aware of the EMC implications.

In such case the component is considered equivalent to apparatus. Some variable speed power drive products fall into this category, eg, a drive with enclosure and sold as a complete unit (CDM) to the enduser who installs it into his own system. All provisions of the EMC Directive will apply (CE mark, Declaration of conformity and technical documentation).

Components or subassemblies intended for incorporation into an apparatus by the other manufacturer or assembler

Components or sub-assemblies intended for incorporation into an apparatus or an other sub-assembly by other manufacturers or assemblers are not considered to be “apparatus” and are therefore not covered by the EMC Directive. These components include resistors, cables, terminal blocks, etc.

Some variable speed power drive products fall into this category as well, eg, basic drive module (BDM). These are meant to be assembled by a professional assembler (eg, panel builder or system manufacturer) into a cabinet not in the scope of delivery of the manufacturer of the BDM. According to the EMC Directive, the requirement for the BDM supplier is to provide instructions for installation and use.

Note:
The manufacturer or assembler of the panel or system is responsible for CE mark, Declaration of conformity and technical documentation.

Finished appliance

A finished appliance is any device or unit containing electrical and/or electronic components or sub-assemblies that delivers a function and has its own enclosure. Similarly than components, the interpretation finished appliance can be divided into two categories: it can be intended for the end users, or for the other manufacturers or assemblers.

Finished appliance intended for the end users

A finished appliance is considered as apparatus in the sense of the EMC Directive, if it is intended for the end-user and thus has to fulfill all the applicable provisions of the Directive.

Finished appliance intended for the other manufacturer or assembler

When the finished appliance is intended exclusively for an industrial assembly operation for incorporation into other apparatus, it is not an apparatus in the sense of the EMC Directive and consequently the EMC Directive does not apply for such finished appliances.

Systems (Combination of finished appliances)

A combination of several finished appliances which is combined, and/or designed and/or put together by the same person (ie, the system manufacturer) and is intended to be placed on the market for distribution as a single functional unit for an end-user and intended to be installed and operated together to perform a specific task.

All provisions of the EMC Directive, as defined for apparatus, apply to the combination as a whole.

Apparatus

Apparatus means any finished appliance or combination thereof made commercially available (ie, placed on the market) as a single functional unit, intended for the end-user, and liable to generate electromagnetic disturbance, or the performance of which is liable to be affected by such disturbance.

Fixed installation

A particular combination of several types of apparatus, equipment and/or components, which are assembled, installed and intended to be used permanently at a predefined location.

Equipment

Any apparatus or fixed installation

Chapter 4 - Purchasing decisions for PDSs

What you need to know and do

Starting on page 23, we offer a step-by-step guide relating to your purchasing requirements for power drive systems.

Key point:

Before turning to page 23, you **need to know** the following terms for PDSs and their component parts, which may be unfamiliar to many users.

TERMS THAT YOU MUST KNOW

1. Basic drive module (BDM) consists of the converter section and the control circuits needed for torque or speed. A BDM is the essential part of the power drive system taking electrical power from a 50 Hz constant frequency supply and converting it into a variable form for an electric motor.

2. Complete drive module (CDM) consists of the drive system without the motor and the sensors mechanically coupled to the motor shaft. The CDM also includes the Basic Drive Module (BDM) and a feeder section. Devices such as an incoming phase-shift transformer for a 12-pulse drive are considered part of the CDM.

3. Power drive system, or PDS, is a term used throughout this technical guide. A PDS includes the frequency converter and feeding section (the CDM and BDM), motors, sensors, all cabling, filters, panels and any other components needed to make the PDS work effectively.

Note: The load is not considered part of the PDS, but the CDM can incorporate the supply sections and ventilation.



Now we strongly advise you turn to page 23, to discover the type of person you are.

To make this technical guide easy to use, we have also identified certain types of people who will be involved in the purchasing of drives.

Please identify the type nearest to your job function and turn to the relevant section

WHO ARE YOU?

	IF THIS IS YOU, TURN NOW TO PAGE...
Machine builder is a person who buys either a PDS, CDM or BDM and other mechanical or electrical component parts, such as a pump, and assembles these into a machine. **Note:** A machine is defined as an assembly of linked parts or components, at least one of which moves. It includes the appropriate actuators, control and power circuits joined together for a specific application, in particular for processing, treatment, moving or packaging of a material.	**25**
System designer carries out all the electrical design of the power drive system, specifying all component parts which comprise a PDS.	**28**
End-user is the final customer who will actually use the machine, PDS or CDM/BDM.	**31**
Panel builder constructs enclosures into which a panel builder will install a variety of components, including a CDM/BDM and sometimes the motor. However, the built enclosure does not constitute a machine.	**32**

WHO ARE YOU?	IF THIS IS YOU, TURN NOW TO PAGE...
Distributor acts as the sales distribution channel between the CDM/ BDM manufacturer and the end-user, machine builder, OEM, panel builder or system designer.	35
Installer carries out the entire electrical installation of the PDS.	35
Original equipment manufacturer (OEM) For the purposes of purchasing drives, an OEM will normally fall into the category of a machine builder, system designer or panel builder. Therefore, if you identify yourself as an OEM, refer to the relevant pages for each of these job functions.	25 28 32



NOTE: Before reading this section we strongly urge you to familiarise yourself with the terms explained on pages 21-24.

If you are a machine builder buying a PDS...

...You have the following responsibilities:

1. Because you are building a complete machine, which includes coupling up the motors to the PDS and providing the mechanical guarding and so on, you are liable for the total mechanical and electrical safety of the machine as specified in the **Machinery Directive**.

   Therefore, the PDS is ultimately your responsibility. You need to ensure that the entire PDS meets the **Machinery Directive**. Only then can **CE marking** be applied to the whole machine.

2. You are also responsible for the electrical safety of all parts of the PDS as specified in the **Low Voltage Directive**.

3. You must ensure electrical equipment and components are manufactured in accordance with the **EMC Directive**. The manufacturer of these parts is responsible for EMC for that particular part. Nevertheless you are responsible for EMC for the machine. You may choose electrical parts not in accordance with the EMC directive, but then you have the responsibility for compliance of parts.

   Note: Be aware that combining CE marked sub-assemblies may not automatically produce an apparatus that meets the requirements.

4. You must ensure that the PDS or its component parts carry **declarations of conformity** in accordance with the electrical safety requirements of the **Low Voltage Directive**.

5. You must be able to assure an **authority** and customers that the machine has been built according to the **Machinery Directive**, the **Low Voltage Directive** and the **EMC Directive**. It may be necessary to issue technical documentation to demonstrate compliance. You must keep in mind that you and only you have responsibility for compliance with directives.

6. A **Declaration of conformity** according to the directives above must be issued by the **machine builder** and **CE marking** must then be affixed to the machine or system.

7. Any machine that does not comply must be withdrawn from the market.

Actions you must take

To meet the **Machinery Directive** (see page 55) you need to:

a. Comply with the following mechanical safety checklist. **The aim is to eliminate any risk of accident throughout the machinery's life. This is not a complete list, the detailed list is contained within the Machinery Directive:**

- ☐ Eliminate risk as far as possible, taking the necessary protective measures if some risks cannot be eliminated.
- ☐ Inform users of the residual risks; indicate whether any training is required and stress the need for personal protective equipment.
- ☐ Machinery design, construction and instructions must consider any abnormal use.
- ☐ Under the intended conditions of use, the discomfort, fatigue and stress of the operator must be reduced.
- ☐ The manufacturer must take account of the operator's constraints resulting from the use of personal protective equipment.
- ☐ Machinery must be supplied with all essential equipment to enable it to be used without risk.

b. Comply with the following electrical safety checklist: **To ensure the electrical safety of all parts of the PDS as specified in the Low Voltage Directive (refer to page 56) you need to comply with the following safety checklist, which is not necessarily complete.**

- ☐ The electricity supply should be equipped with a disconnecting device and with emergency devices for prevention of unexpected startup.
- ☐ The equipment shall provide protection of persons against electric shock from direct or indirect contact.

The equipment is protected against the effects of:

☐ overcurrent arising from a short circuit.

☐ overload current.

☐ abnormal temperatures.

☐ loss of, or reduction in, the supply voltage.

☐ overspeed of machines/machine elements.

The electrical equipment is equipped with an equipotential bonding circuit consisting of the:

– PE terminal.
– conductive structural parts of the electrical equipment and the machine.
– protective conductors in the equipment or the machine.

☐ The control circuits and control functions ensure safe operation including the necessary inter-lockings, emergency stop, prevention of automatic re-start, etc.

Defined on page 40

c. Compile a **technical file** for the machine, including the PDS.

Key point:

Generally, must carry **CE marking** and have a **Declaration of conformity**.

For machines that pose a high risk of accident, a **type certification** (see page 46) is required from a **notified body**. Such machinery is included in Annex IV of the **Machinery Directive**.

The **type certificate** issued should be included in the **technical file** for the machine or safety component. Refer now to page 40.

☐ 2. Declarations of conformity from each of the component suppliers whose products make up the PDS and incorporate them into the technical documentation, referring to all three directives. If buying a PDS from a system designer (see below), he should be able to provide all declarations. If system designer or component supplier cannot provide a Declaration of conformity, the responsibility of demonstrating compliance according to EMC Directive or Low Voltage Directive lies on machine builder.

If the panel builder buys non-CE marked components, the drive may be made to conform without further testing if the components themselves have been tested. However, tested components do not carry the CE mark but must carry suitable instructions for installation. It is these instructions which must be demonstrably met.

Option A - Actions to meet these responsibilities

☐ 1. Follow the **installation guidelines** issued by each of the component suppliers.

☐ 2. Optimise the construction of the installation to ensure the design meets the required EMC behaviour, ie, the location of filters.

☐ 3. Issue **technical documentation** for the system.

☐ 4. If you choose to assess yourself you must make reference to EMC Directives:

2004/108/EC;

And to harmonised standard:

EN 61800-3

And you must make reference to LVD Directive:

2006/95/EC

And corresponding harmonized standard:

EN 61800-5-1 or EN 50178

Defined on pages 36-46

☐ 5. Once testing is completed, the results need to be included in the **technical documentation (TD)** for the panel.

☐ 6. **Technical documentation** shall be assessed by youself in order to demonstrate compliance. You may use **Notified Body** for assessment as well.

☐ 7. You must then issue the **Declaration of conformity** and **CE marking** for the panel.

Option B - To buy CE marked components

Option B - Actions to meet these responsibilities

☐ 1. Buying CE marked components creates a system or an apparatus (refer to page 17-20) depending on the nature of the panel.

☐ 2. Although the panel builder does not have to carry out tests, he must ensure he conforms to the installation guidelines given by each of the component manufacturers.
Note: Be aware that combining two or more CE-marked components may not automatically produce a system, which meets the requirements.

☐ 3. Beware! These guidelines could differ greatly from those given for normal installation purposes because the components will be in close proximity to each other.

☐ 4. Issue **instructions for use** in order to operate the system or **apparatus**.

☐ 5. Issue **technical documentation**.

☐ 6. Issue a **Declaration of conformity.**

☐ 7. Apply **CE marking** to your panel in the case of an apparatus. In the case of a system **DO NOT** apply **CE marking.**

Additional actions

The panel can be either sold on the open market or use as part of a machine. For each option there is a different requirement:

☐ 1. If you know that the panel is to be used as part of a machine then you must request from the CDM / BDM manufacturer a **Declaration of incorporation**.

☐ 2. The **Declaration of incorporation** must be supplied with the panel to the **machine builder**, but **CE marking** based on Machinery Directive MUST NOT be affixed. This is because **CE marking** always needs a **Declaration of conformity**.

Key point:

The **Declaration of incorporation** CAN NOT be used to apply **CE marking.**

☐ 3. The **machine builder** will need this **Declaration of incorporation** because he has to construct a **technical documentation (TD**) for the machine and in that file all the declarations need to be included.

If you are a distributor buying a CDM/BDM...

...You have the following responsibilities:

1. If a distributor is selling boxed products, like CDMs and BDMs (drives), direct from the manufacturer, his only responsibility is to pass on the **installation guidelines** to the end-user, **machine builder** or **system designer**. In addition, the **Declaration of conformity** must be passed to the **machine builder** or **system designer.**

2. Both the **installation guidelines** and the **Declaration of conformity** are available from the manufacturer.

Actions you must take to meet these responsibilities

1. Pass all **installation guidelines** and **declaration of conformities** to either the **end-user, machine builder** or **system designer.**

If you are an installer buying a CDM/BDM or PDS...

...You have the following responsibilities:

1. You must ensure that the **installation guidelines** of the **machine builder** and/or **system designer** are adhered to.

Actions you must take to meet these responsibilities

1. Follow **machinery builder** and/or **system designer Installation guidelines.**

2. See Technical guide No. 3 for recommended installation guidelines.

Chapter 5 - Terminology

Technical documentation (TD)

APPLIED TO: electrical equipment

RESPONSIBILITY: electrical equipment manufacturer, system designer, panel builder, OEM, installer

REQUIRED BY: EMC Directive, Low Voltage Directive

What is technical documentation?

Technical documentation (TD) must be provided for the entire equipment or system and if required is to show a **competent authority** that you have met the essential requirements of the **EMC Directive** (see page 57) and Low Voltage Directive (see page 56).

The TD consists of three parts:

1. A description of the product.

2. Procedures used to ensure conformity of the product to the requirements.

3. A statement from a notified body, if third party assessment route is chosen.
   Note: Using a notified body is voluntary and can be decided by the manufacturer

Key point:

The full content of the technical documentation are given on pages 36-39.

Why is technical documentation deemed to be important?

Anyone placing a product onto the market within the EU must be able to show that the product meets the requirements of the appropriate **EU Council Directive** and must be able to demonstrate this to a **competent authority** without further testing.

Technical documentation allows the appropriate **Declaration of conformity** to be drawn up.

Will customers always receive a copy of technical documentation?

The content of the technical documentation is meant for the authorities, and thus the electrical equipment manufacturer does not have to give the technical documentation or any part of it to the customer.

However, as the customer needs to know whether the product is in conformance, he will obtain this assurance from the documentation delivered with the product. It is not required to supply a declaration of conformity with the product, but the end-user may ask for this from the manufacturer.

What is the shelf life of technical documentation?

Any technical documentation must be accessible to the appropriate authorities for 10 years from the last relevant product being delivered.

How do I ensure that tests are always carried out?

The whole system is based on self certification and good faith. In various parts of Europe the methods of ensuring compliance will vary. Supervision of these regulations is achieved through market control by a competent authority. If the equipment fails to meet the requirements of the EMC and Low Voltage Directives competent authorities can use the safeguard clause of the Directives (withdraw the product from the market, take legal action).

Can drive manufacturers help more?

Manufacturers accept that there is a need to work more closely with OEMs and machine builders where the converter can be mounted on the machine. A standard assembly or design should be achieved so that no new parts of technical documentation need to be created.

However, the idea of mounting drives in motor control centres (MCCs) must be much more carefully thought out by system specifiers.

The concept of mounting several drives in a motor control centre must be more carefully thought out, as the summing of high frequency emissions to determine the effects at the MCC terminals is a complex issue and the possibilities of cross coupling are multiplied.

How to make up a TD

1. Description of the product

(Note: You can photocopy these pages and use as a tickbox checklist)

i. identification of product

☐ a. brand name.

☐ b. model number.

☐ c. name and address of manufacturer or agent.

☐ d. a description of the intended function of the apparatus.

☐ e. any limitation on the intended operating environment.

ii. a technical description

☐ a. a block diagram showing the relationship between the different functional areas of the product.

☐ b. relevant technical drawings, including circuit diagrams, assembly diagrams, parts lists, installation diagrams.

☐ c. description of intended interconnections with other products, devices, etc.

☐ d. description of product variants.

2. Procedures used to ensure product conformity

i. details of significant design elements

☐ a. design features adopted specifically to address EMC and electrical safety problems.

☐ b. relevant component specifications.

☐ c. an explanation of the procedures used to control variants in the design together with an explanation of the procedures used to assess whether a particular change in the design will require the apparatus to be re-tested.

☐ d. details and results of any theoretical modelling of performance aspects of the apparatus.

☐ e. a list of standards applied in whole or part.

☐ f. the description of the solution adopted in order to comply with the directive.

ii. test evidence where appropriate

☐ a. a list of the EMC and electrical safety tests performed on the product, and test reports relating to them, including details of test methods, etc.

☐ b. an overview of the logical processes used to decide whether the tests performed on the apparatus were adequate to ensure compliance with the directive.

☐ c. a list of the tests performed on critical sub-assemblies, and test reports or certificates relating to them.

3. If chosen a statement from notified body

This will include:

☐ i. reference to the exact build state of the apparatus assessed

☐ ii. comment on the technical documentation.

☐ iii. statement of work done to verify the contents and authenticity of the design information.

☐ iv. statement, where appropriate, on the procedures used to control variants, and on environmental, installation and maintenance factors that may be relevant.

4. Actions by the notified body

The **notified body** will study the **technical documentation** and issue the statement and this should be included in the **technical documentation.**

Note: When compiling the **technical documentation** you may need all **Declarations from suppliers**, ie, **Declaration of conformity** and **Declaration of incorporation** depending on the parts, to ensure they carry **CE marking.**

Technical file (for mechanical safety aspects)

APPLIED TO: machines and safety components

RESPONSIBILITY: machine builder / system designer

REQUIRED BY: Machinery Directive

What is a technical file?

A technical file is the internal design file which should show how and where the standards are met and is all that is needed if self certifying the equipment by the standards compliance route.

If a Declaration of incorporation is included in a set of papers and this claims to meet the appropriate parts of the standards and simply instructs the user to meet the standards with other parts of his machine, it is possible to use this as a part of a technical file.

How to make up a technical file

Drawings and diagrams

1. Overall drawings of the machine.

2. Control circuit diagrams.

Health and safety

1. All drawings, calculations and test results used to check the machine's conformity with essential health and safety requirements.

Machine design

1. Lists of the essential health and safety requirements, **harmonised standards**, other standards and technical specifications used when designing the machine.

2. Description of methods used to eliminate hazards presented by the machine.

Other certificates required

1. A technical report or certificate issued by a **notified body** - if required.

2. A copy of the instructions for the machine.

3. For series produced machines, the control measures that are used to ensure that subsequent manufacture remains in conformity with the directive.

Certificate of Adequacy

APPLIED TO: machines / safety components

RESPONSIBILITY: notified body / machine builder

REQUIRED BY: Machinery Directive

What if standards cannot be wholly implemented?

In this case the adequacy of the **technical file** is proved by a **Certificate of Adequacy** issued by a **notified body.**

How to obtain a Certificate of Adequacy

The **Certificate of Adequacy** is a document drawn up by a **notified body**. Once the body has established that the **technical file** contains all the necessary information, the **Certificate of Adequacy** will be issued.

Key point:

The **Certificate of Adequacy** provided should be included in the **technical file.**

Statement

APPLIED TO: electrical equipment

RESPONSIBILITY: notified body

REQUIRED BY: EMC Directive

When the statement is needed

The primary way for manufacturer (or his authorised representative in the Community) to demonstrate the compliance is to use internal production control method. If the manufacturer chooses, he may use other method based on an assessment of a **notified body**.

How to obtain the statement

The manufacturer shall present the **technical documentation** to the **notified body** and request the **notified body** for an assessment thereof. The manufacturer shall specify to the **notified body** which aspects of the essential requirements must be assessed.

The **notified body** shall review the **technical documentation** and assess whether the **technical documentation** properly demonstrates that the requirements of the **Directive**. If the compliance of the apparatus is confirmed, the **notified body** shall issue a statement confirming the compliance of the apparatus.

Key point:

The **statement** provided shall be included in the **technical documentation**.

Report

APPLIED TO: electrical equipment

RESPONSIBILITY: notified body / competent body

REQUIRED BY: Low Voltage Directive

What if standards cannot be wholly implemented?

In the event of a challenge the manufacturer or importer may submit a report issued by a notified body. This report is based on the technical file.

How to obtain a report

The report is a document drawn up by a notified body. Once the body has established that the technical documentation contains all the necessary information and the equipment fulfils the requirements of the Low Voltage Directive, the report will be issued.

Key point:

The report provided should be included in the technical documentation.

Declaration of conformity (for EMC and electrical safety aspects)

APPLIED TO: electrical equipment and electrical equipment of machines

RESPONSIBILITY: equipment manufacturer

REQUIRED BY: Low Voltage Directive and EMC Directive

How to obtain a Declaration of conformity

You need to provide the following:

1. a reference to the Directive(s),
2. an identification of the apparatus to which it refers (including name, type and serial number),
3. the name and address of the manufacturer and, where applicable, the name and address of his authorised representative in the Community,
4. a dated reference to the specifications under which conformity is declared,
5. the date of the declaration,
6. the identity and signature of the person empowered to bind the manufacturer or his authorised representative.

Declaration of conformity (for mechanical safety aspects)

APPLIED TO: machines

RESPONSIBILITY: machine builder

REQUIRED BY: Machinery Directive

How to obtain a Declaration of conformity

You need to provide the following:

1. business name and full address of the manufacturer or, his authorised representative;
2. name and address of the person authorised to compile the technical file, who must be established in the Community;

3. description and identification of the machinery, including generic denomination, function, model, type, serial number and commercial name;

4. a sentence expressly declaring that the machinery fulfils all the relevant provisions of the machinery Directive

5. where appropriate, the name, address and identification number of the notified body which carried out the EC type-examination and the number of the EC type-examination certificate;

6. where appropriate, the name, address and identification number of the notified body which approved the full quality assurance system;

7. a list to the harmonised standards or the other technical standards and specifications used;

9. the place and date of the declaration as well as the identity and signature of the person empowered to draw up the declaration on behalf of the manufacturer or his authorised representative.

Declaration of incorporation

APPLIED TO: machines or equipment intended for incorporation into other machinery

RESPONSIBILITY: drives manufacturer / machine builder / panel builder

REQUIRED BY: Machinery Directive

What is a Declaration of incorporation?

Drives manufacturers must meet the appropriate parts of the Machinery Directive and provide a Declaration of incorporation which states that the drive does not comply on its own and must be incorporated in other equipment.

This declaration will show the standards that have been applied to the parts of the system within the manufacturer's scope.

This declaration includes a statement restricting the user from putting the equipment into service until the machinery into which it is to be incorporated, or of which it is to be a component, has been found, and declared, to be in conformity with the provisions of the Machinery Directive and the national implementing legislation, ie, as a whole including the equipment referred to in this declaration.

The declaration then lists the standards relating to the Machinery and Low Voltage Directives which the manufacturer has met.

It concludes that the entire equipment must meet the provisions of the directive.

Quite simply, the manufacturer passes on the responsibility to the machine or system builder.

Is there no way out of this type of declaration?

No. You must understand that because the manufacturer may be supplying only one part in a machinery, such as the inverter, the manufacturer is legally obliged to ensure that whoever puts the system together must check that it is safe.

Only then can the machine or system builder use the Declaration of incorporation in his technical file of the machine.

Key point:

Most manufacturers will include a Declaration of incorporation covering the Machinery Directive for all built PDS products.

What a Declaration of incorporation contains

1. business name and full address of the manufacturer or his authorised representative;

2. description and identification of the partly completed machinery including generic denomination, function, model, type, serial number and commercial name;

3. a sentence declaring which essential requirements of the Directive are applied and fulfilled;

4. an undertaking to transmit, in response to a reasoned request by the national authorities, relevant information on the partly completed machinery;

5. a statement that the partly completed machinery must not be put into service until the final machinery into which it is to be incorporated has been declared in conformity with the provisions of the Directive;

6. the place and date of the declaration as well as the identity and signature of the person empowered to draw up the declaration on behalf of the manufacturer or his authorised representative.

Type certification

APPLIED TO: machines and safety components

RESPONSIBILITY: machine builder / approved body

REQUIRED BY: Machinery Directive

How to obtain type certification

Type certification is carried out by an **notified body** who will establish that the unit supplied, along with a **technical file**, may be used safely and that any **standards** have been correctly applied.

Once the **type certification** has established this, a **type examination certificate** will be issued.

Chapter 6 - Authorities and bodies

The responsibility for product conformity is given to the manufacturer. If there is any doubt about conformity, then the Authorities can demand technical documentation to show that a product complies with the directives concerning the product.

When assessing product conformity, a manufacturer can use a third party to examine the conformity.

The following types of authorities and bodies exist:

Competent authority

A **competent authority** in any EU or EEA country supervises markets to prevent hazardous products being sold and marketed. They can also withdraw such products from markets.

Notified body

A **notified body** issues type certificates for products, which have their own directives and/or require type testing.

To find a suitable competent authority or **notified body** you can contact:
EU Commission
Enterprise and Industry DG
Information and Documentation Centre
BREY 5 / 150
B-1049 Brussels
Belgium
Ph: +32 2 296 45 51

Or you may find contact through web.site: http://ec.europa.eu/enterprice/electr_equipment/

Chapter 7 - Standards and directives

The use of standards is voluntary, but compliance with directives without the use of harmonised standards is extremely difficult.

There are two ways to show that a power drive system or part of it conform:

– Use of harmonised standards (EN).

– By way of a technical documentation when no harmonised standards exist, or if all parts of a harmonised standard cannot be applied.

Key point:

It is recommended to use technical documentation even when standards are harmonised as it makes it easier to show conformity afterwards, if required by authorities.

Directive or standard?

The legislation of the European Union is defined by different directives.

The directives concerning power drive systems are known as new approach directives, which means that they do not include exact figures or limits for products. What they do include is essential requirements mainly for health and safety which make the application of the relevant harmonised standards mandatory.

The requirements of directives are firmly established in standards. Standards give exact figures and limits for products.

The responsibility for defining standards in Europe rests with three committees: CEN, for areas of common safety, CENELEC, for electrical equipment and ETSI, for telecommunications.

Harmonised standards for PDSs

To remove technical barriers to trade in EU or EEA countries, the standards are harmonised in member states.

In the harmonisation procedure, all member states are involved in developing the Committee's proposals for their own national standard. A standard becomes harmonised when published in the Official Journal of the EU.

The idea is that if a product conforms to the **harmonised standard**, it is legally manufactured and when placed onto the market in one country, it must be freely marketed in other member countries.

How to recognise a European standard

Harmonised standards come in the following format:

XX EN 60204-1

where

XX = the national prefix (eg BS = UK; SFS = Finland)
EN = the abbreviation of Euronorm
60204-1 = an example of a standard number

The numbering of European standards follows a well structured and organized sequence:
- EN 50225:1996 (the year of availability of the EN is separated from the number by a colon)
- EN 50157-2-1:1996 (the part number is indicated by a hyphen)

The first two numerals indicate the origin of the standard:
- 40xxx to 44xxx cover domains of common CEN/CENELEC activities in the IT field
- 45xxx to 49xxx cover domains of common CEN/CENELEC activities outside the IT field
- 50xxx to 59xxx cover CENELEC activities, where
  - EN 50xxx refer to the standards issued by CENELEC only
  - EN 55xxx refer to the implementation of CISPR documents
- 60000 to 69999 refer to the CENELEC implementation of IEC documents with or without changes

European standards are adopted and confirmed by CENELEC member countries by adding national prefix before the standard id (for example: SFS-EN 60601-1, DIN EN 60601-1, BS EN 60601-1).

There is also some clue as to a standard's status:

prEN 50082-2 = proposal for standard sent to member states
ENV 50 = pre-standard which is in force for 3 years to obtain practical experience from member states

Your questions answered

Which standards directly relate to drives?

At the moment, there are three **Product Specific Standards** (see page 50) which relate to the compliance with EU directives. They are called as “EN 61800-3 Adjustable speed electrical power drive systems. Part 3: EMC product standard including specific test methods”, which relates to **EMC Directive**, “EN 61800-5-1 Adjustable speed electrical power drive systems. Part 5-1: Safety requirements. Electrical, thermal and energy”, which relates to **Low Voltage Directive** and EN 61800-5-2, Part 5-1: Safety requirements. Electrical, thermal and energy”, which relates to **Low Voltage Directive** and “EN 61800-5-2 Adjustable speed electrical power drive systems. Part 5-2: Safety requirements. Functional safety”, which relates to **Machinery Directive.**

In addition there are other standards which need to be taken account:

- EN 60204-1, Electrical Equipment of Machines, which, in addition to being a **Low Voltage Directive** standard for all electrical equipment, is also an electrical safety standard under the **Machinery Directive**.
- EN 50178 according to **Low Voltage Directive** and
- EN 61800-1/2/4, which give rating specifications for Power Drive Systems (LV DC, LV AC and MV AC PDS respectively).
- EN 61000-3-2 and EN 61000-3-12 which give requirements for harmonic current caused by equipment

What are the issues of EN 61800-3 and drives?

For emissions there are two main aspects to be considered:

Conducted emissions: these are seen on the power supply cables and will also be measured on the control connections, while radiated emissions are air borne.

Conducted emissions at low frequencies are known as harmonics which have been a familiar problem to many users of a PDS. Where harmonics are concerned EN 61800-3 refers to EN 61000-3-2 which applies for equipment under 16 A per phase. In addition, the harmonics standard EN 61000-3-12 applies up to 75 A per phase.

At the moment following groups can be separated
- Below 16 A per phase
  - Professional, over 1kW => No limits.
  - Other > the limits specified.
- Between 16 A and 75 A per phase

- Equipment for public low voltage systems => the limits specified.
- Equipment for other systems => the limits specified

Conformity with conducted emissions can be helped by good product design and is readily achieved, in most situations, using filters, providing this is for a single drive.

Radiated emissions: These are more problematic. While it is possible to make the drive enclosure into a Faraday cage and thereby have all radiation attenuated to earth, in practice it is the outgoing connections where inadequate cabling radiates emissions and cross couples with other cables in the vicinity. Important attenuation methods are shielded cables and 360° grounding.

What are the solutions to radiated emissions?

The most important solutions are good installation practice, tight enclosure, shielded cables and 360° grounding. (See Technical guide No. 3 for tips and advice).

Do I have to conform to the standards?

The use of standards is voluntary, but compliance with a Directive without the use of **Harmonised Standards** is difficult in the majority of cases.

Can I be fined for not conforming?

Yes. Failure to comply with any of the Directives will be a criminal offence.

The Product Specific Standard EN 61800-3

This standard defines the required emission and immunity levels of PDSs and the test methods to measure the levels. In Europe, the standard takes precedence over all generic or product family EMC standards previously applicable.

The standard defines two environments where equipment can be used:

First environment

- environment that includes domestic premises, it also includes establishments directly connected without intermediate transformers to a low-voltage power supply network which supplies buildings used for domestic purposes. Houses, apartments, commercial premises or offices in a residential building are examples of this kind of locations.

Second environment

– environment that includes all establishments other than those directly connected to a low voltage power supply network which supplies buildings used for domestic purposes. Industrial areas, technical areas of any building fed from a dedicated transformer are examples of second environment locations

The standard divides PDSs and their component parts into four categories depending on the intended use

PDS of category C1:

A PDS with rated voltage less than 1,000V and intended for use in the first environment. A (PDS (or CDM) sold "as built" to the end-user.

Description
Placed on the market. Free movement based on compliance with the EMC Directive. The **EC Declaration of Conformity** and **CE Marking** are required.

The PDS manufacturer is responsible for EMC behaviour of the PDS under specified conditions. Additional EMC measures are described in an easy-to-understand way and can be implemented by a layman.

When PDS/CDM is going to be incorporated with another product, the resulting EMC behaviour of that product is the responsibility of the assembler of the final product, by following the manufacturer's recommendations and guidelines.

PDS of category C2:

PDS with rated voltage less than 1,000 V, which is neither a plug in device nor a movable device and is intended to be installed and commissioned only by a professional.

A PDS (or CDM/BDM) sold to be incorporated into an apparatus, system or installation.

Description:
Placed on the market. Intended only for professional assemblers or installers who have the level of technical competence of EMC necessary to install a PDS (or CDM/BDM) correctly. The manufacturer of the PDS (or CDM/BDM) is responsible for providing **Installation Guidelines**. The **EC Declaration of Conformity** and **CE Marking** are required.

When a PDS/CDM/BDM is to be incorporated with another product, the resulting EMC behaviour of that product is the responsibility of the assembler of the final product.

PDS of category C3:

PDS with rated voltage less than 1,000 V, intended for use in the second environment.

A PDS (or CDM/BDM) sold "as built" to the end-user or in order to be incorporated into an apparatus, system or installation.

Description
Placed on the market. Free movement based on compliance with the EMC Directive. The **EC Declaration of Conformity** and **CE Marking** are required.

The PDS manufacturer is responsible for EMC behaviour of the PDS under specified conditions. Additional EMC measures are described in an easy-to-understand way and can be implemented by a layman.

When PDS/CDM is going to be incorporated with another product, the resulting EMC behaviour of that product is the responsibility of the assembler of the final product, by following the manufacturer's recommendations and guidelines.

PDS of category C4:

PDS with rated voltage equal to or above 1,000 V, or rated current equal to or above 400 A, or intended for use in complex systems in the second environment.

A PDS (or CDM/BDM) sold to be incorporated into an apparatus, system or installation.

Description
Category C4 requirements include all other EMC requirements but radio frequency emission. They assessed only when it is installed in its intended location. Therefore category C4 PDS is treated as a fixed installation, and thus has no requirement for **EC Declaration of Conformity** or **CE Marking**.

The EMC directive requires the accompanying documentation to identify the fixed installation, its electromagnetic compatibility characteristics and responsible person, and to indicate the precautions to be taken in order not to compromise the conformity of that installation.

In order to comply the above requirements in the case of category C4 PDS (or CDM/BDM), the user and the manufacturer shall agree on an EMC plan to meet the EMC requirements of the intended application. In this situation, the user defines the EMC characteristics of the environment including the whole installation and the neighborhood. The manufacturer of PDS shall provide information on typical emission levels and installation guidelines of the PDS which is to be installed. Resulting EMC behaviour is the responsibility of the **installer** (eg, by following the EMC plan).

Where there are indications of non-compliance of the category C4 PDS after commissioning, the standard includes procedure for measuring the emission limits outside the boundary of an installation.

Examples concerning applications of different approaches

1. BDM used in domestic or industrial premises, sold without any control of the application.

The manufacturer is responsible that sufficient EMC will be achieved even by a layman. Although the EMC Directive applies to the apparatus and fixed installations only (generally components are excluded), it states that the components which are intended for incorporation into apparatus by the end user and which liable to generate electromagnetic disturbances are included. Thus, if members of the public (**end-users**) buy a component off the shelf, they will not have to worry about compliance when they fit it to their machine. Therefore, the responsibility for compliance and **CE Marking** such components under EMC lies with the manufacturer. Depending of intended installation location category C1 or C3 equipment is allowed.

2. PDS or CDM/BDM for domestic or industrial purposes, sold to professional assembler.

This is sold as a sub-assembly to a professional assembler who incorporates it into a machine, apparatus or system. Conditions of use are specified in the manufacturer's documentation. Exchange of technical data allows optimization of the EMC solutions. In addition of categories C1 and C3, also category C2 is allowed.

3. PDS or CDM/BDM for use in installations.

The conditions of use are specified at the time by the purchase order; consequently an exchange of technical data between supplier and client is possible. It can consist of different commercial units (PDS, mechanics, process control etc).

The combination of systems in the installation should be considered in order to define the mitigation methods to be used to limit emissions. Harmonic compensation is an evident example of this, both for technical and economical reasons.

In addition of categories C1, C2 and C3, also category C4 is allowed.

4. PDS or CDM/BDM for use in machine.

PDS or CDM/BDM combined with application device (machine) such as a vacuum cleaner, fan, pump or such like, ie, ready to use apparatus. Similarly inverters (E.Q. subassemblies of BDMs) come under this class of components. On their own they do not have an intrinsic function for the **end-users**, but are sold to professional **installers** who incorporate them into a machine, apparatus or system. They are not on sale directly to the **end-user**.

Therefore for EMC Directive point of view the PDS/CDM/BDM here is a component which is excluded from the directive. The machine builder is responsible for all EMC issues. The manufacturer of PDS/CDM/BDM is responsible for providing installation, maintenance and operation instructions to the machine builder in order to achieve compliance with EMC Directive.

Nevertheless, it is recommended to use category C1, C2, C3 or C4 PDS/CDM/BDM rather than drives without any compliance.

Machinery Directive 98/37/EC

How does the Machinery Directive affect my drive?

This directive concerns all combinations of mechanically joined components, where at least one part is moving and which have the necessary control equipment and control and power input circuits.

The directive concerns all machines but not those like lifts, which have a specific directive.

The new machinery Directive 2006/42/EC has been published. Since the old directive 98/37/EC can be used until December 29, 2009, the changes due to the new directive will be consider in the future editions of this Guide.

Key point:

As far as drives are concerned, the new version of EN 60204-1, ed. 5, is already published. The old and the new versions can be used until June 1, 2009. After that date only the new version shall be applied.

On its own, the **complete drive module (CDM)** does not have a functional value to the user. It always needs its motor coupled to the driven load before it can function effectively. Thus, it cannot carry the **CE marking** based on the **Machinery Directive**.

Where can I obtain a Machinery Directive copy?

To obtain a copy of the **Machinery Directive** you can contact a local competent authority or download it from European Unions web-site related to the legislation (http://europa.eu.int/eur-lex/).

Low Voltage Directive

How does the LVD affect my drive?

2006/95/EC

This directive concerns all electrical equipment with nominal voltages from 50 V to 1 kV AC and 75 V to 1.5 kV DC.

The aim of the directive is to protect against electrical, mechanical, fire and radiation hazards. It tries to ensure only inherently safe products are placed on the market.

All parts of a PDS from converters and motors to control gear must conform with the **Low Voltage Directive**.

To guarantee that a product complies, the manufacturer must provide a **Declaration of conformity**. This is a Declaration that the product conforms to the requirements laid down within this Directive.

If a product conforms to the Directive and has a **Declaration of conformity**, then it must carry the **CE marking.**

In the case of a power drive system, the **Declaration of conformity** is needed for each of its component parts. Thus, the **Declaration of conformity** for the complete drive module (CDM) and for the motor have to be given separately by the manufacturer of each product.

Key point:

Most manufacturers will include a **Declaration of conformity** covering the **Low Voltage Directive** for all built PDS/CDMs. These are drives built into an enclosure, which can be wired up to the supply and switched on without any further work being undertaken. This is in contrast to an open chassis (BDM), which is a component and needs an enclosure.

Why is the Declaration of conformity important?

Key point:

Without the **Declaration of conformity** the CDM could not carry the **CE marking** and therefore it could not be sold within EEA countries and therefore could not be used legally in any system.

EMC Directive

How does the EMC Directive affect my drive?

2004/108/EC

The intention of the **EMC Directive** is, as its name implies, to achieve EMC compatibility with other products and systems. The directive aims to ensure emissions from one product are low enough so as not to impinge on the immunity levels of another product.

There are two aspects to consider with the **EMC Directive**:

– the **immunity** of the product.
– the **emissions** from that product.

Although the directive expects that EMC should be taken into account when designing a product, in fact EMC cannot be handled by design only – it shall be measured quantitatively as well.

Key point:

Most drives bear **CE-marking**. Newertheless, some cases drives are part of the machinery or process equipment/system and classified as components they are not included into the EMC directive.

The **machine builder**, therefore, has the final responsibility to ensure that the machine including any PDS and other electrical devices, meets the EMC requirements.

At each stage of the manufacturing process, from component to system, each manufacturer is responsible for applying the appropriate parts of the directive. This may be in the form of instructions on how to install or fit the equipment without causing problems. It does not imply that there is a string of **Declarations of conformity** to be compiled into a manual.

Who has the responsibility to ensure CE marking?

A frequency converter is likely to be only a part of a power drive system.

Yet it is the entire system or machinery that must meet the requirements of the EMC Directive.

So, drives manufacturers are in a position to choose whether to put **CE marking** on to a frequency converter to indicate compliance with the EMC Directive or to deliver it as a component without **CE marking**.

Key point:

It is the responsibility of the person who finally implements the system to ensure EMC compliance.

Either the **machine builder** or **system supplier** has the final responsibility that the machine or system including the drive and other electrical and electronic devices will meet the EMC requirements.

A drive manufacturer is able to help **machine builder** or **system supplier** by providing BDM/CDM/PDS which are according to the EMC directive and **CE-marked**.

Summary of responsibilities

Summary of manufacturer's responsibilities in the application of EC Directives to systems containing a PDS:

Warnings & guide

Power drive system

Machinery Directive	Low Voltage Directive	EMC Directive
Any safety relevant standard such as EN 61800-5-2, EN 60204-1, etc	EN 61800-5-1 EN 50178 EN 60204-1	EN 61800-3
TECHNICAL FILE	TECHNICAL FILE	TECHNICAL DOCUMENTATION
Apply Harmonised Standards as far as possible	Apply Harmonised Standards	Apply Harmonised Standards
Declaration of Incorporation	EU Declaration of Conformity	EU Declaration of Conformity
No CE marking as the PDS is a component of the machine	CE mark applied	CE mark applied

If some of the directives result in CE marking, the PDS (or CDM or BDM) can be CE marked with the corresponding Declaration of conformity.

An analogue of this procedure occurs for each end product which is to be combined with a PDS. However, check all directives applicable to the end product.

Achieving conformity with EC Safety Directives



* Only if required during market surveillance
** Optional procedure, if chosen by the manufacturer

Index

A
abnormal temperatures 27
apparatus 34, 38

B
basic drive module 22
BDM 22, 31, 32, 35, 57, 59

C
CDM 22
CE mark 32, 34, 59
CEN 48, 49
CENELEC 48, 49
certificate of adequacy 41
competent authority 47, 60
complete drive module 22
components 30, 34
component supplier 29, 30, 33
conducted emissions 51
control circuit diagrams 40

D
Declaration of conformity 29, 30, 31, 34, 57, 59
Declaration of incorporation 34, 35, 59
distributor 24
drive 22, 24

E
EEA 11, 15, 47, 48, 57
electrical safety 25, 26, 31, 32, 50
electromagnetic compatibility 53
EMC 11, 29, 30, 33, 36, 39, 57, 59
EMC Directive 30
EN61800-3 33, 50
end user 23, 24
ETSI 48
EU 11, 49, 59
EU Council Directives 1, 11
European Union 48

F
Faraday cage 51
filter 30, 33
frequency converter 21, 58

H
harmonics 9, 50
harmonised standard 48, 49

I
IEC 49
indirect contact 26
installation 22
installation guidelines 29, 30
installation instructions 18
installer 24

L
Low Voltage Directive 11, 56, 57, 59

M
machine builder 23, 24, 25, 40, 41, 46
machinery builder 35
Machinery Directive 11, 40, 41, 46, 55, 59
MCC 37
microprocessor 12
mobile radio transmitters 12
motor 22
motor control centre 37

N
notified body 40, 41

O
OEM 24
overload current 27

P
panel builder 23, 24, 32
parameters 16
PDS 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 48, 57, 59, 60
phase-shift transformer 21
portable car telephones 12
power drive system 22, 59

S
safety component 40, 41, 46
screen 12
self certification 15, 16, 37
sensor 22
short circuit 27
single functional unit 29, 30
standards 39, 40, 46, 48, 50, 51
system designer 23, 24, 30, 35
systems 1, 3, 9, 12, 13, 21, 48, 50, 51, 53, 55, 57, 59

T
TD 33, 35, 36, 38
technical construction file 38
technical documentation 15, 28, 29, 30, 33, 34, 35, 36, 37, 39, 42, 47, 48
technical file 27, 59, 60
type certificate 27
type certification 46
type examination certificate 46

W
walkie-talkies 12

Contact us

For more information contact
your local ABB representative or visit:

www.abb.com/drives
www.abb.com/drivespartners

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.

3AFE61253980 REV D EN 29.4.2011 #15647

Power and productivity
for a better world™

ABB drives

Technical guide No. 3
EMC compliant installation and configuration for a power drive system

Power and productivity
for a better world™

Technical guide No. 3
EMC compliant installation and configuration for a power drive system

3

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AFE61348280 REV D 14.6.2011

Contents

Chapter 1 - Introduction 7

General 7
Purpose of this guide 7
Directives concerning the drive 7
Who is the manufacturer? 7
Manufacturer's responsibility 7
OEM customer as a manufacturer 8
Panel builder or system integrator as a manufacturer 8
Definitions 8
Practical installations and systems 8
Earthing principles 9
Product-specific manuals 9

Chapter 2 - Definitions 10

Electromagnetic compatibility (EMC) of PDS 10
Immunity 10
Emission 10
Power drive system 11
Types of equipment 12
Components or sub-assemblies intended for incorporation 12
into an apparatus by the end users 12
Components or sub-assemblies intended for incorporation 12
into an apparatus by other manufacturers or assemblers 12
Finished appliance 13
Finished appliance intended for end users 13
Finished appliance intended for other manufacturer or assembler 13
Systems (combination of finished appliances) 14
Apparatus 14
Fixed installation 14
Equipment 14
CE marking for EMC 14
Installation environments 15
First environment 15
Second environment 16
EMC emission limits 16
PDS of category C1 16
PDS of category C2 16
PDS of category C3 16
PDS of category C4 17

Chapter 3 - EMC solutions 19

General 19
Solutions for EMC compatibility 19
Emissions 19

Conducted emission 19
Radiated emission 20
Enclosure 20
Cabling and wiring 20
Installation 21
Clean and dirty side 21
RFI filtering 22
Selecting the RFI filter 23
Installation of the RFI filter 23
Selection of a secondary enclosure 23
Holes in enclosures 24
360° HF earthing 25
HF earthing with cable glands 25
HF earthing with conductive sleeve 26
360° earthing at motor end 27
Conductive gaskets with control cables 28
The shielding should be covered with conductive tape. 28
Installation of accessories 29
Internal wiring 29
Control cables and cabling 31
Power cables 32
Transfer impedance 33
Use of ferrite rings 33
Simple installation 35
Typical installation 35

Chapter 4 - Practical examples 35

Example of by-pass system <100 kVA 36
Typical example of 12-pulse drive 37
Example of EMC plan 39

Chapter 5 - Bibliography 41

Chapter 6 - Index 42

Chapter 1 - Introduction

General

This guide assists design and installation personnel when trying to ensure compliance with the requirements of the EMC Directive in the user's systems and installations when using AC drives.

Purpose of this guide

The purpose of this guide is to guide original equipment manufacturers (OEM), system integrators and panel builders (assemblers) in designing or installing AC drive products and their auxiliary components into their own installations and systems. The auxiliaries include contactors, switches, fuses, etc. By following these instructions it is possible to fulfill EMC requirements and give CE marking when necessary.

Directives concerning the drive

There are three directives that concern variable speed drives. They are the Machinery Directive, Low Voltage Directive and EMC Directive. The requirements and principles of the directives and use of CE marking are described in technical guide No. 2 "EU Council Directives and adjustable electrical power drive systems". This document deals only with the EMC Directive.

Who is the manufacturer?

According to the EMC Directive (2004/108/EC), the definition of a manufacturer is following: "This is the person responsible for the design and construction of an apparatus covered by the Directive with a view to placing it on the EEA market on his own behalf. Whoever modifies substantially an apparatus resulting in an "as-new" apparatus, with a view to placing it on the EEA market, also becomes the manufacturer."

Manufacturer's responsibility

According to the EMC Directive the manufacturer is responsible for attaching the CE mark to each unit. Equally the manufacturer is responsible for writing and maintaining technical documentation (TD).

OEM customer as a manufacturer

It is well known that OEM customers sell equipment using their own trademarks or brand labels. Changing the trademark, brand label or the type marking is an example of modification resulting in “as new” equipment.

Frequency converters sold as OEM products shall be considered components (complete drive module (CDM) or basic drive module (BDM)). Apparatus is an entity and includes any documentation (manuals) intended for the final customer. Thus, the OEM-customer has sole and ultimate responsibility concerning the EMC of equipment, and he shall issue a Declaration of Conformity and technical documentation for the equipment.

Panel builder or system integrator as a manufacturer

According to the EMC Directive, a system is defined as a combination of several types of equipment, finished products, and/or components combined, designed and/or put together by the same person (system manufacturer) intended to be placed on the market for distribution as a single functional unit for an end-user and intended to be installed and operated together to perform a specific task.

A panel builder or system integrator typically undertakes this kind of work. Thus, the panel builder or system integrator has sole and ultimate responsibility concerning the EMC of the system. He cannot pass this responsibility to a supplier.

In order to help the panel builder/system integrator, ABB Oy offers installation guidelines related to each product as well as general EMC guidelines (this document).

Definitions

The EMC Product Standard for Power Drive Systems, EN 61800-3 (or IEC 61800-3) is used as the main standard for variable speed drives. The terms and definitions defined in the standard are also used in this guide.

Practical installations and systems

This guide gives practical EMC examples and solutions that are not described in product specific manuals. The solutions can be directly used or applied by the OEM or panel builder.

Earthing principles

The earthing and cabling principles of variable speed drives are described in the manual “Grounding and cabling of the drive system”, code 3AFY61201998. It also includes a short description of interference phenomena.

Product-specific manuals

Detailed information on the installation and use of products, cable sizes etc. can be found in the product specific manuals. This guide is intended to be used together with product specific manuals.

Chapter 2 - Definitions

Electromagnetic compatibility (EMC) of PDS

EMC stands for Electromagnetic compatibility. It is the ability of electrical/electronic equipment to operate without problems within an electromagnetic environment. Likewise, the equipment must not disturb or interfere with any other product or system within its locality. This is a legal requirement for all equipment taken into service within the European Economic Area (EEA). The terms used to define compatibility are shown in figure 2-1.



Figure 2-1 Immunity and emission compatibility.

As variable speed drives are described as a source of interference, it is natural that all parts which are in electrical or airborne connection within the power drive system (PDS) are part of the EMC compliance. The concept that a system is as weak as its weakest point is valid here.

Immunity

Electrical equipment should be immune to high-frequency and low-frequency phenomena. High-frequency phenomena include electrostatic discharge (ESD), fast transient burst, radiated electromagnetic field, conducted radio frequency disturbance and electrical surge. Typical low-frequency phenomena are mains voltage harmonics, notches and imbalance.

Emission

The source of high-frequency emission from frequency converters is the fast switching of power components such as IGBTs and control electronics. This high-frequency emission can propagate by conduction and radiation.

Power drive system

The parts of a variable speed drive controlling driven equipment as a part of an installation are described in EMC Product Standard EN 61800-3. A drive can be considered as a basic drive module (BDM) or complete drive module (CDM) according to the standard.

It is recommended that personnel responsible for design and installation have this standard available and be familiar with this standard. All standards are available from the national standardization bodies.

Systems made by an OEM or panel builder can consist more or less of the PDS parts alone, or there can be many PDSs in a configuration.

The solutions described in this guide are used within the definition of power drive system, but the same solutions can, or in some cases, should, be extended to all installations. This guide gives principles and practical EMC examples, which can be applied to a user's system.



Figure 2-2 Abb reviations used in drives.

Types of equipment

The EMC Directive (2004/108/EC) defines equipment as any apparatus or fixed installation. As there are separate provisions for apparatus and fixed installations, it is important that the correct category of the equipment (PDM, CDM or BDM) is determined.

In technical-commercial classifications the following terminology is frequently used: components, sub-assemblies, finished appliances (ie, finished products), a combination of finished appliances (ie, a system), apparatus, fixed installations and equipment.

The key issue here is whether the item is meant for end users or not:

- if it is meant for end users, the EMC directive applies;
- if it is meant for manufacturers or assemblers, the EMC directive does not apply.

Components or sub-assemblies intended for incorporation into an apparatus by the end users

A manufacturer may place components or sub-assemblies on the market, which are:

- for incorporation into an apparatus by the end-user,
- available to end-users and likely to be used by them.

These components or sub-assemblies are to be considered as apparatus with regard to the application of the EMC. The instructions for use accompanying the component or sub-assembly should include all relevant information, and should assume that adjustments or connections can be performed by an end user not aware of the EMC implications.

In such case the component is considered equivalent to apparatus. Some variable speed power drive products fall into this category, eg, a drive with enclosure and sold as a complete unit (CDM) to the end user who installs it into his own system. All provisions of the EMC Directive will apply (CE mark, EC declaration of conformity and technical documentation).

Components or sub-assemblies intended for incorporation into an apparatus by other manufacturers or assemblers

Components or sub-assemblies intended for incorporation into an apparatus or another sub-assembly by other manufacturers or assemblers are not considered to be “apparatus” and are therefore not covered by the EMC Directive. These components include resistors, cables, terminal blocks, etc.

Some variable speed power drive products fall into this category as well, eg, basic drive modules (BDM). These are meant to be assembled by a professional assembler (eg, panel builder or system manufacturer) into a cabinet not in the scope of delivery of the manufacturer of the BDM. According to the EMC Directive, the requirement for the BDM supplier is to provide instructions for installation and use.

Note:
The manufacturer or assembler of the panel or system is responsible for the CE mark, the EC Declaration of Conformity, and the technical documentation.

Finished appliance

A finished appliance is any device or unit containing electrical and/or electronic components or sub-assemblies that delivers a function and has its own enclosure. Similarly to components, the interpretation “finished appliance” can be divided into two categories: it can be intended for end users, or for other manufacturers or assemblers.

Finished appliance intended for end users

A finished appliance is considered as apparatus in the sense of the EMC Directive if it is intended for the end-user and thus has to fulfill all the applicable provisions of the Directive.

Variable speed power drive products that fall into this category are whole power drive systems (PDS) or complete drive modules (CDM). In this case all provisions of the EMC Directive will apply (CE mark, EC Declaration of Conformity, and technical documentation). The drive product manufacturer is responsible for the CE mark, EC Declaration of Conformity, and technical documentation.

Finished appliance intended for other manufacturer or assembler

When the finished appliance is intended exclusively for an industrial assembly operation for incorporation into other apparatus, it is not an apparatus in the sense of the EMC Directive and consequently the EMC Directive does not apply for such finished appliances.

The variable speed power drive products that fall into this category are basic drive modules (BDM). The approach is the same as for components or sub-assemblies when they are intended for incorporation into an apparatus by another manufacturer or assembler. Thus the manufacturer or assembler of the panel or system is responsible for all actions relating to the EMC Directive.

Systems (combination of finished appliances)

A combination of several finished appliances which is combined, and/or designed and/or put together by the same party (ie, the system manufacturer) and is intended to be placed on the market for distribution as a single functional unit for an end-user and intended to be installed and operated together to perform a specific task.

All provisions of the EMC Directive, as defined for apparatus, apply to the combination as a whole. The variable speed power drive products that fall into this category are power drive systems (PDS). Thus the manufacturer of the PDS is responsible for all actions relating to the EMC Directive.

Apparatus

Apparatus means any finished appliance or combination thereof made commercially available (ie, placed on the market) as a single functional unit, intended for the end-user, and liable to generate electromagnetic disturbance, or the performance of which is liable to be affected by such disturbance.

Fixed installation

A particular combination of several types of apparatus, equipment and/or components, which are assembled, installed and intended to be used permanently at a predefined location.

Equipment

Any apparatus or fixed installation

CE marking for EMC

Components or sub-assemblies intended for incorporation into an apparatus by the end users need to carry the CE marking for EMC.

Components or sub-assemblies intended for incorporation into an apparatus by another manufacturer or assembler do not need to carry the CE marking for EMC.
Note: The products may carry the CE marking for other directives than EMC.

Apparatus and systems must be CE marked.

Fixed installations are required to satisfy various parts of the Directives, but are not required to be CE marked.

Figure 2-3 The CE mark.

Installation environments

The PDSs can be connected to either industrial or public power distribution networks. The environment class depends on the way the PDS is connected to power supply. The environment classes are first and second environment according to the EN61800-3 standard.

First environment

“The first environment includes domestic premises. It also includes establishments directly connected without intermediate transformer to a low-voltage power supply network which supplies buildings used for domestic purposes.”



Figure 2-4 Illustration of environment classes.

Second environment

"The second environment includes all establishments other than those directly connected to a low-voltage power supply network which supplies buildings used for domestic purposes".

EMC emission limits

The product standard EN 61800-3 divides PDSs into four categories according to the intended use. In Europe, the standard takes precedence over all generic or product family EMC standards previously applicable. Limits for certain conditions can be selected by using the flow chart shown in figure 2-5.

PDS of category C1

A PDS (or CDM) with rated voltage less than 1000 V and intended for use in the first environment. A PDS (or CDM) sold "as built" to the end user.

The PDS manufacturer is responsible for the EMC behavior of the PDS under specified conditions. Additional EMC measures are described in an easy-to-understand way and can be implemented by a layman.

When PDS/CDM is to be incorporated with another product, the resulting EMC behavior of that product is the responsibility of the assembler of the final product, by following the manufacturer's recommendations and guidelines.

PDS of category C2

A PDS (or CDM/BDM) with rated voltage less than 1,000 V, which is neither a plug in device nor a movable device and is intended to be installed and commissioned only by a professional. A PDS (or CDM/BDM) sold to be incorporated into an apparatus, system or installation.

When a PDS/CDM/BDM is to be incorporated with another product, the resulting EMC behavior of that product is the responsibility of the assembler of the final product.

PDS of category C3

A PDS (or CDM/BDM) with rated voltage less than 1,000 V, intended for use in the second environment. A PDS (or CDM/BDM) sold "as built" to the end user or in order to be incorporated into an apparatus, system or installation.

The PDS manufacturer is responsible for the EMC behavior of the PDS under specified conditions. Additional EMC measures are described in an easy-to-understand way and can be implemented by a layman.

When a PDS/CDM is to be incorporated with another product, the resulting EMC behavior of that product is the responsibility of the assembler of the final product, by following the manufacturer's recommendations and guidelines.

PDS of category C4

A PDS (or CDM/BDM) with rated voltage equal to or above 1,000 V, or rated current equal to or above 400 A, or intended for use in complex systems in the second environment. A PDS (or CDM/BDM) sold to be incorporated into an apparatus, system or installation.

Category C4 requirements include all other EMC requirements except for radio frequency emission. They are assessed only when it is installed in its intended location. Therefore a category C4 PDS is treated as a fixed installation, and thus has no requirement for an EC Declaration of Conformity or CE Marking.

The EMC directive requires the accompanying documentation to identify the fixed installation, its electromagnetic compatibility characteristics and the person responsible, and to indicate the precautions to be taken in order not to compromise the conformity of that installation.

In order to comply with the above requirements in the case of a category C4 PDS (or CDM/BDM), the user and the manufacturer shall agree on an EMC plan to meet the EMC requirements for the intended application. In this situation, the user defines the EMC characteristics of the environment including the whole installation and the neighborhood. The PDS manufacturer shall provide information on typical emission levels and installation guidelines for the PDS to be installed. The resulting EMC behavior is the responsibility of the installer (eg, by following the EMC plan).

Where there are indications of non-compliance of the category C4 PDS after commissioning, the standard includes a procedure for measuring the emission limits outside the boundary of an installation.



Figure 2-5 Emission limits for PDS.

Chapter 3 - EMC solutions

General

The solutions used to fulfill immunity and both radiated and conducted emission requirements are described in this chapter.

Solutions for EMC compatibility

There are some basic principles which must be followed when designing and using drive systems incorporating AC drive products. These same principles were used when these products were initially designed and constructed, where such issues as printed circuit board layout, mechanical design, wire routing, cable entries and other special points were all considered in great detail.

Emissions

The emissions can be classified into two types; conducted emission and radiated emission. The disturbances can be emitted in various ways as shown in the following figure:



Figure 3-1 Emissions.

Conducted emission

Conducted disturbances can propagate to other equipment via all conductive parts including cabling, earthing and the metal frame of an enclosure.

Conductive emissions can be reduced in the following way:

- By RFI filtering for HF disturbances
- Using ferrite rings in power connection points
- Using an AC or DC choke (even meant against harmonics, it reduce HF disturbances as well.
- Using an LCL filter in the case of regenerative drives
- Using a du/dt filter

Radiated emission

To be able to effectively prevent disturbance through the air, all parts of the power drive system should form a Faraday cage against radiated emissions. The installation of a PDS includes cabinets, auxiliary boxes, cabling, motors, etc.

Some methods for ensuring the continuity of the Faraday cage are listed as follows:

Enclosure

- The enclosure must have an unpainted non-corroding surface finish at every point where other plates, doors, etc. make contact.
- Unpainted metal-to-metal contacts shall be used throughout, with conductive gaskets, where appropriate.
- Use unpainted installation plates, bonded to a common earth point, ensuring all separate metal items are firmly bonded to achieve a single path to earth.
- Use conductive gaskets in doors and covers. Separate the radiative ie, “dirty” side from the “clean side” by metal covers and design.
- Holes in enclosure should be minimized.

Cabling and wiring

- Use special HF cable entries for high frequency earthing of power cable shields.
- Use conductive gaskets for HF earthing of control cable shield.
- Use shielded power and control cables. See product specific manuals.
- Allow no breaks in the cable shields.
- Select low impedance shield connections on the MHz range.
- Route power and control cables separately.
- Use twisted pairs to avoid disturbances.
- Use ferrite rings for disturbances, if necessary.
- Select and route internal wires correctly.
- See product specific manuals

Installation

- Auxiliaries used with complete drive modules (CDMs) should be CE marked products conforming to both the EMC & Low Voltage Directives, NOT ONLY to the LV directive, unless they are intended for incorporation into an apparatus by another manufacturer or assembler.
- Selection and installation of accessories in accordance with manufacturers' instructions.
- For wall-mounted units, strip the sheathing of a motor cable back far enough to expose the copper wire screen so that the screen can be twisted into a pigtail. Keep the short pigtail short and connect it to the ground.
- For cabinet –models, lead the cables into the inside of the enclosure. Apply 360° grounding of the cable shield at the entry into the cabinet. See product specific manuals.
- 360° earthing at motor end. See motor manuals.

Clean and dirty side

The circuit before the point where the supply power is connected to the CDM and where the filtering starts is referred to as the clean side. The parts of the BDM that can cause disturbances are described as the dirty side.

Enclosed wall-mounted drives are designed so that the circuit followed by the output connection is the only dirty part. That is the case if the installation instructions of the drive are followed.

To be able to keep the clean side "clean", the dirty parts are separated into a Faraday cage. This can be done either with separation plates or with cabling.



Figure 3-2 "Clean" and "dirty" sides of the BDM.

When using separation plates, the rules for enclosure holes are applicable (see Holes in enclosures section later in this chapter).

When the Faraday cage is formed by cabling, the rules for cabling must be applied (see sections on cabling and wiring in this chapter and follow the product specific instructions for the drive).

The use of additional components, eg, contactors, isolators, fuses, etc. in some cases makes it difficult to keep the clean and the dirty side separate.

This can happen when contactors or switches are used in circuits to change over from clean to dirty side (eg, by-pass).

Some examples of solutions are described in chapter 4, Practical examples.

RFI filtering

RFI filters are used to attenuate conducted disturbances in a line connecting point where the filter leads the disturbances to earth.

Output filters attenuate disturbances at the output of a PDS. Eg, du/dt and common mode filters help somewhat, even if they have not been designed for RFI.

Filters cannot be used in a floating network (IT-network) where there is high impedance or no physical connection between the phases and the earth.



Figure 3-3 Example of filtering integrated in drive module.

Figure 3-3 shows an example of integral, distributed filtering. Some drive products need a separate filter (see product specific instructions).

Selecting the RFI filter

An RFI filter is selected to attenuate the conducted disturbances. It is not possible to compare the disturbances measured from a source, and the insertion loss for a filter, as the measurement base for the two items of information will not correspond.

It is always necessary to test a filter in conjunction with the source of disturbance to ensure adequate attenuation and to meet applicable emission limits.

Installation of the RFI filter

Reliable HF/low impedance connections are essential to ensure proper functioning of the filter, therefore the following instructions are to be followed.

- The filter shall be assembled on a metal plate with unpainted connection points all in accordance with the filter manufacturer's instructions.
- The orientation of the filter must be such that it provides enough distance between the input and output wiring of the filter in order to prevent cross-coupling between the clean and dirty side.
- The length of the cable between the filter and the drive must be minimized.
- The input cable of the filter shall be separated from the cable which connects the filter to the drive
- The input cable of the filter shall be separated from the motor cable

Selection of a secondary enclosure

Where the BDM is to be installed, (eg, an IP00 open chassis converter), or if additional components are to be connected to the dirty side of an otherwise compliant unit, it is always necessary to provide an EMC enclosure.

For enclosed chassis modules where the motor connections are made directly to the converter output terminals and all the internal shielding parts are fitted, there are no requirements for special enclosures.

If drives are fitted with output switching devices, for example, then an EMC enclosure will be needed, as the integral Faraday cage will no longer apply.

As a reminder, EMC is only one part of enclosure selection. The enclosure is sized according to several criteria:

- Safety
- Degree of protection (IP rating)

– Heat rejection capability
– Space for accessory equipment
– Cosmetic aspects
– Cable access
– EMC compliance
– General requirements for EMC compatibility

The manufacturer's guidelines for construction and earthing must be followed.



Figure 3-4 Typical enclosure aperture detail.

Holes in enclosures

In most cases, some holes must be made in the enclosure eg, for door devices, louvers, locks, cables, etc.

When an EMC enclosure is to be used, the maximum diagonal or diameter for any hole is 100 mm, which equates to 1/10th of the wavelength of a 300 MHz frequency. This dimension has been found acceptable in EMC tests.

Holes bigger than 100 mm must be covered with a metal frame surrounding the aperture and earthed to the enclosure.

Larger viewing holes can be covered by proprietary glazing with conductive coating.



Figure 3-8 360° earthing with clamping of cable shield.

The advantage of this solution is that the same sleeve can be used for cables with different diameters.

The cable can be mechanically supported by clamps, and a specific cable gland is not required.

Note that the sleeve does not act as a strain relief clamp.

360° earthing at motor end

The continuity of the Faraday cage at the motor end must be ensured by the same methods as in cabinet entry, namely:

- Faraday cage and IP55 degree of protection. This includes:
  - Cable gland providing galvanic contact must be used for clamping the cable.
  - Cable shielding should be sealed with conductive tape.
  - Conductive gaskets should be used for sealing both the cable gland plate and the terminal box cover
- Note: Please check availability from motor manufacturer. It is common that this is one option for the motor
- Pigtails of earthing conductors must be as short as possible.

Figure 3-9 shows a Faraday cage solution at the motor end.

For motors that are not totally enclosed, such as in cooling form IC01, IC06, etc. the continuity of the Faraday cage must be ensured in the same manner as for the converter enclosure.



Figure 3-9 Essential points in motor cabling.

Conductive gaskets with control cables

The 360° HF earthing for control cables can be done with conductive gaskets. In this method the shielded control cable is led through two gaskets and pressed tightly together, as shown in figure 3-9.

When gaskets are mounted at a gland plate, the cable shielding must continue as near to the control connections as possible. In this case the outer insulation of the cable should be removed to allow connection to the shield for the length of the gasket transit.

The shielding should be covered with conductive tape.

The best HF earthing is achieved if gaskets are mounted as near to the control connections as possible.

The gaskets must be installed to connect with the earthed unpainted surfaces of the gland plate to which they are mounted.

All connection tails should be as short as possible, and twisted in pairs where appropriate. The cable shield should be earthed to the connection end by a short pigtail.

The hole size in a gland plate required by these gaskets is typically 200 x 50 mm.



Figure 3-10 Essential points for control cabling transit.

Installation of accessories

The variety of accessories that can be installed is so large that only basic principles for selection and installation can be given for them.

Accessories can, however, be divided into two categories depending on how immune/sensitive they are. The protected device in this context means its ability to keep the Faraday cage closed. It is therefore recommended to use metal enclosed/shielded devices wherever such devices are available.

The rules for holes in the enclosure must be applied if there are devices forming a bridge between the clean side and the dirty side, which can be disturbed.

Typical open devices are fuses, switch fuses, contactors etc., which do not have a metal covering around them.

In general, such devices cannot be installed into the clean side without protective metallic shielding plates. The rules for holes in the enclosure must then be applied.

Some examples of protected and open devices are given in the chapter Practical examples.

Internal wiring

There are some basic rules for internal wiring:
- Always keep clean and dirty side cables separate and shielded from one another.
- Internal clean power connections with integrally filtered drive units, eg, from contactor to converter input, do not require shielded cables but may require de-coupling ferrite rings where they enter the converter input.

- Use twisted pair wires wherever possible.
- Use shielded twisted pairs for signal level outward and return wires exiting from the overall enclosure.
- Avoid mixing pairs with different signal types eg,
- 110 V AC, 230 V AC, 24 V DC, analogue, digital.
- Run wires along the metal surface and avoid wires hanging in free air, which can become an antenna.
- If plastic trunking is used, secure it directly to installation plates or the framework. Do not allow spans over free air, which could form an antenna.
- Keep power and control wiring separate.
- Use galvanically isolated (potential free) signals.
- Keep wires twisted as near the terminal as possible.
- Keep pigtails as short as possible.
- Earthing connections should be as short as possible in flat strip, multi-stranded or braided flexible conductors for low RFI impedance.



Figure 3-11 Principles of wiring inside CDM.

Control cables and cabling

The control cabling is a part of the Faraday cage as described in the section Conductive gaskets with control cables.

In addition to correct HF earthing there are some basic rules for control cabling:

- Always use shielded twisted pair cables:
  - double-shielded cable for analogue signals
  - single-shielded for other signals is acceptable, but double-shielded cable is recommended.
- Don't run 110/230 V signals in the same cable as lower signal level cables.
- Keep twisted pairs individual for each signal.
- Earth directly on the frequency converter side.

If instructions for the device at the other end of the cable specify earthing at that end, earth the inner shields at the end of the more sensitive device and the outer shield at the other end.

Route signal cables according to figure 3-12 whenever possible, and follow instructions given by the product specific manuals.



Figure 3-12 Routing principles of control cables.

There is more about control cabling in the "Grounding and cabling of the drive system" documents" and in product specific manuals.

Power cables

As the cables are part of the PDS they are also part of the Faraday cage. To be able to meet the EMC requirements, power cables with good shielding effectiveness must be used.

The purpose of the shield is to reduce radiated emission.

In order to be efficient, the shield must have good conductivity and cover most of the cable surface. If the cable shield is used as protective earthing, the shield cross area (or equivalent conductivity) must be at least 50 percent of the cross sectional area of the phase conductor.

The product specific manuals describe some cable types that can be used in mains supply and motor output.

If such types are not available locally, and because cable manufacturers have several different shield constructions, the types can be evaluated by the transfer impedance of the cable.

The transfer impedance describes the shielding effectiveness of the cable. It is commonly used with communication cables.

The cable can consist of either braided or spiral shield, and the shield material should preferably be either copper or aluminum.

The suitability for certain drive types is mentioned in the product specific manuals.



Figure 3-13 Galvanized steel or tinned copper wire with braided shield.



Figure 3-14 Layer of copper tape with concentric layer of copper wires.



Figure 3-15 Concentric layer of copper wires with an open helix of copper tape.

Transfer impedance

To meet the requirements for radiated emission, the transfer impedance must be less than 100 mΩ/m in the frequency range up to 100 MHz. The highest shielding effectiveness is achieved with a metal conduit or corrugated aluminum shield. Figure 3-16 shows typical transfer impedance values of different cable constructions. The longer the cable run, the lower the transfer impedance required.



Figure 3-16 Transfer impedance for power cables.

Use of ferrite rings

In particular cases, due to high emission levels, common mode inductors can be used in signal cables to avoid interfacing problems between different systems.

Common mode disturbances can be suppressed by wiring conductors through the common mode inductor ferrite core (figure 3-17).

The ferrite core increases inductance of conductors and mutual inductance, so common mode disturbance signals above a certain frequency are suppressed. An ideal common mode inductor does not suppress a differential mode signal.



Figure 3-17 Ferrite ring in signal wire.

The inductance (ie, the ability to suppress HF disturbances) can be increased by multiple turns of the signal wire.

When using a ferrite ring with power cable, all phase conductors should be led through the ring. The shielding and possible earth wire must be wired outside the ring to keep the common mode inductor effect. With power cables it is not normally possible to make multiple turns through the ring. The inductance can be increased by using several successive rings.

If for any reasons the installation instructions cannot be followed and therefore additional ferrites or filters are added afterwards, it is recommended that measurements be made to show conformance.



Figure 4-3 Basic scheme with by-pass.

Typical example of 12-pulse drive

In this case a 12-pulse rectifier is an IT system, unearthed due to the delta winding; therefore any filter in the line must be at the primary side of the phase shift transformer.

Experience has shown that, in this case, with short connections to the busbars, the earth shield between the transformer windings is not quite adequate for conducted emissions attenuation for use in the first environment. Therefore an RFI filter may be needed at the primary side of the transformer for EMC compliance. An RFI filter is not normally needed for the second environment.

For equipment fed from an IT system, a similar procedure can be used. An isolating transformer allows the PDS to be earthed and to use a suitable filter, for use in the first environment. The point of coupling is at a medium voltage and emissions may be considered at the next low voltage point of coupling in the system. The level of emissions should correspond to those for the appropriate environment. For definitions, see the Installation environments section in chapter 2.



Note: All equipment inside must be enclosed
Figure 4-4 12-pulse converter system fed at LV.



Figure 4-5 12-pulse converter system fed at LV (CDM, transformer and switch fuse have separate housing).

ABB drives

Technical guide No. 4
Guide to variable speed drives

Power and productivity
for a better world™

Technical guide No. 4
Guide to variable speed drives

4

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AFE61389211 REV C 12.5.2011

Contents

Chapter 1 - Introduction 7

General 7

Chapter 2 - Processes and their requirements 8

Why variable speed control? 8
Industrial segments with VSD processes 9
Variables in processing systems 10
Machines are used to alter materials' properties... 11
Well defined shape 11
Indefinite shape 11
...and to transport materials 12
Solid materials 12
Liquid materials 12
Gaseous materials 12

Chapter 3 - The workhorse of industry: the electric motor 13

Electric motors drive most machines 13
Motors convert electrical energy into mechanical energy 14
Frequency converters control electromagnetic induction 15
The efficiency of the drive system 16
Reversed rotation or torque is sometimes required 17
The load, friction and inertia resist rotation 18
The motor has to overcome the loading torque 19
The drive torque and load torque are equal at nominal speed 20

Chapter 4 - Variable volumes require some form of control 21

Variable material flow and input/output requirements 21
Simpler control methods 22
The best control method is VSD 23
Mechanical, hydraulic and electrical VSDs 24
Hydraulic coupling 24
DC drive 24
AC drive 24
Electrical VSDs dominate the market 25
Maintenance costs 25
Productivity 25
Energy saving 25
Higher quality 25
The AC drives market is growing fast 26

Chapter 5 - AC drive: the leading control method 27

The basic functions of an AC drive 27
A motor's load capacity curves with an AC drive 28

AC drive features for better process control 29
Reversing 30
Torque control 30
Eliminating mechanical vibrations 30
Power loss ride-through 31
Stall function 31
Slip compensation 32
Flying start 32
Environmental features 33
EMC 33

Chapter 6 - Cost benefits of AC drives 34

Technical differences between other systems and AC drives 35
No mechanical control parts needed 36
Factors affecting cost 37
Investment costs: mechanical and electrical components 38
The motor 38
The AC drive 38
Installation costs: throttling compared to AC drive 39
Operational costs: maintenance and drive energy 40
Total cost comparison 41

Chapter 7 - Index 42

Chapter 1 - Introduction

General

This guide continues ABB's technical guide series, describing different variable speed drives (VSD) and how they are used in industrial processes. Special attention has been given to electrical VSDs and especially to AC Drives.

The guide tries to be as practical as possible. No special knowledge of VSDs is required, although basic technical know-how is required to fully understand the terms and descriptions used.



Machines are used to alter materials' properties...

As mentioned earlier in this guide, working machine processes can be divided into two categories. The first category is material treatment, which is accomplished using various types of processing apparatus to alter a material's properties into another form.

Well defined shape

Processing apparatus can be divided into two groups according to the resulting shape of the material being treated. The shape can be either well defined or indefinite. Materials with a well-defined shape, such as paper, metal and wood, are processed with machinery. Examples are paper machines, rolling mills and saw mill lines.

Indefinite shape

Materials with an indefinite shape, such as various food products, plastics etc., are processed with plant equipment. Examples of this kind of equipment are margarine stirrers, and different kinds of centrifuges and extruders.



...and to transport materials

The second category consists of machines which transport material to a desired location. This group consists of conveying, dosing and pressure changing apparatus. These machines can be divided into three different sub-groups according to whether the type of material being treated is a solid, liquid or gas.

Solid materials

Solid materials, such as shipping containers, metal, wood, minerals and of course people, are transported by conveying apparatus. Such apparatus includes cranes, conveyors and elevators.

Liquid materials

Liquid materials, for example, water, oil or liquid chemicals, are transported by pumps.

Gaseous materials

Gaseous materials such as air are transported using fans, compressors or blowers. A special application of these machines is air conditioning.

In the diagram above, five different types of machines are presented. They either shape or transport different types of material, but all of them can be potentially used with Variable Speed Drives.


M
WM
Product or final material state
Material supply (and energy/ signal)
Power supply: fuel, gas pressure, mains
Energy control: conversion and/or regulation of energy supplied
The Motor: conversion of energy supplied into mechanical (rotary) energy
Transmission: conversion and/or regulation of mechanical energy provided
The w orking machine: processing of material (and energy/signal) using mechanical energy
points of possible variable spee



Frequency converters control electromagnetic induction

There are eight different switching positions in the inverter. In two positions, the voltage is zero, ie, when all the phases are connected to the same DC bus, either negative or positive. So in the remaining six switching positions there is voltage in the motor windings, and this voltage creates magnetic flux.

The diagram shows these six switching positions and the flux directions, which the voltage in the windings generates in each case. Voltage also generates current in the windings, the directions of which are marked with arrows in each phase.

In practice, control is not quite as simple as presented here. Magnetic flux generates currents in the rotor. These rotor currents complicate the situation. External interference, such as temperature or load changes, can also cause some control difficulties. Nevertheless, with today's technology and know-how, it is possible to effectively deal with interference.

Electrical VSDs also provide many additional benefits, such as energy savings, because the motor does not use more electrical energy than required. Furthermore, control is better than with conventional methods, because electrical VSDs also provide the possibility for stepless control.



The efficiency of the drive system

The total efficiency of the drive system depends on the losses in the motor and its control. Both drive and motor losses are thermal, so they appear as heat. Input power to the drive system is electrical in form, while output power is mechanical. That is why calculating the coefficient of efficiency (η) requires knowledge of both electrical and mechanical engineering.

Electrical input power $\boldsymbol{P}_{in}$ depends on voltage (***U***), current (***I***) and the power factor (cosφ). The power factor tells us what proportion of the total electric power is active power and how much is so called reactive power. To produce the required mechanical power, active power is required. Reactive power is needed to produce magnetisation in the motor.

Mechanical output power $\boldsymbol{P}_{out}$ depends on the required torque (***T***) and rotating speed (***n***). The greater the speed or torque required, the greater the power required. This has a direct effect on how much power the drive system draws from the electrical supply. As mentioned earlier, the frequency converter regulates the voltage, which is fed to the motor, and in this way directly controls the power used in the motor as well as in the process being controlled.

Electrical switching with transistors is very efficient, so the efficiency of the frequency converter is very high, from 0.97 to 0.99. Motor efficiency is typically between 0.82 and 0.97 depending on the motor size and its rated speed. So it can be said that the total efficiency of the drive system is always above 0.8 when controlled by a frequency converter.



Reversed rotation or torque is sometimes required

In some cases, reversed rotation of the motor is required. In addition, torque direction requirements might change. These factors combined form the so called “four quadrant drive”. The name comes from the four different quadrants (I to IV) shown in the diagram.

I quadrant: In the first quadrant, the motor is rotating clockwise. Because the torque is in the same direction as the speed, the drive is accelerating.

II quadrant: In the second quadrant, the motor is still rotating clockwise, but the torque is in the opposite direction, so the drive is decelerating.

III & IV quadrants: In the third and fourth quadrant, the motor is rotating counterclockwise and the drive is again accelerating or decelerating, depending on the torque direction.

With a frequency converter, torque direction changes can be implemented independent of the direction of rotation. To produce an efficient four quadrant drive, some kind of braking arrangement is required. This kind of torque control is especially required in crane applications, where the rotation direction might change, but the torque direction remains the same.



The load, friction and inertia resist rotation

The motor must produce the required torque to overcome the load torque. Load torque consists of friction, inertia of the moving parts and the load itself, which depends on the application. In the example in the diagram, the motor torque has to be greater than the load torque, which is dependent on the mass of the box, if the box is to rise.

Load factors change according to the application. For example, in a crusher, the load torque is dependent not only on friction and inertia, but also on the hardness of the crushed material. In fans and blowers, air pressure changes affect the load torque, and so on.



The motor has to overcome the loading torque

In any case, the loading torque has to be known before selecting the motor for the application. The required speed also has to be known. Only then can a suitable motor be selected for the application.

If the motor is too small, the requirements cannot be met and this might lead to serious problems. For example, in crane applications, a motor that is too small may not be able to lift the required load quickly enough to the desired height. It might even drop the load completely, as shown in the diagram. This could be disastrous for people working at the harbour or site where this crane would be used. To calculate the rated torque of the motor the following formula can be used:

$$T[Nm] = 9550 \times \frac{P[kW]}{n[1/min]}$$



The drive torque and load torque are equal at nominal speed

A motor's torque/speed curve is unique and has to be calculated for every motor type separately. A typical torque/speed curve is shown in the graph as T_m. As can be seen, the maximum load torque is reached just below nominal speed.

Load torque T_l usually increases with speed. Depending on the application it can be linear or quadratic. The motor will automatically accelerate until the load torque and motor torque are equal. This point is shown on the graph as the intersection of T_m and T_l. Actual torque (T_{act}) is shown on the y-axis and actual speed (n_{act}) on the x-axis.

These are the principles that govern how an ordinary squirrel cage motor works. With a frequency converter, optimal control performance can be obtained from the motor and the whole drive system. This will be introduced later in this guide.

Chapter 4 - Variable volumes require some form of control

In most processes there is at least one variable. This variable causes the need for process adjustment. Therefore variable processes and material volumes need some form of control.

In this chapter we will look at processes and their variables. We will also examine different control methods.



Typical cases

	Application	Input	Interference	Output
1	Submersible pump	Water level		
2	Pump application	Water level		Water flow
3	FD fan	Heat demand	Atmospheric pressure	
4	Sawmill line	Log diameter	Hardness of wood	
5	Screw conveyor			Material volume
6	Feeder		Hardness of material	Load
7	Grinder		Wear of the grind	

Variable material flow and input/output requirements

There may be many different parameters involved in a process, the most common being input, output and interference. These parameters may need to be constant or they may need to be changed according to a preset pattern. As discussed in the first chapter, there are always inputs and outputs present in a process and, in almost every case, interference as well.

In some processes there is no interference and the input is constant. This kind of process works without any variable speed control. However, if the output parameters need to be changed, the input is variable or there is interference present, then variable speed control might be the solution to fulfilling the process requirements.

The above table lists some processes in which variable speed control is required. It also shows the reasons for the control; input, interference or output.



Simpler control methods

There are many simpler control methods in existence such as throttling or bypass control. The construction of such equipment is usually very simple and the investment may look cost effective at first.

However, there are many drawbacks. For example the optimal process capacity, which gives the best quality of the process, is very difficult to achieve with simple control. An increase in production capacity usually requires reconstruction of the whole process and with each direct on-line startup there is a risk of electrical and/or mechanical damage.

The simple control methods are also energy consuming, so in addition to the total operating cost being higher than with VSDs, the environmental effects, such as CO_2 emissions from power plants, also increase. Therefore, the total life-cycle cost of investment in simple control methods is much higher than with VSDs.



The best control method is VSD

The best control method for most systems is VSD. Imagine you are driving a car for example. If you are driving on a highway and entering a populated area, you need to reduce speed so that you don't risk your own and other peoples' lives.

The best possible way to do this is of course to reduce motor rotation speed by taking your foot off the gas pedal and, if necessary, changing to a lower gear. Another possibility would be to use the same gear, keep your foot on the gas and reduce speed simply by braking. This would not only cause wear on the engine and brakes, but also use a lot of fuel and reduce your overall control of the vehicle. Furthermore, the original goal of reducing speed without risking your own and other peoples' lives would not have been achieved.



Mechanical, hydraulic and electrical VSDs

Above are the four most common VSDs in the industrial sector. Mechanical variable speed control usually uses belt drives, and is controlled by moving conical pulleys manually or with positioning motors.

Hydraulic coupling

In hydraulic coupling, the turbine principle is used. By changing the volume of oil in the coupling, the speed difference between the driving and driven shafts changes. The oil amount is controlled with pumps and valves.

DC drive

In the DC drive, a DC converter changes the motor supply voltage fed to the DC motor. In the motor, a mechanical inverter, a commutator, changes direct current to alternating current.

AC drive

In the frequency converter or AC drive, a standard squirrel cage motor is used, so no mechanical inverters are required. The speed of the motor is regulated by a frequency converter that changes the frequency of the motor voltage, as presented earlier in this guide. The frequency converter itself is controlled with electrical signals.

The diagram shows the location of the control equipment for each type of VSD. In mechanical and hydraulic VSDs, the control equipment is located between the motor and the working machine, which makes maintenance very difficult.

In electrical VSDs, all control systems are situated in an electrical equipment room and only the driving motor is in the process area. This is just one benefit of electrical VSDs. Other benefits are presented on the following page.

Chapter 5 - AC drive: the leading control method

Taking into account everything presented so far, we can confidently say that the AC drive is the leading control method. In the following chapter we will take a closer look at the different features of the AC drive, and the levels of performance the drive can offer.



The basic functions of an AC drive

In this diagram, the basic functions of an AC drive are presented. There are four different components in AC drive motor control. These components are the user interface, the motor, the electrical supply and the process interface.

An electrical supply feeds the required electricity to the drive; one selection criteria for the drive is the supply voltage and its frequency. The AC drive converts the frequency and voltage and feeds the motor. This conversion process is controlled by signals from the process or user via the process and user interfaces.

The user interface provides the ability to observe the AC drive and obtain different process information via the drive. This makes the drive easy to integrate with other process control equipment and overriding process control systems.



A motor's load capacity curves with an AC drive

If the motor is driven without a frequency converter, its load capacity curves cannot be modified. It will produce a specified torque at certain speed and maximum torque cannot be exceeded.

With a frequency converter drive, there are different loading options. The standard curve, Curve 1 in the diagram, can be used continuously. Other curves can only be used for certain periods of time, because the motor's cooling system is not designed for this kind of heavy use.

These higher load capacity levels might be needed, for example, during startup. In certain applications, as much as twice the amount of torque is required when starting. With a frequency converter this is possible, meaning that a motor can be dimensioned according to its normal use. This reduces the investment cost.

To be able to use these features it is very important that the load, the AC drive and the motor are compatible. Otherwise the motor or the converter will overheat and be damaged.

Important features:
- inputs and outputs
- reversing function
- ramp times acceleration/deceleration
- variable torque V/Hz settings
- torque boosting
- eliminating mechanical vibrations
- load limits to prevent nuisance faults
- power loss ride-through
- stall function
- slip compensation
- flying start

AC drive features for better process control

AC drives also have other internal features and functions which are sometimes required for better process control. Examples of these features are listed in the diagram. With inputs and outputs for example, different kinds of process information can be fed to the drive and it will control the motor accordingly. Alternatively, the load can be limited to prevent nuisance faults and to protect the working machine and the whole drive system.

In the following sections the listed features are presented in more detail.



Reversing

Reversing the motor rotation is simple to accomplish with an AC drive. With ABB's frequency converters it can be achieved simply by pressing one button. Furthermore, it is possible to set different acceleration and deceleration ramp times. The ramp form can also be modified according to the user's wishes. In the diagram (above, left) an S-ramp has been presented. Another possibility could be a linear ramp.

Torque control

Torque control is relatively simple with an AC drive. Torque boosting, which was presented earlier, is necessary if a very high starting torque is required. Variable torque ***U/f*** settings mean that maximum torque can be achieved at a lower speed of rotation than normal.

Eliminating mechanical vibrations

Mechanical vibrations can be eliminated by by-passing critical speeds. This means that when a motor is accelerated close to its critical speed, the drive will not allow the actual speed of the motor to follow the reference speed. When the critical point has been passed, the motor will return to the regular curve very quickly and pass the critical speed.



Power loss ride-through

The power loss ride-through function is used if the incoming supply voltage is cut off. In such a situation, the AC drive will continue to operate using the kinetic energy of the rotating motor. The drive will be fully operational as long as the motor rotates and generates energy for the drive.

Stall function

With an AC drive, the motor can be protected in a stall situation with the stall function. It is possible to adjust supervision limits and choose how the drive reacts to the motor stall condition. Protection is activated if three conditions are met at the same time.

1. The drive frequency has to be below the preset stall frequency.

2. The motor torque has to rise to a certain limit, calculated by the drive software.

3. The final condition is that the motor has been in the stall limit for longer than the time period set by the user.



Slip compensation

If the motor load torque is increased, the speed of the motor will decrease as shown in the diagram (above, left). To compensate for this slip, the torque/speed curve can be modified with the frequency converter so that torque increase can be accomplished with the same speed as previously.

Flying start

The flying start feature is used when a motor is connected to a flywheel or a high inertia load. The flying start works even without a speed feedback. In case of rotating motor, the inverter is first started with a reduced voltage and then synchronised to the rotating rotor. After synchronised the voltage and the speed are increased to the corresponding levels.



Environmental features

Any drive system has to handle different environmental stresses such as moisture or electrical disturbances. The squirrel cage motor is very compact and can be used in very hostile conditions. The IP54 degree of protection guarantees that it can work in a dusty environment and that it can bear sprinkling water from any direction.

The frequency converter usually has an IP21 degree of protection. This means that it is not possible to touch the live parts and that vertically dripping water will not cause any harm. If a higher degree of protection is required, it can be obtained, for example, by installing the drive inside a cabinet with the required degree of protection. In such cases, it is essential to ensure that the temperature inside the cabinet will not exceed the allowed limits.

EMC

Another important environmental feature is electromagnetic compatibility (EMC). It is very important that a drive system fulfills the EMC directives of the European Union. This means that the drive system can bear conductive and radiative disturbances, and that it does not send any conductive or radiative disturbances itself either to the electrical supply or the surrounding environment.

If you require more information about the EMC directives and their effects on drives, please refer to ABB's Technical guide No. 3, EMC Compliant Installation and Configuration for a Power Drive System.

Chapter 6 - Cost benefits of AC drives

In addition to their technical advantages, AC drives also provide many cost benefits. In this chapter, these benefits are reviewed, with the costs divided into investment, installation and operational costs.



At the moment there are still plenty of motors sold without variable speed AC drives. This pie chart shows how many motors below 2.2 kW are sold with frequency converters, and how many without. Only 3 percent of motors in this power range are sold each year with a frequency converter; 97 percent are sold without an AC drive.

This is astonishing considering what we have seen so far in this guide. Even more so after closer study of the costs of an AC drive compared to conventional control methods. But first let's review AC drive technology compared to other control methods.



Technical differences between other systems and AC drives

AC drive technology is completely different from other, simpler control methods. It can be compared, for example, to the difference between a zeppelin and a modern airplane.

We could also compare AC drive technology to the development from a floppy disk to a CD-ROM. Although it is a simpler information storage method, a floppy disk can only handle a small fraction of the information that a CD-ROM can.

The benefits of both these innovations are generally well known. Similarly, AC drive technology is based on a totally different technology to earlier control methods. In this guide, we have presented the benefits of the AC drive compared to simpler control methods.



No mechanical control parts needed

To make a proper cost comparison, we need to study the configurations of different control methods. Here we have used pumping as an example. In traditional methods, there is always a mechanical part and an electrical part.

In throttling you need fuses, contactors and reactors on the electrical side and valves on the mechanical side. In On/Off control, the same electrical components are needed, as well as a pressure tank on the mechanical side. The AC drive provides a new solution. No mechanics are needed, because all control is already on the electrical side.

Another benefit, when thinking about cost, is that with an AC drive we can use a regular 3-phase motor, which is much cheaper than the single phase motors used in other control methods. We can still use 220 V single phase supply, when speaking of power below 2.2 kW.

Conventional methods:	AC drive:
both electrical and mechanical parts	all in one
many electrical parts	only one electrical component
mechanical parts need regular maintenance	no mechanical parts, no wear and tear
mechanical control is energy consuming	saves energy

Factors affecting cost

This list compares the features of conventional control methods with those of the AC drive, as well as their effect on costs. In conventional methods there are both electrical and mechanical components, which usually have to be purchased separately. The costs are usually higher than if everything could be purchased at once.

Furthermore, mechanical parts wear out quickly. This directly affects maintenance costs and in the long run, maintenance is a very important cost item. In conventional methods there are also many electrical components. The installation cost is at least doubled when there are several different types of components rather than only one.

And last but not least, mechanical control is very energy consuming, while AC drives practically save energy. This not only helps reduce costs, but also helps minimise environmental impact by reducing emissions from power plants.



Investment costs: mechanical and electrical components

In this graph, the investment structure as well as the total price of each pump control method is presented. Only the pump itself is not added to the costs because its price is the same regardless of whether it's used with an AC drive or valves. In throttling, there are two possibilities depending on whether the pump is used in industrial or domestic use. In an industrial environment there are stricter requirements for valves and this increases costs.

The motor

As can be seen, the motor is much more expensive for traditional control methods than for the AC drive. This is due to the 3-phase motor used with the AC drive and the single phase motor used in other control methods.

The AC drive

The AC drive does not need any mechanical parts, which reduces costs dramatically. Mechanical parts themselves are almost always less costly than a frequency converter, but electrical parts also need to be added to the total investment cost.

After taking all costs into account, an AC drive is almost always the most economical investment, when compared to different control methods. Only throttling in domestic use is as low cost as the AC drive. These are not the total costs, however. Together with investment costs we need to look at installation and operational costs.

	Throttling	AC drive
Installation material	20 USD	10 USD
Installation work	5h x 65 USD = 325 USD	1h x 65 USD = 65 USD
Commissioning work	1h x 65 USD = 65 USD	1h x 65 USD = 65 USD
Total	410 USD	140 USD
Savings in installation: 270 USD!		

Installation costs: throttling compared to AC drive

Because throttling is the second lowest investment after the AC drive, we will compare its installation and operating costs to the cost of the AC drive. As mentioned earlier, in throttling there are both electrical and mechanical components. This means twice the amount of installation material is needed.

Installation work is also at least doubled in throttling compared to the AC drive. To install a mechanical valve into a pipe is not that simple and this increases installation time. To have a mechanical valve ready for use usually requires five hours compared to one hour for the AC drive. Multiply this by the hourly rate charged by a skilled installer to get the total installation cost.

The commissioning of a throttling-based system does not usually require more time than commissioning an AC drive based system. One hour is usually the time required in both cases. So now we can summarise the total installation costs. As you can see, the AC drive saves up to USD 270 per installation. So even if the throttling investment costs were lower than the price of a single phase motor (approximately USD 200), the AC drive would pay for itself before it has even worked a second.

	Throttling	AC drive saving 50 percent
Power required	0.75 kW	0.37 kW
Annual energy 4000 hours/year	3000 kWh	1500 kWh
Annual energy cost with 0.1 USD/kWh	300 USD	150 USD
Maintenance/year	40 USD	5 USD
Total cost/year	340 USD	155 USD
Savings in one year: 185 USD!		

Operational costs: maintenance and drive energy

In many surveys and experiments it has been proved that a 50 percent energy saving is easily achieved with an AC drive. This means that where power requirements with throttling would be 0.75 kW, with the AC drive it would be 0.37 kW. If a pump is used 4000 hours per year, throttling would need 3000 kWh and the AC drive 1500 kWh of energy per year.

To calculate the savings, we need to multiply the energy consumption by the energy price, which varies depending on the country. Here USD 0.1 per kWh has been used.

As mentioned earlier, mechanical parts wear a lot and this is why they need regular maintenance. It has been estimated that whereas throttling requires USD 40 per year for service, maintenance costs for an AC drive would be USD 5. In many cases however, there is no maintenance required for a frequency converter.

Therefore, the total savings in operating costs would be USD 185, which is approximately half of the frequency converter's price for this power range. This means that the payback time of the frequency converter is two years. So it is worth considering that instead of yearly service for an old valve it might be more profitable to change the whole system to an AC drive based control. To retrofit an existing throttling system the pay-back time is two years.



Total cost comparison

In the above figure, all the costs have been summarised. The usual time for an operational cost calculation for this kind of investment is 10 years. Here the operational costs are rated to the present value with a 10 percent interest rate.

In the long run, the conventional method will be more than twice as expensive as a frequency converter. Most of the savings with the AC drive come from the operational costs, and especially from the energy savings. It is in the installation that the highest individual savings can be achieved, and these savings are realised as soon as the drive is installed.

Taking the total cost figure into account, it is very difficult to understand why only 3 percent of motors sold have a frequency converter. In this guide we have tried to present the benefits of the AC drive and why we at ABB think that it is absolutely the best possible way to control your process.

Chapter 7 - Index

A
ABB 30, 33, 41
AC drive 24, 25, 26, 27, 28, 29, 30, 31, 34, 35, 36, 37, 38, 39, 40, 41
AC drives market 26
AC motor 13, 14
active power 16

B
belt drives 24
blowers 18
braking 17, 23
bypass control 22

C
coefficient of efficiency 16
Commissioning 39
commutator 24, 26
contactors 36
crane 17, 19
critical speed 30
crusher 18
current 14, 15, 16, 24

D
DC bus 14, 15
DC converter 24
DC drive 24, 26
DC motor 24, 26
Direct on-line starting 25
drive frequency 31
drive software 31
drive system 16, 20, 29, 33

E
electrical disturbances 33
electrical equipment room 24
electrical supply 16, 27, 33
electromagnetic compatibility 33
electromagnetic induction 14, 15
EMC 33
EMC directives 33
energy 14, 15, 22, 25, 26, 31, 37, 40, 41

F
fans 18
flux 14, 15
flying start 29, 32
flywheel 32
four quadrant drive 17
frequency converter 14, 16, 17, 20, 24, 28, 32, 33, 34, 40, 41
friction 18
fuses 36

H
harbour 19
hydraulic coupling 24

I
industrial processes 13
inertia 18, 32
input power 16
interference 15, 21
inverter 14, 15, 24
IP21 33
IP54 33

L
linear ramp 30
load capacity curves 28

M
machine 11, 13, 24, 29
magnetic flux 14, 15
maintenance 24, 25, 26, 37, 40
mechanical power 16
mechanical vibrations 29, 30
motor load 32
motor losses 16
motor phase 14
motor size 16
motor stall condition 31
motor windings 14, 15

N
nuisance faults 29

O
output power 16

P
power factor 16
power loss ride-through 29, 31
power plants 22, 37
process control 25, 26, 27, 29
processing system 10
pump 24, 25, 36, 40

R
rated speed 16
Reactive power 16
reactive power 16
reactors 36
rectifier 14
reference speed 30
reversing function 29
right hand rule 14

S
S-ramp 30
slip 14, 29, 32
squirrel cage motor 20, 24, 33
stall frequency 31
stall function 29, 31
stator 14
stepless control 15

T
temperature 15, 33
throttling 22, 36, 39, 40
torque 16, 17, 18, 19, 20, 28, 29, 30, 31, 32
transistors 16

V
valve 40
valves 24, 36
variable speed control 8, 21, 24
variable speed drives 1, 3
voltage 14, 15, 16, 24, 27, 31
VSD 9, 15, 22, 23, 24, 25, 26

Contact us

For more information contact
your local ABB representative or visit:

www.abb.com/drives
www.abb.com/drivespartners

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.

3AFE61389211 REV C EN 12.5.2011 #15677

Power and productivity
for a better world™

ABB

ABB drives

Technical guide No. 5
Bearing currents in modern AC drive systems

Power and productivity
for a better world™

Technical guide No. 5
Bearing currents in modern AC drive systems

5

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AFE64230247 REV C EN 27.4.2011

Contents

Chapter 1 - Introduction 7

General 7
Avoiding bearing currents 7

Chapter 2 - Generating bearing currents 8

High frequency current pulses 8
Faster switching 9
How are HF bearing currents generated? 9
Circulating current 9
Shaft grounding current 9
Capacitive discharge current 10
Common mode circuit 10
Stray capacitances 11
How does the current flow through the system? 12
Voltage drops 13
Common mode transformer 14
Capacitive voltage divider 15

Chapter 3 - Preventing high frequency bearing current damage 17

Three approaches 17
Multicore motor cables 17
Short impedance path 17
High frequency bonding connections 18
Follow product specific instructions 19
Additional solutions 19
Measuring high frequency bearing currents 19
Leave the measurements to the specialists 20

Chapter 4 - References 21

Chapter 5 - Index 22

Chapter 1 - Introduction

General

Some new drive installations can have their bearings fail only a few months after startup. Failure can be caused by high frequency currents, which flow through the motor bearings.

While bearing currents have been around since the advent of electric motors, the incidence of damage they cause has increased during the last few years. This is because modern variable speed drives with their fast rising voltage pulses and high switching frequencies can cause current pulses through the bearings whose repeated discharging can gradually erode the bearing races.

Avoiding bearing currents

To avoid damage occurring, it is essential to provide proper earthing paths and allow stray currents to return to the inverter frame without passing through the bearings. The magnitude of the currents can be reduced by using symmetrical motor cables or inverter output filtering. Proper insulation of the motor bearing construction breaks the bearing current paths.

Chapter 2 - Generating bearing currents

High frequency current pulses

Bearing currents come in several different guises. However, while modern motor design and manufacturing practices have nearly eliminated the low frequency bearing currents induced by the asymmetry of the motor, the rapid switching in modern AC drive systems may generate high frequency (HF) current pulses through the bearings. If the energy of these pulses is sufficiently high, metal transfers from the ball and the races to the lubricant. This is known as electrical discharge machining or EDM. The effect of a single pulse is insignificant, but a tiny EDM pit is an incontinuity that will collect more pulses and expand into a typical EDM crater. The switching frequency of modern AC drives is very high and the vast number of pulses causes the erosion to quickly accumulate. As a result, the bearing may need replacing after only a short time in service.

High frequency bearing currents have been investigated by ABB since 1987. The importance of system design has been highlighted in the last few years. Each individual item involved, such as the motor, the gearbox or the drive controller, is the product of sophisticated manufacturing techniques and normally carries a favourable mean time between failure (MTBF) rate. It is when these components are combined and the installed system is looked upon as a whole, that it becomes clear that certain installation practices are required.



Figure 1: Bearing currents can cause “bearing fluting”, a rhythmic pattern on the bearing’s races.

Faster switching

Current AC drive technology, incorporating insulated gate bipolar transistors (IGBT), creates switching events 20 times faster than those considered typical ten years ago. Recent years have seen a rising number of EDM-type bearing failures in AC drive systems relatively soon after startup, within one to six months. The extent to which this occurs depends on the AC drive system architecture and the installation techniques used.

How are HF bearing currents generated?

The source of bearing currents is the voltage that is induced over the bearing. In the case of high frequency bearing currents, this voltage can be generated in three different ways. The most important factors that define which mechanism is prominent, are the size of the motor and how the motor frame and shaft are grounded. The electrical installation, meaning a suitable cable type and proper bonding of the protective conductors and the electrical shield, plays an important role. Du/dt of the AC drive power stage components and the DC-link voltage level affect the level of bearing currents.

Circulating current

In large motors, high frequency voltage is induced between the ends of the motor shaft by the high frequency flux circulating around the stator. This flux is caused by a net asymmetry of capacitive current leaking from the winding into the stator frame along the stator circumference. The voltage between the shaft ends affects the bearings. If it is high enough to overcome the impedance of the bearings' oil film, a current that tries to compensate the net flux in the stator starts to flow in the loop formed by the shaft, the bearings and the stator frame. This current is a circulating type of high frequency bearing current.

Shaft grounding current

The current leaking into the stator frame needs to flow back to the inverter, which is the source of this current. Any route back contains impedance, and therefore the voltage of the motor frame increases in comparison to the source ground level. If the motor shaft is earthed via the driven machinery, the increase of the motor frame voltage is seen over the bearings. If the voltage rises high enough to overcome the impedance of the drive-end bearing oil film, part of the current may flow via the drive-end bearing, the shaft and the driven machine back to the inverter. This current is a shaft grounding type of high frequency bearing current.

Capacitive discharge current

In small motors, the internal voltage division of the common mode voltage over the internal stray capacitances of the motor may cause shaft voltages high enough to create high frequency bearing current pulses. This can happen if the shaft is not earthed via the driven machinery while the motor frame is earthed in the standard way for protection.

Common mode circuit

High frequency bearing currents are a consequence of the current flow in the common mode circuit of the AC drive system.

A typical three-phase sinusoidal power supply is balanced and symmetrical under normal conditions. That is, the vector sum of the three phases always equals zero. Thus, it is normal that the neutral is at zero volts. However, this is not the case with a PWM switched three-phase power supply, where a dc voltage is converted into three phase voltages. Even though the fundamental frequency components of the output voltages are sy mmetrical and balanced, it is impossible to make the sum of three output voltages instantaneously equal to zero with two possible output levels available. The resulting neutral point voltage is not zero. This voltage may be defined as a common mode voltage source. It is measurable at the zero point of any load, eg. the star point of the motor winding.



Figure 2: This schematic shows the phase voltages of a typical three phase PWM power supply and the average of the three, or neutral point voltage, in a modern AC drive system. The neutral voltage is clearly not zero and its presence can be defined as a common mode voltage source. The voltage is proportional to the DC bus voltage, and has a frequency equal to the inverter switching frequency.

Any time one of the three inverter outputs is changed from one of the possible potentials to another, a current proportional to this voltage change is forced to flow to earth via the earth capacitances of all the components of the output circuit. The current flows back to the source via the earth conductor and stray capacitances of the inverter, which are external to the three phase system. This type of current, which flows through the system in a loop that is closed externally to the system, is called common mode current.



Figure 3: An example of the common mode current at the inverter output. The pulse is a superposition of several frequencies due to the different natural frequencies of the parallel routes of common mode current.

Stray capacitances

A capacitance is created any time two conductive components are separated by an insulator. For instance, the cable phase wire has capacitance to the PE-wire separated by PVC insulation, for example, and the motor winding turn is insulated from the frame by enamel coating and slot insulation, and so has a value of capacitance to the motor frame. The capacitances within a cable and especially inside the motor are very small. A small capacitance means high impedance for low frequencies, thus blocking the low frequency stray currents. However, fast rising pulses produced by modern power supplies contain frequencies so high that even small capacitances inside the motor provide a low impedance path for current to flow.

Common mode transformer

The largest share of the motor's stray capacitance, is formed between the stator windings and the motor frame. This capacitance is distributed around the circumference and length of the stator. As the current leaks into the stator along the coil, the high frequency content of the current entering the stator coil is greater than the current leaving.

This net current produces a high frequency magnetic flux that will circulate in the stator laminations, inducing an axial voltage in the shaft ends. If the voltage becomes large enough, a high frequency circulating current can flow, internal to the motor, through the shaft and both bearings. The motor can, in this case, be thought of as a transformer, where the common mode current flowing in the stator frame acts as a primary and induces the circulating current into the rotor circuit or secondary. This bearing current is considered to be the most damaging with typical peak values of 3 to 20 amps depending on the rated power of the motor, du/dt of the AC drive power stage components and DC-link voltage level.



Figure 7: The high frequency axial shaft voltage can be thought of as the resultant of a transformer effect, in which the common mode current flowing in the stator frame acts as a primary, and induces the circulating current into the rotor circuit or secondary.

Another version of circulating bearing current occurs when, the current, instead of circulating completely inside the motor, flows via the shaft and the bearings of the gearbox or driven machinery and in a structural element that is both external and common to the motor and the driven machine. The origin of the current is the same as in the current circulating inside the motor. An example of this "vagabond" circulating bearing current is shown in figure 8.



Figure 8: "Vagabond" circulating bearing current, where the current loop is external to the motor.

Capacitive voltage divider

Other stray capacitances are also present in the motor, such as the capacitance between the stator windings and the rotor, or that existing in the motor's airgap between the stator iron and the rotor. The bearings themselves may even have stray capacitance.

The existence of capacitance between the stator windings and the rotor effectively couples the stator windings to the rotor iron, which is also connected to the shaft and the bearing's inner races. Fast changes in the common mode current from the inverter can not only result in currents in the capacitance around the circumference and length of the motor, but also between the stator windings and the rotor into the bearings.



Figure 9: Common mode loop of variable speed drive, showing stator, rotor and bearing stray capacitances.

The current flow into the bearings can change rapidly, as this depends on the physical state of the bearing at any one time. For instance, the presence of stray capacitance in the bearings is only sustained for as long as the balls of the bearings are covered in oil or grease and are non-conducting. This capacitance, where

the induced shaft voltage builds up, can be short-circuited if the bearing voltage exceeds the threshold of its breakover value or if a “high spot” on a ball breaks through the oil film and makes contact with both bearing races. At very low speed, the bearings have metallic contact since the balls have not risen on an oil film.

Generally, the bearing impedance governs the voltage level at which the bearings start to conduct. This impedance is a non-linear function of bearing load, temperature, speed of rotation and lubricant used, and the impedance varies from case to case.

Chapter 3 - Preventing high frequency bearing current damage

Three approaches

There are three approaches used to affect high frequency bearing currents: a proper cabling and earthing system; breaking the bearing current loops; and damping the high frequency common mode current. All these aim to decrease the bearing voltage to values that do not induce high frequency bearing current pulses at all, or damp the value of the pulses to a level that has no effect on bearing life. For different types of high frequency bearing currents, different measures need to be taken.

The basis of all high frequency current mastering is the proper earthing system. Standard equipment earthing practices are mainly designed to provide a sufficiently low impedance connection to protect people and equipment against system frequency faults. A variable speed drive can be effectively earthed at the high common mode current frequencies, if the installation follows three practices:

Multicore motor cables

Use only symmetrical multicore motor cables. The earth (protective earth, PE) connector arrangement in the motor cable must be symmetrical to avoid bearing currents at fundamental frequency. The symmetricity of the PE-conductor is achieved by a conductor surrounding all the phase leads or a cable that contains a symmetrical arrangement of three phase leads and three earth conductors.



Figure 10: Recommended motor cable with symmetrical core configuration.

Short impedance path

Define a short, low impedance path for common mode current to return to the inverter. The best and easiest way to do this is to use shielded motor cables. The shield must be continuous and of good conducting material, ie, copper or aluminium and the connections at both ends need to be made with 360° termination.

Figures 11a and 11b show 360° terminations for European and American cabling practices.

Figure 11 a: Proper 360° termination with European cabling practice. The shield is connected with as short a pigtail as possible to the PE terminal. To make a 360° high frequency connection between the EMC sleeve and the cable shield, the outer insulation of the cable is stripped away.



Figure 11 b: Proper 360° termination with American cabling practice. An earthing bushing should be used on both ends of the motor cable to effectively connect the earth wires to the armour or conduit.

High frequency bonding connections

Add high frequency bonding connections between the installation and known earth reference points to equalise the potential of affected items, using braided straps of copper 50 - 100 mm wide; flat conductors will provide a lower inductance path than round wires. This must be made at the points where discontinuity between the earth level of the inverter and that of the motor is suspected. Additionally it may be necessary to equalise the potential between the frames of the motor and the driven machinery to short the current path through the motor and the driven machine bearings.



Figure 12: HF bonding strap

Follow product specific instructions

Although the basic principles of installations are the same, for different products suitable installation practices may differ. Therefore, it is essential to carefully follow the installation instructions given in product specific manuals.

Additional solutions

Breaking the bearing current loops is achieved by insulating the bearing construction. The high frequency common mode current can be damped by using dedicated filters. As a manufacturer of both inverters and motors, ABB can offer the most appropriate solution in each case as well as detailed instructions on proper earthing and cabling practices.

Measuring high frequency bearing currents

Monitoring the bearing condition must be conducted with established vibration measurements.

It is impossible to measure bearing currents directly from a standard motor. But if high frequency bearing currents are suspected, field measurements can be taken to verify the existence of suspected current loops. Measuring equipment needs to have wide bandwidth (minimum 10 kHz to 2 MHz) capable of detecting peak values of at least 150 to 200 A and RMS values at least down to 10 mA. The crest factor of measured signals is seldom less than 20. The current may flow in unusual places, such as rotating shafts. Thus, special equipment and experienced personnel are needed.

ABB uses a specially designed, flexible, air-cored, Rogowski-type current sensor with dedicated accessories and has vast experience of over one thousand measured drives in different applications worldwide.

The most important measurement points are within the motor. During measurements, the motor speed needs to be at least 10 percent of the nominal for the bearings to rise on the oil film. As an example, basic measurements are shown in figure 13. Figure 14 shows examples of measured current waveforms. GTO (gate turn-off thyristor) inverters were used mainly in the 1980s and IGBT inverters are used today. Note the different scale in the various graphs.



Figure 13: Basic measurements: A) circulating current measured with a jumper, B) shaft grounding current.

A) Circulating current



GTO-inverter, 5 μs/div, 2 A/div **IGBT-inverter, 5 μs/div, 2 A/div**

B) Shaft grounding current



GTO-inverter, 2 μs/div, 10 A/div **IGBT-inverter, 5 μs/div, 500 mA/div**

Figure 14: Examples of current waveforms at the measuring points shown in Figure 13.

Leave the measurements to the specialists

Since suitable commercial measurement equipment is not available on the market and specialised experience is needed to make the measurements and interpret the results, it is advisable that bearing current measurements are made by dedicated personnel only.

Chapter 4 - References

1. **Grounding and Cabling of the Drive System**, ABB Industry Oy, 3AFY 61201998 R0125

2. **A New Reason for Bearing Current Damage in Variable Speed AC Drives**
   by J. Ollila, T. Hammar, J. Iisakkala, H. Tuusa. EPE 97, 7th European Conference on Power Electronics and Applications, 8-10 September 1997. Trondheim, Norway.

3. **On the Bearing Currents in Medium Power Variable Speed AC Drives**
   by J. Ollila, T. Hammar, J. Iisakkala, H. Tuusa. proceedings of the IEEE IEDMC in Milwaukee, May 1997.

4. **Minimizing Electrical Bearing Currents in Adjustable Speed Drive Systems**
   by Patrick Link. IEEE IAS Pulp & Paper Conference Portland, ME, USA. June 1998.

5. **Instruction on Measuring Bearing Currents with a Rogowski Coil,** ABB Industry Oy, 3BFA 61363602.EN.

6. **Laakerivirta ja sen minimoiminen säädettyjen vaihtovirtakäyttöjen moottoreissa,**
   I. Erkkilä, Automaatio 1999, 16.9.1999, Helsinki, Finland. (In Finnish).

7. **High Frequency Bearing Currents in Low Voltage Asynchronous Motors,**
   ABB Motors Oy and ABB Industry Oy, 00018323.doc.

8. **Bearing Currents in AC Drives**
   by ABB Industry Oy and ABB Motors Oy. Set of overheads in LN database “Document Directory Intranet” on ABB_FI01_SPK08/FI01/ABB

9. **The Motor Guide**
   GB 98-12.

See also product specific installation manuals.

Chapter 5 - Index

Symbols
360° termination 17, 18
360° terminations 18

A
ABB 19
AC drive 9, 10
armour 18
axial shaft voltage 14, 15
axial voltage 14

B
balls 15, 16
bearing 8, 9, 15, 16
bearing current 9, 14, 20
bearing current loops 17, 19
bearing current paths 7
bearing currents 7, 9, 17, 19
bearing fluting 8
bearing races 7
bearings 7, 8, 14, 15, 16
bearing voltage 16
bonding connections 18
braided straps 18

C
cable 17
cable capacitance 12
cable shield 18
circulating current 14
common mode cable 12
common mode current 11, 12, 13, 14, 15, 17, 19
common mode loop 15
common mode voltage 10, 12
conduit 18
crest factor 19
current pulses 7

D
DC bus voltage 10
dedicated filters 19
drive controller 8
driven machine 9, 18
driven machinery 10, 13, 14

E
earthing paths 7
EDM 9
EDM crater 8
electrical discharge machining 8
electrical shield 9
electric motors 7

F
field measurements 19
flat conductors 18
frame 18

G
gearbox 8, 13, 14
GTO (gate turn-off thyristor) inverters 20

H
high frequency bearing currents 9
high frequency bearing voltage 9
high frequency circulating current 14
high frequency current mastering 17
high frequency current pulses 8
high frequency flux 9
high switching frequencies 7

I
IGBT inverters 20
induced shaft voltage 16
insulated gate bipolar transistors (IGBT) 9
internal voltage division 10
inverter 9, 11, 12, 13, 15, 17, 18
inverter frame 7, 13
inverter output filtering 7
inverter power supply 12
inverter switching frequency 10

L
low frequency bearing currents 8

M
machine 13
machinery 13, 18
magnetic flux 14
mean time between failure (MTBF) 8
metallic coupling 13
modern drive systems 8
motor 8, 11, 12, 14, 15, 17, 18, 19
motor bearing 7
motor cable 17, 18
motor frame 9, 10, 11, 12, 13, 14
motors 9, 10, 19
motor shaft 9, 13
motor windings 12

N
neutral point voltage 10

O
oil film 9, 20

P
primary 14
PWM 10, 12

R
races 8, 16
Rogowski-type current sensor 19
rotor 14, 15
rotor circuit 14

S
secondary 14
shaft 10, 14, 15
shaft ends 14
shaft voltages 10
shield 17
stator 9, 14, 15
stator frame 9, 13, 14
stator laminations 14
stator windings 14, 15
stray capacitance 10, 11, 12, 14, 15
stray currents 7
symmetrical motor cables 7
symmetrical multicore motor cables 17

T
three-phase sinusoidal power supply 10
three phase power supply 10
transformer 14

V
variable speed drive 15, 17
voltage drop 12, 13
voltage pulses 7

W
winding 9, 10, 11, 12, 14, 15

Contact us

For more information contact
your local ABB representative or visit:

www.abb.com/drives
www.abb.com/drivespartners

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.

3AFE64230247 REV C EN 27.4.2011 #15648

Power and productivity
for a better world™

ABB drives

Technical guide No. 6
Guide to harmonics with AC drives

Power and productivity
for a better world™

Technical guide No. 6
Guide to harmonics with AC drives

6

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AFE64292714 REV C EN 11.5.2011

Contents

Chapter 1 - Introduction 7

General 7

Chapter 2 - Basics of the harmonics phenomena 8

Chapter 3 - Harmonic distortion sources and effects 10

Chapter 4 - Harmonic distortion calculation by using DriveSize software 11

4.1 Circuit diagram for the calculation example 11
4.2 Input data for motor load 11
4.3 Motor selection 12
4.4 Inverter selection 12
4.5 Inverter supply unit data 12
4.6 Network and Transformer data input 13
4.7 Calculated harmonic current and voltage 13
4.8 Calculated harmonic currents in graphical form 13
4.9 Part of the printed report 14

Chapter 5 - Standards for harmonic limits 15

5.1 EN61800-3 (IEC1800-3) Adjustable speed electrical power drive systems 15
5.2 IEC1000-2-2, Electromagnetic compatibility (EMC) 16
5.3 IEC1000-2-4, Electromagnetic compatibility (EMC) 16
5.4 IEC1000-3-2, Electromagnetic compatibility (EMC) 16
5.5 IEC1000-3-4, Electromagnetic compatibility (EMC) 16
5.6 IEEE519, IEEE Recommended practices and requirements for harmonic control in electrical power systems 17

Chapter 6 - Evaluating harmonics 19

Chapter 7 - How to reduce harmonics by structural modifications in the AC drive system 20

7.1 Factors in the AC drive having an effect on harmonics 20
7.2 Table: List of the different factors and their effects 21
7.3 Using 6-pulse diode rectifier 21
7.4 Using 12-pulse or 24-pulse diode rectifier 22
7.5 Using phase controlled thyristor rectifier 22
7.6 Using IGBT bridge 23
7.7 Using a larger DC or AC inductor 24

Chapter 8 - Other methods for harmonics reduction 27

8.1 Tuned single arm passive filter 27
8.2 Tuned multiple arm passive filter 27
8.3 External active filter 28

Chapter 9 - Summary of harmonics attenuation 30

9.1 6-pulse rectifier without inductor 30
9.2 6-pulse rectifier with inductor 30
9.3 12-pulse rectifier with polycon transformer 30
9.4 12-pulse with double wound transformer 30
9.5 24-pulse rectifier with 2 3-winding transformers 31
9.6 Active IGBT rectifier 31

Chapter 10 - Definitions 32

Index 34

Chapter 1 - Introduction

General

This guide continues ABB's technical guide series, describing harmonic distortion, its sources and effects, and also distortion calculation and evaluation. Special attention has been given to the methods for reducing harmonics with AC drives.

Chapter 2 - Basics of the harmonics phenomena

Harmonic currents and voltages are created by non-linear loads connected on the power distribution system. Harmonic distortion is a form of pollution in the electric plant that can cause problems if the sum of the harmonic currents increases above certain limits.

All power electronic converters used in different types of electronic systems can increase harmonic disturbances by injecting harmonic currents directly into the grid. Figure 2.1 shows how the current harmonics (ih) in the input current (is) of a power electronic converter affect the supply voltage (ut).



Figure 2.1 Plant with converter load, mains transformer and other loads.

The line current of a 3-phase, 6-pulse rectifier can be calculated from the direct output current by using the following formula.

$$I_1' = \sqrt{\frac{2}{3}} * I_d$$ **, where**

$I_1' =$ **the total RMS current and**

$I_d =$ **direct current output from the rectifier. (valid for ideal filtered DC current)**

The fundamental current is then

$$I_1 = I_1' * \frac{3}{\pi}$$

In a theoretical case where output current can be estimated as clean DC current, the harmonic current frequencies of a 6-pulse three phase rectifier are n times the fundamental frequency (50 or 60 Hz). The information given below is valid in the case when the line inductance is insignificant compared to the DC reactor inductance. The line current is then rectangular with 120° blocks. The order numbers n are calculated from the formula below:

$$n = 6k \pm 1, \text{ where } k = 1,2,3,...$$

The rms values of the harmonic components are:

$$I_{ni} = \frac{I_1}{n}$$

and the harmonic components are as shown in Figure 2.2.



Figure 2.2 The harmonic content in a theoretical rectangular current of a 6-pulse rectifier.

The principle of how the harmonic components are added to the fundamental current is shown in figure 2.3, where only the 5th harmonic is shown.



Figure 2.3 The total current as the sum of the fundamental and 5th harmonic.

Chapter 3 - Harmonic distortion sources and effects

Common non-linear loads include motor starters, variable speed drives, computers and other electronic devices, electronic lighting, welding supplies and uninterrupted power supplies.

The effects of harmonics can be overheating of transformers, cables, motors, generators and capacitors connected to the same power supply with the devices generating the harmonics. Electronic displays and lighting may flicker, circuit breakers can trip, computers may fail and metering can give false readings.

If the cause of the above mentioned symptoms is not known, then there is cause to investigate the harmonic distortion of the electricity distribution at the plant. The effects are likely to show up in the customer's plant before they show on the utility system. This Technical guide has been published to help customers to understand the possible harmonic problems and make sure the harmonic distortion levels are not excessive.

Chapter 4 - Harmonic distortion calculation by using DriveSize software

The harmonic currents cause a distortion of the line voltage. In principle the voltage harmonics can be calculated at any point of the network if the harmonic currents and the corresponding source impedance are known. The circuit diagrams in figure 4.1. show the network supplying the converter and the other essential parts of the installation. ABB DriveSize software is used for the calculation.

4.1 Circuit diagram for the calculation example



Figure 4.1. Network supplying a frequency converter in the middle and its equivalent diagram on the right. The data for this example is on the left.

4.2 Input data for motor load



Figure 4.2. The most important motor load data for harmonics calculation is the base power in kW.

4.3 Motor selection

Selected motor data
M2BA 315 SMC 6

Selection	DriveSize
Voltage [V]	415
Connection	D
Frequency [Hz]	50
Power [kW]	110
Poles	6
Speed [rpm]	992
Max mech.speed [rpm]	2300
Current [A]	197
Torque [Nm]	1060
T max/Tn	3,2
Power factor	0,82
Efficiency [%]	95,6
Insulation class	F

Figure 4. 3. The software makes the motor selection for the defined load. If required there is an option to select a different motor than that selected by the DriveSize.

4.4 Inverter selection

Selected inverter data
ACS607-0140-3

Selection	User
Selection method	Current (normal)
Voltage [V]	400
Drive power [kVA]	140
Pn [kW]	110
Normal Icont [A]	216
Normal Imax [A]	238
Phd [kW]	90
Heavyduty Icont [A]	178
Heavyduty Imax [A]	267
Pulse	6
Frame type	R8
P&F 12Nsq [A]	260

Figure 4.4. The inverter selection is based on the previous motor selection and here also the user has an option to select the inverter manually.

4.5 Inverter supply unit data

Supply unit data

Pulse #	6
Lv [µH]	110
Cdc [mF]	4,95
Udc [V]	560
Idc [A]	191

Figure 4.5. The supply unit data is defined by DriveSize according to the inverter type selected.

4.6 Network and Transformer data input



Figure 4.6. The network and transformer data input is given here. For standard ABB transformers the data is shown automatically.

4.7 Calculated harmonic current and voltage



n	f [Hz]	Current [A]	In/I1	Voltage [V]
1	50	2,8	100,0%	21996,6
5	250	1,2	41,2%	32,9
7	350	0,6	19,5%	21,7
11	550	0,2	8,6%	15,1
13	650	0,2	5,6%	11,7
17	850	0,1	4,2%	11,3
19	950	0,1	2,7%	8,1
23	1150	0,1	2,3%	8,2
25	1250	0,0	1,4%	5,5
29	1450	0,0	1,2%	5,3
31	1550	0,0	0,8%	3,7
35	1750	0,0	0,5%	3,0
37	1850	0,0	0,6%	3,3

Figure 4.7. The harmonics are calculated by making discrete Fourier transformation to the simulated phase current of the incoming unit. Different kinds of circuit models are used, one for SingleDrive with AC inductors and one for diode and thyristor supply with DC inductors. There are also models for 6, 12 and 24 pulse connections.

4.8 Calculated harmonic currents in graphical form



Figure 4.8. The results of calculations can be shown in table form as above or as a graph.

4.9 Part of the printed report

Network check					
			ACS607-0140-3		
Network and Transformer data		Supply unit data			
Normal voltage [V]	22000 (primary side)	Pulse #		6	
Frequency [Hz]	50	Lv [µH]		110	
Network Sk [MVA]	150	Cdc [mF]		4,95	
Transformer Sn [kVA]	400	Udc [V]		560	
Transformer Pk [kW]	3,0	Idc [A]		191	
Transformer Zk [%]	3,8				
Supply cable type	Cable				
Cable quantity	3				
Cable lenght	60				
Result				IEEE 519 limits	calc/limit
Cosfii	0,999	THD Current	47,1%	THD Current	0,2%/15,0%
Tot. power factor	0,90	THD Voltage	0,2%	THD Voltage	0,2%/5,0%
Unmax mot.	98%				

Figure 4.9. The input data and calculated results can be printed out as a report, which is partly shown here.

Chapter 5 - Standards for harmonic limits

The most common international and national standards setting limits on harmonics are described below. Figure 5.1 is shown as an example for harmonic distortion limits.

5.1 EN61800-3 (IEC1800-3) Adjustable speed electrical power drive systems

Part 3: EMC product standard including specific test methods

The countries of the European Economic Area (EEA) have agreed on common minimum regulatory requirements in order to ensure the free movement of products within the EEA. The CE marking indicates that the product works in conformity with the directives that are valid for the product. The directives state the principles that must be followed. Standards specify the requirements that must be met. EN61800-3 is the EMC product standard of adjustable speed electrical power drive systems (PDS). Meeting the requirements of this standard, is the minimum condition for free trade of power electronics converters inside the EEA.

EN61800-3 states, that the manufacturer shall provide in the documentation of the PDS, or on request, the current harmonic level, under rated conditions, as a percentage of the rated fundamental current on the power port. The referenced values shall be calculated for each order at least up to the 25^{th}. The current THD (orders up to and including 40), and its high-frequency component PHD (orders from 14 to 40 inclusive) shall be evaluated. For these standard calculations, the PDS shall be assumed to be connected to a PC with Rsc = 250 and with initial voltage distortion less than 1 percent. The internal impedance of the network shall be assumed to be a pure reactance.

In a low voltage public supply network, the limits and requirements of IEC1000-3-2 apply for equipment with rated current ≤ 16 A. The use of the future IEC1000-3-4 is recommended for equipment with rated current > 16 A. If PDS is used in an industrial installation, a reasonable economical approach, which considers the total installation, shall be used. This approach is based on the agreed power, which the supply can deliver at any time. The method for calculating the harmonics of the total installation is agreed and the limits for either the voltage distortion or the total harmonic current emission are agreed on. The compatibility limits given in IEC1000-2-4 may be used as the limits of voltage distortion.

5.2 IEC1000-2-2, Electromagnetic compatibility (EMC)

Part 2: Environment - Section 2: Compatibility levels for low frequency conducted disturbances and signalling in public low voltage power supply systems

This standard sets the compatibility limits for low frequency conducted disturbances and signalling in **public low voltage power supply** systems. The disturbance phenomena include harmonics, inter-harmonics, voltage fluctuations, voltage dips and short interruptions voltage inbalance and so on. Basically this standard sets the design criteria for the equipment manufacturer, and amounts to the minimum immunity requirements of the equipment. IEC1000-2-2 is in line with the limits set in EN50160 for the quality of the voltage the utility owner must provide at the customer's supply-terminals.

5.3 IEC1000-2-4, Electromagnetic compatibility (EMC)

Part 2: Environment - Section 4: Compatibility levels in industrial plants for low frequency conducted disturbances

IEC1000-2-4 is similar to IEC1000-2-2, but it gives compatibility levels **for industrial and non-public networks**. It covers low-voltage networks as well as medium voltage supplies excluding the networks for ships, aircraft, offshore platforms and railways.

5.4 IEC1000-3-2, Electromagnetic compatibility (EMC)

Part 3: Limits - Section 2: Limits for harmonic current emissions (equipment current < 16 A per phase)

This standard deals with the harmonic current emission limits of individual equipment connected to **public networks**. The date of implementation of this standard is January 1, 2001, but there is extensive work going on at the moment to revise the standard before this date. The two main reasons for the revision are the need for the standard to cover also the voltage below 230 V and the difficulties and contradictions in applying the categorisation of the equipment given in the standard.

5.5 IEC1000-3-4, Electromagnetic compatibility (EMC)

This standard has been published as a Type II Technical report. Work is going on to convert it into a standard. It gives the harmonic current emission limits for individual equipment having a rated current of more than 16 A up to 75 A. It applies to public networks having nominal voltages from 230 V single phase to 600 V three phase.

The standard gives three different stages for connection procedures of the equipment. Meeting the individual harmonic limits of stage 1 allows the connection of the equipment at any point in the supply system. Stage 2 gives individual harmonic current limits as well as THD and its weighted high frequency counterpart PWHD. The limits are classified and tabulated by the short circuit ratio. The third stage of connection is based on an agreement between the user and the supply authority, based on the agreed active power of the consumer's installation. If the rated current is above 75 A, stage 3 applies in any case.

The structure of this standard is generally seen to be good, but it may justly be questioned whether single and three-phase equipment should have different limits in stage 2. It is very probable that the structure of the standard will remain as it is, but the version having the status of actual standard, will contain different limits for single and three-phase equipment.



Figure 5.1 Limits on harmonics in the proposed EN61000-3-4.

5.6 IEEE519, IEEE Recommended practices and requirements for harmonic control in electrical power systems

The philosophy of developing harmonic limits in this recommended practice is to limit the harmonic injection from individual customers so that they will not cause unacceptable voltage distortion levels for normal system characteristics and to limit overall harmonic distortion of the system voltage supplied by the utility. This standard is also recognised as American National Standard and it is widely used in the USA, especially in the municipal public works market.

The standard does not give limits for individual equipment, but for individual customers. The customers are categorised by the ratio of available short circuit current (Isc) to their maximum demand load current (IL) at the point of common coupling. The total demand load current is the sum of both linear and non-linear loads. Within an industrial plant, the PCC is clearly defined as the point between the non-linear load and other loads.

The allowed individual harmonic currents and total harmonic distortion are tabulated by the ratio of available short circuit current to the total demand load current (Isc/IL) at the point of common coupling. The limits are as a percentage of IL for all odd and even harmonics from 2 to infinity. Total harmonic distortion is called total demand distortion and also it should be calculated up to infinity. Many authors limit the calculation of both the individual components and TDD to 50.

The table 10.3 of the standard is sometimes misinterpreted to give limits for the harmonic emissions of a single apparatus by using Rsc of the equipment instead of Isc/IL of the whole installation. The limits of the table should not be used this way, since the ratio of the short circuit current to the total demand load current of an installation should always be used.

Chapter 6 - Evaluating harmonics

The “Guide for Applying Harmonic Limits on Power Systems” P519A/D6 Jan 1999 introduces some general rules for evaluating harmonic limits at an industrial facility. The procedure is shown in the flowchart in figure 6.1.



Figure 6.1 Evaluation of harmonic distortion.

Chapter 7 - How to reduce harmonics by structural modifications in the AC drive system

7.1 Factors in the AC drive having an effect on harmonics

Harmonics reduction can be done either by structural modifications in the drive system or by using external filtering. The structural modifications can be to strengthen the supply, to use 12 or more pulse drive, to use a controlled rectifier or to improve the internal filtering in the drive.

Figure 7.1 shows the factors in the AC drive system which have some influence on harmonics. The current harmonics depend on the drive construction and the voltage harmonics are the current harmonics multiplied by the supply impedances.



Figure 7.1 Drive system features affecting harmonics.

7.2 Table: List of the different factors and their effects

The cause	The effect
The larger the motor…	the higher the current harmonics
The higher the motor load…	the higher the current harmonics
The larger the DC or AC inductance…	the lower the current harmonics
The higher the number of pulses in the rectifier…	the lower the current harmonics
The larger the transformer…	the lower the voltage harmonics
The lower the transformer impedance…	the lower the voltage harmonics
The higher the short circuit capacity of supply…	the lower the voltage harmonics

7.3 Using 6-pulse diode rectifier

The connections for different rectifier solutions are shown in figure 7.2. The most common rectifier circuit in 3-phase AC drives is a 6-pulse diode bridge. It consists of six uncontrollable rectifiers or diodes and an inductor, which together with a DC-capacitor forms a low-pass filter for smoothing the DC-current. The inductor can be on the DC- or AC-side or it can be left totally out. The 6-pulse rectifier is simple and cheap but it generates a high amount of low order harmonics 5^{th}, 7^{th}, 11^{th} especially with small smoothing inductance.

The current form is shown in figure 7.2. If the major part of the load consists of converters with a 6-pulse rectifier, the supply transformer needs to be oversized and meeting the requirements in standards may be difficult. Often some harmonics filtering is needed.



Figure 7.2 Harmonics in line current with different rectifier constructions.


0,25
0,2
0,15
0,1
0,05
0
5

– Nearly sinusoidal supply current with low harmonic content. Measured results for one drive is shown in figure 7.5. When comparing with figure 7.3 we can see a clear difference. IGBT has very low harmonics at lower frequencies, but somewhat higher at higher frequencies.
– Voltage boost capability. In case of low supply voltage the DC voltage can be boosted to keep motor voltage higher than supply voltage.

The main drawback is the high cost coming from the IGBT bridge and extra filtering needed.



Figure 7.5 Harmonics in line current IGBT line generating unit.

7.7 Using a larger DC or AC inductor

The harmonics of a voltage source AC drive can be significantly reduced by connecting a large enough inductor in its AC input or DC bus. The trend has been to reduce the size of converter while the inductor size has been also reduced, or in several cases it has been omitted totally. The effect of this can be seen from the curve forms in figure 7.6.



Figure 7.6 The effect of the inductor on the line current.

The chart in figure 7.7 shows the effect of the size of the DC inductor on the harmonics. For the first 25 harmonic components the theoretical THD minimum is 29 percent. That value is practically reached when the inductance is 100 mH divided by the motor kW or 1 mH for a 100 kW motor (415 V, 50 Hz). Practically sensible is about 25 mH divided by motor kW, which gives a THD of about 45 percent. This is 0.25 mH for a 100 kW motor.



Figure 7.7 Harmonic current as function of DC inductance.

The voltage distortion with certain current distortion depends on the short circuit ratio Rsc of the supply. The higher the ratio, the lower the voltage distortion. This can be seen in Figure 7.8.



Figure 7.8 THD voltage vs type of AC drive and transformer size.

Figure 7.9 introduces a simple nomogram for estimation of harmonic voltages. On the graph below right select first the motor kilowatt, then the transformer kVA and then move horizontally to the diagonal line where you move upwards and stop at the curve valid for your application. Then turn left to the y-axis and read the total harmonic voltage distortion.



Figure 7.9 Total harmonic distortion nomogram.

Results from laboratory tests with drive units from different manufacturers are shown in figure 7.10. Drive A with large DC inductor has the lowest harmonic current distortion, drives with no inductor installed have the highest distortion.



Figure 7.10 Harmonic current with different DC-inductances.

Chapter 8 - Other methods for harmonics reduction

Filtering is a method to reduce harmonics in an industrial plant when the harmonic distortion has been gradually increased or as a total solution in a new plant. There are two basic methods: passive and active filters.

8.1 Tuned single arm passive filter

The principle of a tuned arm passive filter is shown in figure 8.1. A tuned arm passive filter should be applied at the single lowest harmonic component where there is significant harmonic generation in the system. For systems that mostly supply an industrial load this would probably be the fifth harmonic. Above the tuned frequency the harmonics are absorbed but below that frequency they may be amplified.



- Detuned - Single tuning frequency
- Above tuned frequency harmonics absorbed
- Below tuned frequency harmonics may be amplified
- Harmonic reduction limited by possible over compensation at the supply frequency and network itself

Figure 8.1 Tuned singel arm passive filter.

8.2 Tuned multiple arm passive filter

This kind of filter consists of an inductor in series with a capacitor bank and the best location for the passive filter is close to the harmonic generating loads. This solution is not normally used for new installations.

The principle of this filter is shown in figure 8.2. This filter has several arms tuned to two or more of the harmonic components which should be the lowest significant harmonic frequencies in the system. The multiple filter has better harmonic absorption than the one arm system.



- Capacitive below tuned frequency/Inductive above
- Better harmonic absorption
- Design consideration to amplification harmonics by filter
- Limited by KVAr and network

Figure 8.2 Tuned multiple arm passive filter.

The multiple arm passive filters are often used for large DC drive installations where a dedicated transformer is supplying the whole installation.

8.3 External active filter

A passive tuned filter introduces new resonances that can cause additional harmonic problems. New power electronics technologies are resulting in products that can control harmonic distortion with active control. These active filters, see figure 8.3, provide compensation for harmonic components on the utility system based on existing harmonic generation at any given moment in time.



Figure 8.3 External active filter principle diagram.

The active filter compensates the harmonics generated by non-linear loads by generating the same harmonic components in opposite phase as shown in figure 8.4. External active filters are most suited to multiple small drives. They are relatively expensive compared to other methods.



Figure 8.4 External active filter waveforms and harmonics.

Chapter 9 - Summary of harmonics attenuation

There are many options to attenuate harmonics either inside the drive system or externally. They all have advantages and disadvantages and all of them show cost implications. The best solution will depend on the total loading, the supply to the site and the standing distortion.

In the following tables different internal actions are compared to the basic system without inductor. The harmonic content is given with 100 percent load. The costs are valid for small drives. For multidrive the 12-pulse solution is quite a lot cheaper.

9.1 6-pulse rectifier without inductor

Manufacturing cost 100 percent
Typical harmonic current components.

Fundamental	5th	7th	11th	13th	17th	19th
100%	63%	54%	10%	6,1%	6,7%	4,8%

9.2 6-pulse rectifier with inductor

Manufacturing cost 120%. AC or DC choke added
Typical harmonic current components.

Fundamental	5th	7th	11th	13th	17th	19th
100%	30%	12%	8,9%	5,6%	4,4%	4,1%

9.3 12-pulse rectifier with polycon transformer

Manufacturing cost 200%
Typical harmonic current components.

Fundamental	5th	7th	11th	13th	17th	19th
100%	11%	5,8%	6,2%	4,7%	1,7%	1,4%

9.4 12-pulse with double wound transformer

Manufacturing cost 210%
Typical harmonic current components.

Fundamental	5th	7th	11th	13th	17th	19th
100%	3,6%	2,6%	7,5%	5,2%	1,2%	1,3%

9.5 24-pulse rectifier with 2 3-winding transformers

Manufacturing cost 250%
Typical harmonic current components.

Fundamental	5th	7th	11th	13th	17th	19th
100%	4,0%	2,7%	1,0%	0,7%	1,4%	1,4%

9.6 Active IGBT rectifier

Manufacturing cost 250%. Not significant if electrical braking is anyway needed.
Typical harmonic current components.

Fundamental	5th	7th	11th	13th	17th	19th
100%	2,6%	3,4%	3,0%	0,1%	2,1%	2,2%

Chapter 10 - Definitions

S: Apparent power

P: Active power

Q: Reactive power

Rsc: Short circuit ratio is defined as the short circuit power of the supply at PCC to the nominal apparent power of the equipment under consideration. Rsc = Ss / Sn.

$\omega 1$: Angular frequency of fundamental component $\omega 1 = 2*\pi*f1$, where f1 is fundamental frequency (eg. 50 Hz or 60 Hz).

n: Integer n = 2, 3, ... ∞. Harmonic frequencies are defined as $wn = n*\omega 1$.

In: RMS-value of n:th harmonic component of line current.

Zn: Impedance at frequency $n*\omega 1$.

%Un: Harmonic voltage component as a percentage of fundamental (line) voltage.

THD: Total harmonic distortion in the input current is defined as:

$$THD = \frac{\sqrt{\sum_{n=2}^{\infty} I_n^{\,2}}}{I_1}$$

where I_1 is the rms value of the fundamental frequency current. The THD in voltage may be calculated in a similar way. Here is an example for the 25 lowest harmonic components with the theoretical values:

$$THD = \frac{\sqrt{20^2 + 14.3^2 + 9.1^2 + 7.7^2 + 5.9^2 + 5.3^2 + 4.4^2 + 4^2}}{100}$$

$$THD = 29\%$$

PWHD: Partial weighted harmonic distortion is defined as:

$$PWHD = \sqrt{\sum_{n=14}^{40} n\left(\frac{I_n}{I_1}\right)^2}$$

PCC: Point of common coupling is defined in this text as such a point of utility supply which may be common to the equipment in question and other equipment. There are several definitions of PCC in different standards and even more interpretations of these definitions in literature. The definition chosen here is seen as technically most sound.

PF: Power factor is defined as PF = P/S (power / volt-ampere) = I_1 / Is * DPF (With sinusoidal current PF equals to DPF).

DPF: Displacement power factor is defined as cosϕ1, where ϕ1 is the phase angle between the fundamental frequency current drawn by the equipment and the supply voltage fundamental frequency component.

Index

Symbols
12-pulse rectifier 21, 22, 23, 30
24-pulse rectifier 21, 22, 31
3-winding 31
5th harmonic 9
6-pulse rectifier 8, 9, 21, 22, 23, 30
6-pulse three phase rectifier 9

A
ABB 7, 11, 13
AC inductor 13, 24
active filter 27, 28, 29
active power 17, 32
American National Standard 17
anti-parallel 23
apparent power 32
attenuation 30, 31

C
calculation 7, 11, 12, 13, 14, 15, 18, 19
CE marking 15
circuit breaker 10
common DC-bus 22
commutation notch 23
compatibility limit 15, 16
computer 10
consumer's installation 17
converter 8, 11, 15, 21, 23, 24
converter load 8

D
DC-capacitor 21
DC-current 21
displacement power factor 23, 33
distortion calculation 7, 11, 12, 13, 14
distortion nomogram 26
DriveSize 11, 12, 13, 14

E
effect 7, 10, 20, 21, 24, 25
Electromagnetic compatibility 16
electronic device 10
Electronic display 10
electronic lighting 10
EMC product standard 15
European Economic Area 15
external filtering 20

F
filtering 20, 21, 24, 27
frequency 9, 11, 12, 13, 14, 15, 16, 17, 22, 27, 28, 32, 33
fundamental frequency 9, 32, 33

H
harmonic component 9, 22, 25, 27, 28, 32
harmonic currents 8, 11, 13, 18, 23
harmonic distortion 7, 8, 10, 11, 12, 13, 14, 15, 17, 18, 19, 22, 26, 27, 28, 32
harmonic limit 16, 17, 18, 19
harmonics phenomena 8, 9
harmonics reduction 20, 27, 28, 29
harmonic voltage 26, 32

I
IGBT bridge 23, 24
inductance 9, 20, 21, 25, 26
inductor 13, 21, 24, 25, 26, 27, 30
industrial installation 15
installation 11, 15, 17, 18, 22, 27, 28
inverter selection 12
Inverter supply unit data 12

L
laboratory test 26
line current 8, 9, 21, 24, 32
low-pass filter 21

M
mains transformer 8
manufacturing cost 30, 31
metering 10
motor load 11, 21
motor selection 12
motor starter 10
multiple arm passive filter 27, 28

N
network 11, 13, 14, 15, 16, 17, 27, 28
non-linear load 8, 10, 18, 19

O
overheating 10

P
passive filter 27, 28
phase commutated rectifier 23
point of common coupling 18, 33
power distribution 8
power drive system 15
power factor 12, 14, 19, 23, 33
power port 15
public supply 15
PWHD 17, 32

R
reactive power 23, 32
rectifier 8, 9, 20, 21, 22, 23, 30, 31
rectifying mode 23
regenerating mode 23
report 14, 16

S
short circuit power 20, 32
short circuit ratio 17, 19, 25, 32
source 7, 10, 11, 24
source impedance 11
standard 13, 15, 16, 17, 18, 21, 23, 33
structural modification 20, 21, 22, 23, 24, 25, 26
supply authority 17
supply cable 13, 14
supply transformer 21
supply voltage 8, 24, 33

T
TDD 18
THD 13, 14, 15, 17, 25, 32
three-winding transformer 22
thyristor 13, 20, 22, 23
total demand distortion 18
total harmonic distortion 18, 26, 32
transformer 8, 10, 11, 13, 14, 20, 21, 22, 25, 26, 28, 30, 31
tuned arm passive filter 27

V
variable speed drives 10
voltage 8, 11, 12, 13, 14, 15, 16, 17, 20, 21, 22, 23, 24, 25, 26, 32, 33
voltage boost 23, 24

Contact us

For more information contact
your local ABB representative or visit:

www.abb.com/drives
www.abb.com/drivespartners

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.

3AFE64292714 REV C EN 11.5.2011 #15567

Power and productivity
for a better world™

ABB drives

Technical guide No. 7
Dimensioning of a drive system

Power and productivity
for a better world™

Technical guide No. 7
Dimensioning of a drive system

7

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AFE64362569 REV C EN 28.4.2011

Contents

Chapter 1 - Introduction 7

General 7

Chapter 2 - Drive system 8

Chapter 3 - General description of a dimensioning procedure 9

Chapter 4 - Induction (AC) motor 11

4.1 Fundamentals 11
4.2 Motor current 13
4.2.1 Constant flux range 14
4.2.2 Field weakening range 15
4.3 Motor power 16

Chapter 5 - Basic mechanical laws 17

5.1 Rotational motion 17
5.2 Gears and moment of inertia 20

Chapter 6 - Load types 22

Chapter 7 - Motor loadability 25

Chapter 8 - Selecting the frequency converter and motor 26

8.1 Pump and fan application (Example) 27
8.2 Constant torque application (Example) 29
8.3 Constant power application (Example) 31

Chapter 9 - Input transformer and rectifier 35

9.1 Rectifiers 35
9.2 Transformer 36

Chapter 10 - Index 38

Chapter 1 - Introduction

General

Dimensioning of a drive system is a task where all factors have to be considered carefully. Dimensioning requires knowledge of the whole system including electric supply, driven machine, environmental conditions, motors and drives, etc. Time spent at the dimensioning phase can mean considerable cost savings.

Chapter 2 - Drive system

A single AC drive system consists typically of an input transformer or an electric supply, frequency converter, an AC motor and load. Inside the single frequency converter there is a rectifier, DC-link and inverter unit.



Figure 2.1 A single frequency converter consists of 1) rectifier, 2) DC-link, 3) inverter unit and 4) electric supply.

In multi-drive systems a separate rectifier unit is commonly used. Inverter units are connected directly to a common DC-link.



Figure 2.2 A drive system which has 1) a separate supply section, 2) common DC-link, 3) drive sections and 4) electric supply.

Chapter 3 - General description of a dimensioning procedure

This chapter gives the general steps for dimensioning the motor and the frequency converter.

1) First check the initial conditions.
   In order to select the correct frequency converter and motor, check the mains supply voltage level (380 V to 690 V) and frequency (50 Hz to 60 Hz). The mains supply network's frequency doesn't limit the speed range of the application.

2) Check the process requirements.
   Is there a need for starting torque? What is the speed range used? What type of load will there be? Some of the typical load types are described later.

3) Select the motor.
   An electrical motor should be seen as a source of torque. The motor must withstand process overloads and be able to produce a specified amount of torque. The motor's thermal overloadability should not be exceeded. It is also necessary to leave a margin of around 30 percent for the motor's maximum torque when considering the maximum available torque in the dimensioning phase.

4) Select the frequency converter.
   The frequency converter is selected according to the initial conditions and the selected motor. The frequency converter's capability of producing the required current and power should be checked. Advantage should be taken of the frequency converter's potential overloadability in case of a short term cyclical load.



Figure 3.1 General description of the dimensioning procedure.

Chapter 4 - Induction (AC) motor

Induction motors are widely used in industry. In this chapter some of the basic features are described.

4.1 Fundamentals

An induction motor converts electrical energy into mechanical energy. Converting the energy is based on electromagnetic induction. Because of the induction phenomenon the induction motor has a slip.

The slip is often defined at the motor's nominal point (frequency (f_n), speed (n_n), torque (T_n), voltage (U_n), current (I_n) and power (P_n)). At the nominal point the slip is nominal:

$$s_n = \frac{n_s - n_n}{n_s} * 100\ \% \qquad (4.1)$$

where n_s is the synchronous speed:

$$n_s = \frac{2 * f_n * 60}{\text{pole number}} \qquad (4.2)$$

When a motor is connected to a supply with constant voltage and frequency it has a torque curve as follows:



Figure 4.1 Typical torque/speed curve of an induction motor when connected to the network supply (D.O.L., Direct-On-Line). In the picture a) is the locked rotor torque, b) is the pull-up torque, c) is the maximum motor torque, T_{max} and d) is the nominal point of the motor.

A standard induction motor's maximum torque (T_{max}, also called pull-out torque and breakdown torque) is typically 2-3 times the nominal torque. The maximum torque is available with slip s_{max} which is greater than the nominal slip. In order to use an induction motor efficiently the motor slip should be in the range - s_{max} **...** s_{max}. This can be achieved by controlling voltage and frequency. Controlling can be done with a frequency converter.



Figure 4.2 Torque/speed curves of an induction motor fed by a frequency converter. T_{max} is available for short term overloads below the field weakening point. Frequency converters, however, typically limit the maximum available torque to 70 percent of T_{max}.

The frequency range below the nominal frequency is called a constant flux range. Above the nominal frequency/speed the motor operates in the field weakening range. In the field weakening range the motor can operate on constant power which is why the field weakening range is sometimes also called the constant power range.

The maximum torque of an induction motor is proportional to the square of the magnetic flux ($T_{max} \sim \psi^2$). This means that the maximum torque is approximately a constant at the constant flux range. Above the field weakening point the maximum torque decrease is inversely proportional to the square of the frequency ($T_{max} \sim \left(\frac{f_n}{f_{act}} \right)^2$).



Figure 4.3 Maximum torque, voltage and flux as a function of the relative speed.

4.2 Motor current

An induction motor current has two components: reactive current (i_{sd}) and active current (i_{sq}). The reactive current component includes the magnetizing current (i_{magn}) whereas the active current is the torque producing current component. The reactive and active current components are perpendicular to each other.

The magnetizing current (i_{magn}) remains approximately constant in the constant flux range (below the field weakening point). In the field weakening range the magnetizing current decrease is proportional to speed.

A quite good estimate for the magnetizing current in the constant flux range is the reactive (i_{sd}) current at the motor nominal point.



Figure 4.4 Stator current (i_s) consists of reactive current (i_{sd}) and active current (i_{sq}) components which are perpendicular to each other. Stator flux is denoted as ψ_s.

4.2.1 Constant flux range

Below the field weakening point the current components can be approximated as follows:

$$I_{sd} = I_n \left(\sin(\varphi_n) + \cos(\varphi_n) \left[\sqrt{\left(\frac{T_{max}}{T_n}\right)^2 - 1} - \sqrt{\left(\frac{T_{max}}{T_n}\right)^2 - \left(\frac{T_{load}}{T_n}\right)^2} \right] \right) \quad (4.3)$$

$$I_{sq} = I_n \left(\frac{T_{load}}{T_n} \right) \cos(\varphi_n) \quad (4.4)$$

The total motor current is:

$$i_m = \sqrt{i_{sd}^2 + i_{sq}^2} \quad (4.5)$$

It can be seen that with zero motor torque the active current component is zero. With higher torque values motor current becomes quite proportional to the torque. A good approximation for total motor current is:

$$i_m = \frac{T_{load}}{T_n} * I_n \quad \text{, when } 0.8 * T_n \leq T_{load} \leq 0.7 * T_{max} \quad (4.6)$$

Example 4.1:
A 15 kW motor's nominal current is 32 A and power factor is 0.83. What is the motor's approximate magnetizing current at the nominal point? What is the total approximate current with 120 percent torque below the field weakening point.

Solution 4.1:
At the nominal point the estimate for the magnetizing current is:

$$I_{sd} = I_n \, Sin(\varphi_n) = 32 * \sqrt{1 - 0.83^2} \, A = 17.8 \, A$$

The approximate formula for total motor current with 120 percent torque gives:

$$i_m = \frac{T_{load}}{T_n} * I_n = 1.2 * 32 \, A = 38.4 \, A$$

The approximate formula was used because torque fulfilled the condition $0.8 * T_n \leq T_{load} \leq 0.7 * T_{max}$

4.2.2 Field weakening range

Above the field weakening point the current components also depend on speed.

$$I_{sd} = I_n \left(\frac{n_n}{n} \left(\sin(\varphi_n) + \cos(\varphi_n) \sqrt{\left(\frac{T_{max}}{T_n} \right)^2 - 1} \right) - \cos(\varphi_n) \sqrt{\left(\frac{T_{max}}{T_n} * \frac{n_n}{n} \right)^2 - \left(\frac{T_{load}}{T_n} * \frac{n}{n_n} \right)^2} \right) \tag{4.7}$$

$$I_{sq} = I_n \left(\frac{T_{load}}{T_n} * \frac{n}{n_n} \right) \cos(\varphi_n) = I_n \left(\frac{P_{load}}{P_n} \right) \cos(\varphi_n) \tag{4.8}$$

Total motor current is:

$$i_m = \sqrt{i_{sd}^2 + i_{sq}^2} \tag{4.9}$$

The motor current can be approximated quite accurately within a certain operating region. The motor current becomes proportional to relative power. An approximation formula for current is:

$$i_m = \frac{T_{load}}{T_n} * \frac{n}{n_n} I_n = \frac{P_{load}}{P_n} I_n \tag{4.10}$$

Approximation can be used when:

$$0.8 * \frac{n_n}{n} * T_n \le T_{load} \le 0.7 * \left(\frac{n_n}{n} \right)^2 * T_{max} \tag{4.11}$$

and

$$0.8 * P_n \le P_{load} \le 0.7 * \frac{n_n}{n} * P_{max} \tag{4.12}$$

In the field weakening range the additional current needed in order to maintain a certain torque level is proportional to relative speed.

Example 4.2:
The motor's nominal current is 71 A. How much current is needed to maintain the 100 percent torque level at 1.2 times nominal speed ($T_{max} = 3 * T_n$).

Solution 4.2:
The current can be calculated by using the approximation formula:

$$i_m = \frac{T_{load}}{T_n} * \frac{n}{n_n} I_n = 1 * 1.2 * 71 = 85.2 \text{ A}$$

4.3 Motor power

The motor's mechanical (output) power can be calculated from speed and torque using the formula:

$$P_{out}\,[W] = T\,[Nm] * \omega\,[rad/s] \tag{4.13}$$

Because motor power is most often given in kilowatts (1 kW = 1000 W) and speed in rpm revolutions per minute, 1 rpm = $\frac{2\,\pi}{60}$ rad/s), the following formula can be used:

$$P_{out}\,[kW] = \frac{T\,[Nm] * n\,[rpm]}{9550} \tag{4.14}$$

The motor's input power can be calculated from the voltage, current and power factor:

$$P_{in} = \sqrt{3} * U * I * \cos(\varphi) \tag{4.15}$$

The motor's efficiency is the output power divided by the input power:

$$\eta = \frac{P_{out}}{P_{in}} \tag{4.16}$$

Example 4.3:
The motor nominal power is 15 kW and the nominal speed is 1480 rpm. What is the nominal torque of the motor?

Solution 4.3:
The motor's nominal torque is calculated as follows:

$$T_n = \frac{9550 * 15}{1480}\ Nm = 96.8\ Nm$$

Example 4.4:
What is the nominal efficiency of a 37 kW (P_n = 37 kW, U_n =380 V, I_n =71 A and $\cos(\varphi_n)$ = 0.85) motor?

Solution 4.4:
The nominal efficiency is:

$$\eta_n = \frac{P_{out}}{P_{in}} = \frac{P_n}{\sqrt{3} * U_n * I_n * \cos(\varphi_n)} = \frac{37000}{\sqrt{3} * 380 * 71 * 0.85} \approx 0.931$$

Chapter 5 - Basic mechanical laws

5.1 Rotational motion

One of the basic equations of an induction motor describes the relation between moment of inertia (J [kgm^2]), angular velocity ([rad/s]) and torque (T [Nm]). The equation is as follows:

$$\frac{d}{dt}(J\,\omega) = J\frac{d\,\omega}{dt} + \omega\frac{dJ}{dt} = T - T_{load} \qquad (5.1)$$

In the above equation it is assumed that both the frequency and the moment of inertia change. The formula is however often given so that the moment of inertia is assumed to be constant:

$$J\frac{d\,\omega}{dt} = T - T_{load} \qquad (5.2)$$

Torque T_{load} represents the load of the motor. The load consists of friction, inertia and the load itself. When the motor speed changes, motor torque is different from T_{load} . Motor torque can be considered as consisting of a dynamic and a load component:

$$T = T_{dyn} + T_{load} \qquad (5.3)$$

If the speed and moment of inertia are constants the dynamic component (T_{dyn}) is zero.

The dynamic torque component caused by acceleration/deceleration of a constant moment of inertia (motor's speed is changed by n [rpm] in time t [s], J is constant) is:

$$T_{dyn,n} = J * \frac{2\,\pi}{60} * \frac{\Delta n}{\Delta t} \qquad (5.4)$$

The dynamic torque component caused by a variable moment of inertia at constant speed n[rpm] is:

$$T_{dyn,J} = n * \frac{2\,\pi}{60} * \frac{\Delta J}{\Delta t} \qquad (5.5)$$

If the moment of inertia varies and at the same time the motor is accelerating the dynamic torque component can be calculated using a certain discrete sampling interval. From the thermal dimensioning point of view it is however often enough to take into account the average moment of inertia during acceleration.

Acceleration times for different speed sections are:

0-198.2 rpm $\Delta t = \frac{2\pi}{60} * \frac{1211 * 198.2}{0.99 * 1927} s = 13.2\ s$

198.2-396.4 rpm $\Delta t = \frac{2\pi}{60} * \frac{1211 * 198.2}{0.92 * 1927} s = 14.3\ s$

396.4-594.6 rpm $\Delta t = \frac{2\pi}{60} * \frac{1211 * 198.2}{0.78 * 1927} s = 16.7\ s$

594.6-792.8 rpm $\Delta t = \frac{2\pi}{60} * \frac{1211 * 198.2}{0.57 * 1927} s = 22.9\ s$

792.8-991 rpm $\Delta t = \frac{2\pi}{60} * \frac{1211 * 198.2}{0.29 * 1927} s = 45.0\ s$

The total starting time 0-991 rpm is approximately 112 seconds.

5.2 Gears and moment of inertia

Gears are typical in drive systems. When calculating the motor torque and speed range gears have to be taken into account. Gears are reduced from load side to motor side with following equations (see also figure 5.2):

$$T_1 = \frac{T_2}{\eta} * \left(\frac{n_2}{n_1}\right) \tag{5.6}$$

$$J_1 = J_2 * \left(\frac{n_2}{n_1}\right)^2 \tag{5.7}$$

$$P_1 = \frac{P_2}{\eta} \tag{5.8}$$



Figure 5.2 A gear with efficiency η. Gear ratio is n_1:n_2.

Also all the moments of inertia (J [kgm^2]) within the system have to be known. If they are not known they can be calculated which is rather difficult to do accurately. Typically machine builders can give the necessary data.

Example 5.3:
A cylinder is quite a common shape for a load (rollers, drums, couplings, etc.). What is the inertia of a rotating cylinder (mass=1600 kg, radius=0.7 m)?

Solution 5.3:
The inertia of a rotating cylinder (with mass m [kg] and radius r [m]) is calculated as follows:

$$J = \frac{1}{2} mr^2 = \frac{1}{2} * 1600 * 0.7^2 \text{ kgm}^2 = 392 \text{ kgm}^2$$

In the case of a gear, the moment of inertia to the motor shaft has to be reduced. The following example shows how to reduce gears and hoists. In basic engineering books other formulas are also given.

Example 5.4:
Reduce the moment of inertia to the motor shaft of the following hoist drive system.



Figure 5.3 A Hoist drive system used in example 5.4.

Solution 5.4:
The total moment of inertia consists of J_1=10 kgm^2, J_2=30 kgm^2, r=0.2 m and m=100 kg.
The moment of inertia J_2 and mass m are behind a gearbox with gear ratio n_1:n_2=2:1.

The moment of inertia J_2 is reduced by multiplying with the square of the inverse of the gear ratio. The mass m of the hoist is reduced by multiplying it with square of the radius r and because it is behind the gearbox it has to be multiplied with the square of the inverse of the gear ratio, too.

Thus the total moment of inertia of the system is:

$$J_{red} = J_1 + \left(\frac{n_2}{n_1}\right)^2 [J_2 + mr^2] = 18.5 \text{ kgm}^2$$

Chapter 6 - Load types

Certain load types are characteristic in the industrial world. Knowing the load profile (speed range, torque and power) is essential when selecting a suitable motor and frequency converter for the application.

Some common load types are shown. There may also be combinations of these types.

1. Constant torque
   A constant torque load type is typical when fixed volumes are being handled. For example screw compressors, feeders and conveyors are typical constant torque applications. Torque is constant and the power is linearly proportional to the speed.



Figure 6.1 Typical torque and power curves in a constant torque application.

2. Quadratic torque
   Quadratic torque is the most common load type. Typical applications are centrifugal pumps and fans. The torque is quadratically, and the power is cubically proportional to the speed.



Figure 6.2 Typical torque and power curves in a quadratic torque application.

3. Constant power
   A constant power load is normal when material is being rolled and the diameter changes during rolling. The power is constant and the torque is inversely proportional to the speed.



Figure 6.3 Typical torque and power curves in a constant power application.

4. Constant power/torque
   This load type is common in the paper industry. It is a combination of constant power and constant torque load types. This load type is often a consequence of dimen-sioning the system according to the need for certain power at high speed.



Figure 6.4 Typical torque and power curves in a constant power/torque application.

5. Starting/breakaway torque demand
   In some applications high torque at low frequencies is needed. This has to be considered in dimensioning. Typical applications for this load type are for example extruders and screw pumps.



Figure 6.5 Typical torque curve in an application where starting torque is needed.

There are also several other load types. They are however hard to describe in a general presentation. Just to mention a few, there are different symmetrical (rollers, cranes, etc.) and unsymmetrical loads. Symmetry/non-symmetry in torque can be for example as a function of angle or time. These kinds of load types must be dimensioned carefully taking into account the overloadability margins of the motor and the frequency converter, as well as the average torque of the motor.

Chapter 7 - Motor loadability

Motor thermal loadability has to be considered when dimensioning a drive system. The thermal loadability defines the maximum long term loadability of the motor.

A standard induction motor is self ventilated. Because of the self ventilation the motor thermal loadability decreases as the motor speed decreases. This kind of behaviour limits the continuous available torque at low speeds.

A motor with a separate cooling can also be loaded at low speeds. Cooling is often dimensioned so that the cooling effect is the same as at the nominal point.

With both self and separate cooling methods torque is thermally limited in the field weakening range.



Figure 7.1 A standard cage induction motor's typical loadability in a frequency controlled drive 1) without separate cooling and 2) with separate cooling.

An AC motor can be overloaded for short periods of time without overheating it. Short term overloads are mainly limited by T_{max} (check the safety margin).

Generally speaking, a frequency converter's short term loadability is often more critical than the motor's. The motor thermal rise times are typically from 15 minutes (small motors) to several hours (big motors) depending on the motor size. The frequency converter's thermal rise times (typically few minutes) are given in the product manuals.

Chapter 8 - Selecting the frequency converter and motor

The motor is selected according to the basic information about the process. Speed range, torque curves, ventilation method and motor loadability give guidelines for motor selection. Often it is worth comparing different motors because the selected motor affects the size of the frequency converter.

When selecting a suitable frequency converter there are several things to be considered. Frequency converter manufacturers normally have certain selection tables where typical motor powers for each converter size are given.

The dimensioning current can also be calculated when the torque characteristics is known. The corresponding current values can be calculated from the torque profile and compared to converter current limits. The motor's nominal current gives some kind of indication. It isn't however always the best possible dimensioning criteria because motors might for example be derated (ambient temperature, hazardous area, etc.).

The available supply voltage must be checked before selecting the frequency converter. Supply voltage variations affect the available motor shaft power. If the supply voltage is lower than nominal the field weakening point shifts to a lower frequency and the available maximum torque of the motor is reduced in the field weakening range.

The maximum available torque is often limited by the frequency converter. This has to be considered already in the motor selection phase. The frequency converter may limit the motor torque earlier than stated in the motor manufacturer's data sheet.

The maximum available torque is also affected by transformers, reactors, cables, etc. in the system because they cause a voltage drop and thus the maximum available torque may drop. The system's power losses need to be compensated also by the frequency converter rating.

8.1 Pump and fan application (Example)

Some stages in pump and fan application dimensioning:

- Check the speed range and calculate power with highest speed.
- Check the starting torque need.
- Choose the pole number of the motor. The most economic operating frequency is often in the field weakening range.
- Choose motor power so that power is available at maximum speed. Remember the thermal loadability.
- Choose the frequency converter. Use pump and fan rating. If the pump and fan rating is not available choose the frequency converter according to the motor current profile.

Example 8.1:
A pump has a 150 kW load at a speed of 2000 rpm. There is no need for starting torque.

Solution 8.1:
The necessary torque at 2000 rpm is: $T = \frac{9550 * 150}{2000}\ \text{Nm} = 716\ \text{Nm}$

It seems that 2-pole or 4-pole motors are alternative choices for this application.



Figure 8.1 Motor loadability curves in a pump and fan application. Comparison of 1) 2-pole and 2) 4-pole motors.

1) Motor p=2
For a 2-pole motor the loadability at 2000 rpm according to the loadability curve is about 95 percent. The motor nominal torque must be at least:

$$T_n \geq \frac{716}{0.95}\ \text{Nm} = 754\ \text{Nm}$$

$$P_n \geq \frac{754 * 3000}{9550} \text{ kW} = 237 \text{ kW}$$

$$T_n = \frac{250 * 9550}{2975} \text{ Nm} = 803 \text{ Nm}$$

$$i_m = \frac{T_{load}}{T_n} * I_n = \frac{716}{803} * 431 \text{ A} = 384 \text{ A}$$

$$T_n \geq \frac{716 \text{ Nm}}{0.75} = 955 \text{ Nm}$$

$$P_n \geq \frac{955 * 1500}{9550} \text{ kW} = 150 \text{ kW}$$

$$\frac{150}{160} \quad 305 \text{ A} = 286 \text{ A}$$

A suitable motor could be for example a 55 kW (400 V, 110 A, 50 Hz, 984 rpm and 0.82) motor. The motor nominal torque is:

$$T_n = \frac{55 * 9550}{984} \text{ Nm} = 534 \text{ Nm}$$

The dimensioning current can be approximated at a speed of 1200 rpm:

$$i_m = \frac{T_{load}}{T_n} * \frac{n}{n_n} I_n = \frac{P_{load}}{P_n} * I_n = \frac{48}{55} * 110 \text{ A} = 96 \text{ A}$$

The nominal (continuous) current of the frequency converter must be over 96 A.

The starting torque requirement is less than motor's nominal torque.

If the inertia of the motor is 1.2 kgm^2 the dynamic torque in acceleration is:

$$T_{dyn} = \frac{2\pi}{60} * \frac{1200}{10} * 1.2 \text{ Nm} = 15 \text{ Nm}$$

The total torque needed during acceleration is 397 Nm which is less than the nominal torque of the motor.

A 6-pole motor current is 19 A smaller than with a 4-pole motor. The final frequency converter/motor selection depends on the motor and frequency converter frame sizes and prices.

8.3 Constant power application (Example)

Some stages in dimensioning of a constant power application:

- Check the speed range.
- Calculate the power needed. Winders are typical constant power applications.
- Dimension the motor so that the field weakening range is utilized.

Example 8.3:
A wire drawing machine is controlled by a frequency converter. The surface speed of the reel is 12 m/s and the tension is 5700 N. The diameters of the reel are 630 mm (empty reel) and 1250 (full reel). There is a gear with gear ratio $n_2 : n_1 = 1:7.12$ and the efficiency of the gear is 0.98.

Select a suitable motor and converter for this application.

Solution 8.3:
The basic idea of a winder is to keep the surface speed and the tension constant as the diameter changes.



Figure 8.3 Basic diagram of a winder.

In rectilinear motion the power is: $P = Fv$

In rotational motion the power is: $P = T\omega$

The relation between surface speed and angular velocity is:

$$v\,[m/s] = \omega * r = \frac{2\pi * n\,[rpm] * r}{60} \Leftrightarrow n\,[rpm] = \frac{60 * v}{2\pi * r}$$

Torque is a product of force and radius: $T = Fr$

By using the above formulas the motor can be selected:

$$P = 5700\ N * 12\ m/s = 68.4\ kW$$

$$T_1 = 5700\ N * \frac{0.63}{2}\ m = 1796\ Nm$$

$$n_1 = \frac{12 * 60}{\pi * 0.63}\ rpm = 363.8\ rpm$$

$$T_2 = 5700\ N * \frac{1.25}{2}\ m = 3563\ Nm$$

$$n_2 = \frac{12 * 60}{\pi * 1.25}\ rpm = 183.3\ rpm$$

The gear must be taken into account before choosing the motor. Speeds, torques and power have to be reduced:

$$P = \frac{P}{\eta_{gear}} = \frac{68.4}{0.98}\,kW = 69.8\,kW$$

$$T_1 = \frac{1796}{0.98} * \frac{1}{7.12}\,Nm = 275\,Nm$$

$$n_1 = 363.8 * 7.12\,rpm = 2590\,rpm$$

$$T_2 = \frac{3563}{0.98} * \frac{1}{7.12}\,Nm = 511\,Nm$$

$$n_2 = 183.3 * 7.12\,rpm = 1305\,rpm$$

1) Motor p=2
If a 2-pole motor is selected loadability at a speed of 1305 rpm is about 88 percent and 97 percent at 2590 rpm. The minimum nominal power of the motor is:

$$P_n \geq \frac{511 * 3000}{0.88 * 9550}\,kW = 182\,kW$$

A 200 kW (400 V, 353 A, 50 Hz, 2975 rpm and 0.86) motor is selected. The motor nominal torque is:

$$T_n = \frac{200 * 9550}{2975}\,Nm = 642\,Nm$$

The dimensioning current is calculated according to a torque of 511 Nm:

$$i_m = \frac{T_{load}}{T_n} * I_n = \frac{511}{642} * 353\,A = 281\,A$$

2) Motor p=4
If a 4-pole motor is selected it can be seen from the loadability curve that loadability at a speed of 1305 rpm is about 98 percent and about 60 percent at 2590 rpm. The minimum nominal power of the motor is:

$$P_n \geq \frac{511 * 1500}{0.98 * 9550}\,kW = 82\,kW$$

A 90 kW (400 V, 172 A, 50 Hz, 1473 rpm and 0.83) is selected. The motor nominal torque is:

$$T_n = \frac{90 * 9550}{1473} \text{ Nm} = 584 \text{ Nm}$$

Dimensioning in this case is done according to the motor current at 1305 rpm. The motor current is:

$$i_m = \frac{T}{T_n} I_n = \frac{511}{584} * 172 \text{ A} = 151 \text{ A}$$

With a 2-pole motor the field weakening (constant power) range was not utilized which led to unnecessary overdimensioning. A 4-pole motor is a better choice for this application.

Chapter 9 - Input transformer and rectifier

There are several types of input rectifiers. The rectifier type might limit the operation.

A conventional rectifier is a 6 or 12 pulse diode rectifier. Diode rectifiers only support motoring loads where the power flow is one way only.

In certain processes where the load can also be generating, the energy needs to be absorbed. For short generating loads the traditional solution has been a braking resistor where the power generated has been transformed into heat losses. If however the load is generating all the time, a true 4-quadrant rectifier is needed.

Both the input transformer and the rectifier are dimensioned according to the motor shaft power and system losses. For example if high torque at low speed is delivered the mechanical power is nevertheless quite low. Thus high overloads do not necessarily mean high power from the rectifier point of view.



Figure 9.1 Line current in a constant torque application. Line current is small at low speed.

9.1 Rectifiers

Rectifiers are dimensioned according to motor shaft power. A single drive's input rectifier can be selected using the approximation formula:

$$S_{rectifier} = \frac{P_{motor}}{0.9} \quad (9.1)$$

In drive systems where there is a common DC-link, there can be motoring and generating power at the same time. Rectifier power is then calculated approximately as follows:

$$S_{rectifier} = \frac{\Sigma P_{motoring}}{0.9} - 0.9 \Sigma P_{generating} \quad (9.2)$$

$$S_{transformer} = P_{total} * \frac{1.05}{k} * \frac{1}{\eta_r} * \frac{1}{\cos(\alpha)} * \frac{1}{\eta_c} * \frac{1}{\eta_i} * \frac{1}{\eta_m}$$

$$S_{rectifier} = \frac{48}{0.9} kVA = 53.3\ kVA$$

$$S_{transformer} = 48 * \frac{1.05}{0.95} * \frac{1}{0.985} * \frac{1}{0.97} * \frac{1}{0.95} kVA = 58.4\ k\text{'}^{\wedge}$$



ABB drives

Technical guide No. 8
Electrical braking

Power and productivity
for a better world™

Technical guide No. 8
Electrical braking

8

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AFE64362534 REV B EN 6.5.2011

Contents

Chapter 1 - Introduction 7

1.1 General 7
1.2 Drive applications map according to speed and torque 7

Chapter 2 - Evaluating braking power 9

2.1 General dimension principles for electrical braking 9
2.2 Basics of load descriptions 10
2.2.1 Constant torque and quadratic torque 10
2.2.2 Evaluating brake torque and power 10
2.2.3 Summary and conclusions 14

Chapter 3 - Electrical braking solution in drives 15

3.1 Motor flux braking 15
3.2 Braking chopper and braking resistor 16
3.2.1 The energy storage nature of the frequency converter 16
3.2.2 Principle of the braking chopper 17
3.3 Anti-parallel thyristor bridge configuration 19
3.4 IGBT bridge configuration 21
3.4.1 General principles of IGBT based regeneration units 21
3.4.2 IGBT based regeneration - control targets 21
3.4.3 Direct torque control in the form of direct power control 22
3.4.4 Dimensioning an IGBT regeneration unit 24
3.5 Common DC 24

Chapter 4 - Evaluating the life cycle cost of different forms of electrical braking 26

4.1 Calculating the direct cost of energy 26
4.2 Evaluating the investment cost 26
4.3 Calculating the life cycle cost 27

Chapter 5 - Symbols and definitions 31

Chapter 6 - Index 32

8

Chapter 1 - Introduction

1.1 General

This guide continues ABB's technical guide series, describing the practical solutions available in reducing stored energy and transferring stored energy back into electrical energy. The purpose of this guide is to give practical guidelines for different braking solutions.

1.2 Drive applications map according to speed and torque

Drive applications can be divided into three main categories according to speed and torque. The most common AC drive application is a single quadrant application where speed and torque always have the same direction, ie, the power flow (which is speed multiplied by torque) is from inverter to process. These applications are typically pump and fan applications having quadratic behaviour of load torque and thus often called variable torque applications. Some single quadrant applications such as extruders or conveyors are constant torque applications, ie, the load torque does not inherently change when speed changes.

The second category is two-quadrant applications where the direction of rotation remains unchanged but the direction of torque can change, ie, the power flow may be from drive to motor or vice versa. The single quadrant drive may turn out to be two quadrants for example if a fan is decelerated faster than mechanical losses could naturally achieve. In many industries also the requirement for emergency stopping of machinery may require two-quadrant operation although the process itself is single quadrant type.

The third category is fully four-quadrant applications where the direction of speed and torque can freely change. These applications are typically elevators, winches and cranes, but many machinery processes such as cutting, bending, weaving, and engine test benches may require repetitive speed and torque change. One can also mention single quadrant processes where the power flow is mainly from machinery to inverter such as in a winder or an uphill to downhill conveyor.

It is commonly understood that from the energy saving point of view the AC motor combined with inverter is superior to mechanical control methods such as throttling. However, less attention is paid to the fact that many processes may inherently include power flow from process to drive, but how this braking energy could be utilised in the most economical way has not been considered.



Figure 1.1 Drive applications map according to speed and torque.

Chapter 2 - Evaluating braking power

2.1 General dimension principles for electrical braking

The evaluation of braking need starts from the mechanics. Typically, the requirement is to brake the mechanical system within a specified time, or there are subcycles in the process where the motor operates on the generator side at constant or slightly varying speed.

It is important to note that devices used in electrical braking are dimensioned according to braking power. The mechanical braking power depends on braking torque and speed, formula (2.1). The higher the speed the higher the power. This power is then transferred at a certain specified voltage and current. The higher the voltage the less current is needed for the same power, formula (2.2). The current is the primary component defining the cost in low voltage AC drives.

In formula (2.2) we see the term cosϕ. This term defines how much motor current is used for magnetising the motor. The magnetising current does not create any torque and is therefore ignored.

On the other hand, this motor magnetising current is not taken from the AC supply feeding the converter, ie, the current to the inverter is lower than the current fed to the motor. This fact means that on the supplying side the cosϕ is typically near 1.0. Note that in formula (2.2) it has been assumed that no loss occurs when DC power is converted to AC power. There are some losses in this conversion, but in this context the losses can be ignored.

$$P_{mech} = T * \omega = T * \frac{n}{60} * 2\pi \quad (2.1)$$

$$P_{electrical} = U_{DC} * I_{DC} = \sqrt{3} * U_{AC} * I_{AC} * \cos\phi \quad (2.2)$$

2.2 Basics of load descriptions

Typically loads are categorised as constant torque or quadratic torque type. Quadratic load torque means that the load torque is proportional to the square of the speed. It also means that the power is speed to the power of three. In constant torque applications, the power is directly proportional to speed.

2.2.1 Constant torque and quadratic torque

Constant torque:

C: constant

$$T_{load} = C \tag{2.3}$$

$$P_{load} = T * \omega = C * \omega \tag{2.4}$$

Quadratic torque:

$$T_{load} = C * \omega^2 \tag{2.5}$$

$$P_{load} = T * \omega = C * \omega^2 * \omega = C * \omega^3 \tag{2.6}$$

2.2.2 Evaluating brake torque and power

In the case of steady state operation (the angular acceleration α is zero) the motor torque has to make friction torque correspond proportionally to the angular speed and load torque at that specific angular speed. The braking torque and power need in respect to time varies greatly in these two different load types.

$$T_{motor} = -[J * \alpha + \beta * w + T_{load}(\omega)] \tag{2.7}$$

Let us first consider the case where the load is **constant torque type** and the drive system is not able to generate braking torque, ie, the drive itself is single quadrant type. In order to calculate the braking time needed one can apply the following equation. Please note that formula (2.7) underlines that the torque needed for inertia accelerating (or decelerating), friction and load torque is in the opposite direction to the motor torque.

$$0 = -[J * \alpha + \beta * w + T_{load}(\omega)] \tag{2.8}$$

In practice, it is difficult to define the effect of friction exactly. By assuming friction to be zero the time calculated is on the safe side.



Figure 2.1 Cumulative braking time, braking load power and torque as a function of speed.

$$T_{load}(\omega) = J * \alpha = J * \frac{(\omega_{start} - \omega_{end})}{t} = J * \frac{(n_{start} - n_{end}) * 2\pi}{t * 60} \quad (2.9)$$

By solving t one ends up with the formula:

$$t = J * \frac{(n_{start} - n_{end}) * 2\pi}{60 * T_{load}(\omega)} \quad (2.10)$$

Assuming that the load inertia is 60 kgm^2 and the load torque is 800 Nm over the whole speed range, if the load is running at 1000 rpm and the motor torque is put to zero, the load goes to zero speed in the time:

$$t = J * \frac{(n_{start} - n_{end}) * 2\pi}{60 * T_{load}(\omega)} = 60 * \frac{(1000 - 0) * 2\pi}{60 * 800} = 7.85 \text{ s} \quad (2.11)$$

This applies for those applications where the load torque remains constant when the braking starts. In the case where load torque disappears (eg, the conveyor belt is broken) the kinetic energy of the mechanics remains unchanged but the load torque that would decelerate the mechanics is now not in effect. In that case if the motor is not braking the speed will only decrease as a result of mechanical friction.

Now consider the case with the same inertia and load torque at 1000 rpm, but where **the load torque changes in a quadratic manner**. If the motor torque is forced to zero the load torque decreases in quadratic proportion to speed. If the cumulative braking time is presented as a function of speed, one sees that

the natural braking time at the lower speed, eg, from 200 rpm to 100 rpm, increases dramatically in comparison to the speed change from 1000 rpm to 900 rpm.



Figure 2.2 Natural braking curve for a 90 kW fan braking load power and torque as a function of speed.

A natural braking curve can easily be drawn based on the power and speed at the nominal point applying the formulas (2.5) and (2.6).



Figure 2.3 Cumulative braking time for, eg, a 90 kW fan.

Let us now consider the case where the requirement specifies the mechanical system to be braked in a specified time from a specified speed.

The 90 kW fan has an inertia of 60 kgm^2. The nominal operating point for the fan is 1000 rpm. The fan is required to be stopped within 20 seconds. The natural braking effect caused by the load characteristics is at its maximum at the beginning of the braking. The maximum energy of inertia can be calculated from formula (2.12). The average braking power can be calculated by dividing this braking energy by time. This value is, of course, on the very safe side due to the fact that the fan load characteristics are not taken into account.

$$W_{kin} = \frac{1}{2} * J * \omega^2 = \frac{1}{2} * J * \left(\frac{n}{60} * 2\pi \right)^2 = P * t \qquad (2.12)$$

$$P = \frac{1}{2} * J * \left(\frac{n}{60} * 2\pi \right)^2 * \frac{1}{t} =$$

$$\frac{1}{2} * 60 * \left(\frac{1000}{60} * 2\pi \right)^2 * \frac{1}{20} = 16.4 \text{ kW} \qquad (2.13)$$

When the braking chopper is dimensioned for this 16.4 kW value and the motor braking capability at a higher speed is far more than 16.4 kW, the drive has to include a supervision function for maximum regeneration power. This function is available in some drives.

If one wants to optimise the dimensioning of the brake chopper for a specific braking time one can start by looking at figure (2.3). The speed reduces quickly from 1000 to 500 rpm without any additional braking. The natural braking effect is at its maximum at the beginning of the braking. This clearly indicates that it is not necessary to start braking the motor with the aforementioned 16 kW power in the first instance. As can be seen from figure (2.3) the speed comes down from 1000 rpm to 500 rpm without any additional braking within less than 10 seconds. At that point of time the load torque is only 25 percent of nominal and the kinetic energy conserved in the fan is also only 25 percent of the energy at 1000 rpm. If the calculation done at 1000 rpm is repeated at 500 rpm, it can be seen that the braking power in order to achieve deceleration from 500 rpm to 0 rpm is appr. 8 kW. As stated in previous calculations this is also on the safe side because the natural braking curve caused by the load characteristics is not taken into account.

To summarise, the target for a 20 second deceleration time from 1000 rpm down to 0 rpm is well achieved with a braking chopper and resistor dimensioned for 8.2 kW. Setting the drive regenerative power limit to 8.2 kW sets the level of braking power to an appropriate level.

$$W_{kin} = \frac{1}{2} * J * \omega^2 = \frac{1}{2} * J * \left(\frac{n}{60} * 2\pi \right)^2 = P * t \qquad (2.14)$$

$$P = \frac{1}{2} * J * \left(\frac{n}{60} * 2\pi \right)^2 * \frac{1}{t} =$$

$$\frac{1}{2} * 60 * \left(\frac{500}{60} * 2\pi \right)^2 * \frac{1}{10} = 8.2 \text{ kW} \qquad (2.15)$$

2.2.3 Summary and conclusions

There are two basic load types: constant and quadratic load torque.

Constant torque application:

- The load torque characteristic does not depend on the speed. The load torque remains approximately the same over the whole speed area.
- The power increases linearly as the speed increases and vice versa.
- Typical constant torque applications: cranes and conveyors.

Quadratic torque application:

- The load torque increases to speed to the power of two.
- When the speed increases, the power increases to speed to the power of three.
- Typical quadratic torque applications: fans and pumps.

Braking power evaluation:

- The quadratic load characteristics mean fast natural deceleration between 50-100 percent of nominal speeds. That should be utilised when dimensioning the braking power needed.
- The quadratic load torque means that at low speeds the natural deceleration is mainly due to friction.
- The constant load torque characteristic is constant natural deceleration.
- The braking power is a function of torque and speed at that specified operating point. Dimensioning the braking chopper according to peak braking power typically leads to overdimensioning.
- The braking power is not a function of motor nominal current (torque) or power as such.
- If the load torque disappears when braking starts the natural braking effect is small. This affects the dimensioning of the braking chopper.

Chapter 3 - Electrical braking solution in drives

The modern AC drive consists of an input rectifier converting AC voltage to DC voltage stored in DC capacitors. The inverter converts the DC voltage back to AC voltage feeding the AC motor at the desired frequency. The process power needed flows through the rectifier, DC bus and inverter to the motor. The amount of energy stored in DC capacitors is very small compared with the power needed, ie, the rectifier has to constantly deliver the power needed by the motor plus the losses in drive system.

3.1 Motor flux braking

Flux braking is a method based on motor losses. When braking in the drive system is needed, the motor flux and thus also the magnetising current component used in the motor are increased. The control of flux can be easily achieved through the direct torque control principle (for more information about DTC see Technical guide No. 1). With DTC the inverter is directly controlled to achieve the desired torque and flux for the motor. During flux braking the motor is under DTC control which guarantees that braking can be made according to the specified speed ramp. This is very different to the DC injection braking typically used in drives. In the DC injection method DC current is injected to the motor so that control of the motor flux is lost during braking. The flux braking method based on DTC enables the motor to shift quickly from braking to motoring power when requested.

In flux braking the increased current means increased losses inside the motor. The braking power is therefore also increased although the braking power delivered to the frequency converter is not increased. The increased current generates increased losses in motor resistances. The higher the resistance value the higher the braking energy dissipation inside the motor. Typically, in low power motors (below 5 kW) the resistance value of the motor is relatively large in respect to the nominal current of the motor. The higher the power or the voltage of the motor the less the resistance value of the motor in respect to motor current. In other words, flux braking is most effective in a low power motor.


120
80
40
0
5
10
20
30
40
50
f (Hz)
① 2.2 kW
② 15 kW
③ 37 kW
④ 75 kW
⑤ 250 kW

When to consider other solutions than braking chopper and resistor:

- The braking is continuous or regularly repeated.
- The total amount of braking energy is high in respect to the motoring energy needed.
- The instantaneous braking power is high, eg, several hundred kW for several minutes.
- The ambient air includes substantial amounts of dust or other potentially combustible or explosive or metallic components.

3.3 Anti-parallel thyristor bridge configuration

In a frequency converter the diode rectifier bridges can be replaced by the two thyristor controlled rectifiers in antiphase. This configuration allows changing the rectifier bridge according to the power flow needed in the process.

The main components of the thyristor supply unit are two 6-pulse thyristor bridges. The forward bridge converts 3-phase AC supply into DC. It feeds power to the drives (inverters) via the intermediate circuit. The reverse bridge converts DC back to AC whenever there is a need to pass the surplus motor braking power back to the supply network.



Figure 3.3 Line diagram of anti-parallel thyristor supply unit.

Only one bridge operates at a time, the other one is blocked. The thyristor-firing angle is constantly regulated to keep the intermediate circuit voltage at the desired level. The forward/reverse bridge selection and intermediate circuit voltage control are based on the measurement of the supply current, supply voltage and the intermediate circuit voltage. The DC reactor filters the current peaks of the intermediate circuit.

The main benefits of the anti-parallel thyristor bridge are:

– Well-known solution.
– Less investment needed than for an IGBT solution.
– The DC voltage can be controlled to a lower value than the network. In certain special applications this can be an advantage.

The main drawbacks of the anti-parallel thyristor bridge are:

– The DC bus voltage is always lower than AC supply voltage in order to maintain a commutation margin. Thus the voltage fed to the motor remains lower than the incoming AC. However, this can be overcome by using a step-up autotransformer in the supply.
– If the supplying AC disappears a risk of fuse blowing exists, due to the failure in thyristor commutation.
– The cosϕ varies with loading.
– Total harmonic distortion higher than in IGBT regenerative units.
– The current distortion flows through other network impedance and can cause undesired voltage distortion for other devices supplied from the point where voltage distortion exists.
– The braking capability is not available during main power loss.



Figure 3.4. Example of anti-parallel bridge current and voltage waveforms during braking.

3.4 IGBT bridge configuration

3.4.1 General principles of IGBT based regeneration units

The IGBT based regeneration is based on the same principles as power transmission within a power network. In a power network several generators and load points are connected together. One can assume that at the point of connection the power network is a large synchronous generator having a fixed frequency. The input IGBT bridge of the drive (later line converter) can be considered as another AC voltage system connected through a choke to the generator. The principle of power transfer between two AC systems having voltage U and connected to each other can be calculated from figure (3.4).

$$P = \frac{U_{line} * U_{rec}}{X} \sin\delta \qquad (3.4)$$

The formula indicates that in order to transfer power between these two systems there has to be a phase difference in the angle between the voltages of the two AC systems. In order to control the power flow between the two systems the angle has to be controlled.



Figure 3.5. Typical line current waveform and harmonics of an IGBT line generating unit.

3.4.2 IGBT based regeneration - control targets

There are three general control targets in IGBT based regeneration units. The first one is to keep the DC bus voltage stable regardless of the absolute value of power flow and the direction of power flow. This ensures that inverters feeding AC motors can work in an optimum way regardless of the operation point thanks to a stable DC bus voltage. The DC bus voltage is stable when the power flow into the DC bus equals the power flow out of the DC bus. This control of appropriate power flow is achieved by controlling the power angle between the two AC systems.



Figure 3.6. Fast change from regenerating to motoring operation. Note how stable the DC bus voltage is during this transition.

The second control target is to minimise the supply current needed, ie, to operate at cosφ = 1.0. This is achieved by controlling the output voltage of the line converter. In some applications it is desired that the IGBT line converter also works as an inductive or as a capacitive load.

The third control target is to minimise the harmonic content of the supply current. The main design criteria here are the impedance value of the choke and an appropriate control method.

3.4.3 Direct torque control in the form of direct power control

Direct torque control (DTC) is a way to control an AC motor fed by an inverter. The control principal turns IGBT switches on and off directly based on the difference between the actual AC motor torque and the user's reference torque (Technical Guide No. 1). The very same principle can be applied in a line converter controlling the power flow from power network to drive and vice versa. The power is torque multiplied by angular frequency, which in the network is constant, ie, controlling torque means also control of power flow.

$$P = \frac{U_l \, U_{lc}}{X} \sin\delta = |\underline{T}||\underline{\omega}| \qquad (3.5)$$



Figure 3.7. Fundamental control diagram for DTC based IGBT regeneration unit.

The DTC control method combined with IGBT technology contributes to a low amount of current harmonics. For that reason the IGBT supply unit can be used to replace single quadrant 12-pulse or 18-pulse supply configurations, which are typically used for reducing current harmonics on the supply side. An IGBT supply unit is therefore also a solution for those cases where current harmonics rather than the handling of braking energy is the issue.

The main benefits of an IGBT regeneration unit are:

- Low amount of supply current harmonics in both motoring and regeneration.
- High dynamics during fast power flow changes on the load side.
- Possibility to boost the DC voltage higher than the respective incoming AC supply. This can be used to compensate for a weak network or increase the motor's maximum torque capacity in the field weakening area.
- Full compensation of system voltage drops thanks to voltage boost capability.
- Possibility to control the power factor.
- Power loss ride through operation with automatic synchronisation to grid.
- DC bus voltage has approximately the same value during motoring or braking. No extra voltage stress on insulation of motor winding during braking.



Figure 3.8. Boosting capability of supplying voltage.

The main drawbacks of an IGBT regeneration unit are:

- Higher investment cost.
- The braking capability is not available during main power loss.
- High frequency voltage harmonics due to high switching frequency. These several kilohertz voltage components can excite small capacitors used in other electrical devices. With appropriate design and arrangement of feeding transformers for different devices these phenomena are eliminated.

When to use an IGBT regeneration unit:

- The braking is continuous or repeating regularly.
- The braking power is very high.
- When space savings can be achieved compared to the braking resistor solution.
- When network harmonics limits are critical.

3.4.4 Dimensioning an IGBT regeneration unit

The supply current dimensioning of the IGBT unit is based on power needed. Let us assume that the motoring shaft power needed is 130 kW and braking power 100 kW. To dimension the IGBT supply unit the maximum value of motoring or braking power is selected, in this case 130 kW. The motor voltage is 400 V. The minimum value for the supplying network is 370 V.

In this case the voltage boost capability can be utilised; the DC bus voltage is raised to correspond to an AC voltage of 400 V. However, the required supply current is calculated based on the 370 level. Assuming that there are 5 percent system losses in the motor and drive, the total power needed from the grid is 136.5 kW. The supplying current can be calculated from the formula:

$$I_{in} = \frac{P}{\sqrt{3} * U_{in}} = \frac{136.5\ kW}{\sqrt{3} * 370\ V} = 213\ A \qquad (3.6)$$

The IGBT regeneration unit is selected based solely on the calculated current value.

3.5 Common DC

When a process consists of several drives where one motor may need braking capability when others are operating in motoring mode, the common DC bus solution is a very effective way to reuse the mechanical energy. A common DC bus solution drive system consists of a separate supply rectifier converting AC to DC, and inverters feeding AC motors connected to the common DC bus, ie, the DC bus is the channel to move braking energy from one motor to benefit the other motors. The basic configuration of the common DC bus arrangement can be seen from figure (3.9).



Chapter 4 - Evaluating the life cycle cost of different forms of electrical braking

It has become increasingly important to evaluate the total life cycle cost when investing in energy saving products. The AC drive is used for controlling speed and torque. This basic function of AC drives means savings in energy consumption in comparison to other control methods used. In pump and fan type applications braking is seldom needed. However, modern AC drives are increasingly being used in applications where a need for braking exists.

Several technical criteria are mentioned above. The following examines the economic factors for different electrical braking approaches.

4.1 Calculating the direct cost of energy

The direct cost of energy can be calculated based, for example, on the price of energy and the estimated brak-ing time and power per day. The price of energy varies from country to country, but a typical estimated price level of 0.05 euros per kilowatt-hour can be used. 1 euro ~ 1 USD. The annual cost of energy can be calculated from the formula:

$$\text{Cost} = \text{Braking time (h/day)} * \text{Average braking power (kW)} * \text{price of energy (euros/kWh)} * 365 \quad (4.1)$$

For example, a 100 kW drive is running 8000 hours per year and braking with 50 kW average power for 5 minutes every hour, ie, 667 hours per year. The annual direct cost of braking energy is 1668 euros.

4.2 Evaluating the investment cost

The required investment objects needed for different braking methods vary. The following investment cost components should be evaluated.

Braking chopper:

- The additional investment cost of braking chopper and resistor plus the cost of additional space needed for those components.
- The investment cost of additional ventilation needed for the braking chopper.

Thyristor or IGBT based electrical braking:

– The additional investment cost of thyristor or IGBT regenerative braking in respect to the same power drive without electrical braking capability.

Common DC bus:

– The additional investment cost of braking chopper and resistor including the space needed for those components if needed in a common DC bus solution.
– The investment cost difference between common DC bus solution and the respective single drive solution.

4.3 Calculating the life cycle cost

The life time cost calculation supports the purely economic decision in making an investment. The price level of energy as well as the price of drives varies depending on the country, utility, size of company, interest ratio, the time the investment is used and the overall macroeconomic situation. The absolute values of prices given in the following examples are solely used to illustrate the calculation principles.

Case 1 - Occasional braking

Consider the following application case:
The continuous motoring power is 200 kW at a shaft speed of 1500 rpm. In the event of an emergency stop command the application is required to ramp down within 10 seconds. Based on the experience of the process an emergency stop happens once every month. The inertia J of the drive system is 122 kgm^2. When the emergency stop is activated the load torque can be neglected.

Calculating the braking torque needed for the motor:

$$T = J * \frac{(\omega_{start} - \omega_{end})}{t} = J * \frac{(n_{start} - n_{end}) * 2\pi}{t * 60} =$$

$$122 * \frac{(1500 - 0) * 2\pi}{10 * 60} = 1915 \text{ Nm} \qquad (4.2)$$

The typical torque value for a 200 kW, 1500 rpm motor is about 1200 Nm. A normal AC motor instantaneously controlled by an inverter can be run with torque at 200 percent of nominal value. To achieve higher torque values a proportionally higher motor current is also needed.

The braking power is at its maximum at the beginning of the braking cycle.

$$P_{br,\,max} = T * \omega = 1915 * \frac{1500}{60} * 2\,\pi \approx 300\ kW \tag{4.3}$$

The braking chopper and resistor have to withstand instantenously the current for a power of 300 kW. The average braking power is calculated below.

$$W_{kin} = \frac{1}{2} * J * \omega^2 = \frac{1}{2} * J * \left(\frac{n}{60} * 2\,\pi\right)^2 = P * t \tag{4.4}$$

$$P = \frac{1}{2} * J * \left(\frac{n}{60} * 2\,\pi\right)^2 * \frac{1}{t} =$$
$$\frac{1}{2} * 122 * \left(\frac{1500}{60} * 2\,\pi\right)^2 * \frac{1}{10} = 150.3\ kW \tag{4.5}$$

Cost of resistor braking:
The braking chopper needed is for a maximum braking power of 300 kW. If the drive has a power limitation function the braking resistor can be dimensioned according to the 150.3 kW. The additional cost of the braking chopper and resistor is 4000 euros. The braking resistor requires 0.4 m^2 additional floor space. The cost of floor space is 500 euros/m^2.

Due to the small total heating energy and emergency use of braking, the cost of additional cooling is considered negligible.

The total additional investment cost consists of:

- Braking chopper and resistor in cabinet, 4000 euros.
- Floor space 0.4 m^2 * 500 euros/m^2, 200 euros.

The total cost of wasted energy during one braking is:

$$Cost = \frac{10}{3600}\,(h) * \frac{300}{2}\,(kW) * 0.05\ (euros / kWh) = 0.02\ euros \tag{4.6}$$

In this case the cost of braking energy is negligible.

Cost of 4Q drive:
The additional cost of a respective investment for electrical braking with anti-parallel thyristor bridge in comparison with a drive with braking chopper is 7000 euros. As expected, the energy savings cannot be used as an argument to cover the additional investment required.

Case 2 - Crane application

Consider following application case:
Crane with hoisting power of 100 kW. The crane needs full power on both the motoring and generating side. The longest hoist operation time can be 3 minutes. The average on duty time over one year for the hoist is 20 percent.

Cost of resistor braking:
The braking chopper and resistor have to be dimensioned for continuous 100 kW braking due to the 3 minutes maximum braking time. Typically the maximum braking chopper dimensioning is made for a braking time of 1 minute in 10 minutes.

– Braking chopper and resistor in cabinet 7800 euros.

The mechanical construction of the crane allows having cabinets with braking chopper. No extra cost due to floor space.

It is assumed that for 50 percent of the duty time the crane operates on the generator side, ie, an average 2.4 h/day. The total cost of wasted energy is:

$$\text{Cost} = 2.4\ (\text{h/day}) * 100\ (\text{kW}) * 0.05\ (\text{euros/kWh}) * 365 = 4380\ \text{euros} \quad (4.7)$$

Cost of 4Q drive:
The IGBT 4Q drive is recommended for crane applications.

The additional investment cost for electrical braking with IGBT input bridge in comparison to drive with braking chopper is 4000 euros.

The direct payback calculation indicates that an additional 4000 euros investment brings the same amount of energy savings during the first year of use.

Case 3 - Centrifuge application

Consider the following application case:
Sugar Centrifuge with 6 pole motor 160 kW rating. The motor needs full torque for a period of 30 seconds to accelerate the charged basket to maximum speed of 1100 r/min, centrifuge then spins liquor off the charge for 30 seconds at high speed. Once the charge is dry motor decelerates the centrifuge as fast as possible to allow discharge and recharging.

In a batch cycle the charge, spin and discharge times are fixed, so the only opportunity to increase production is to increase the rates of acceleration and deceleration. This is achieved by using an IGBT 4Q drive as the DC link voltage can be boosted for operation in the field weakening range (1000 to 1100 r/min). This can save around 3 seconds per cycle, therefore reducing cycle time from 110 seconds to 107 seconds. This allows an increase in throughput meaning that the productivity of the process is improved. The cost premium for IGBT is 10 percent.

Chapter 5 - Symbols and Definitions

AC: Alternating current or voltage

B: Friction coefficient

C: Constant or coefficient

cosϕ: Cosine of electrical angle between the fundamental voltage and current

DC: Direct current or voltage

DPF: Displacement power factor defined as cosϕ1, where Ø1 is the phase angle between the fundamental frequency current drawn by the equipment and the supply voltage fundamental frequency component.

I: Current [Ampere, A]

J: Inertia [kgm^2]

n: Rotation speed [revolutions per minute,rpm]

P: Power [Watt, W]

PF: Power factor defined as PF = P/S (power/voltampere) = I_1 / I_s * DPF (With sinusoidal current PF is equal to DPF).

T: Torque (Newton meter, Nm)

t: Time

THD: Total harmonic distortion in the current is defined as

$$THD = \frac{\sqrt{\sum_{2}^{40} I_k^2}}{I_1} \qquad (5.1)$$

where I_1 is the rms value of the fundamental frequency current. The THD in voltage may be calculated in a similar way.

U: Voltage [V]

W: Energy [Joule, J]

ω: Angular speed [radian/second, 1/s]

Chapter 6 - Index

A
AC power 9

B
braking chopper 13, 14, 16, 17, 18, 19, 25, 26, 27, 28, 29
braking power 9, 10, 11, 12, 13, 14, 15, 16, 19, 24, 25, 28

C
centrifuge 29
common DC 24, 25, 27
constant torque 7, 10, 14
conveyors 7, 14
cosϕ 9, 20, 31
crane 29

D
DC injection braking 15
DC power 9
direct torque control 15, 22

E
energy storage 16, 17

F
fans 14
flux braking 15, 16
four-quadrant 7
friction 10, 11, 14, 31

H
harmonic distortion 20, 31

I
IGBT 20, 21, 22, 23, 24, 27, 29, 30
impedance 20, 22
inertia 10, 11, 13, 27, 31
inverter 7, 9, 15, 17, 22, 25, 27

L
line converter 21, 22

N
natural braking 12, 13, 14

O
overvoltage control 17

P
pumps 14

Q
quadratic torque 10, 14

R
rectifier 15, 16, 19, 24, 25

S
single quadrant 7, 10, 23, 25

T
thyristor bridge 19, 20, 28
two-quadrant 7

Contact us

For more information contact
your local ABB representative or visit:

www.abb.com/drives
www.abb.com/drivespartners

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.

3AFE64362534 REV B EN 6.5.2011 #15654

Power and productivity
for a better world™

ABB drives

Technical guide No. 9
Guide to motion control drives

Power and productivity
for a better world™

Technical guide No. 9
Guide to motion control drives

9

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AFE68695201 REV B EN 6.5.2011

Contents

Chapter 1 - Introduction 7

1.1. Motion control versus speed control 7
1.2. Decentralized or centralized control 8
1.3. Comparison between decentralized and centralized systems 9
1.4. Main functional parts of machine 9
1.5. Machine components 10

Chapter 2 - Drive and motor combination 11

2.1. Brush-type DC 11
2.2. Brushless DC 11
2.3. Asynchronous servo 12
2.4. Synchronous servo 13

Chapter 3 - Synchronous technology 14

3.1. Measuring performance 14
3.2. How synchronous servo motors differ from induction motors 15

Chapter 4 - Synchronous servo motor – principle of operation 16

4.1. Special conditions during start up 17
4.2. Traditional speed and current control 17

Chapter 5 - Typical servo motors data 19

5.1. Torque constant 19
5.2. Back EMF 19
5.3. Torque curve 19
5.4. Typical motor data 20

Chapter 6 - Feedback devices 21

6.1. Resolver 21
6.2. Incremental encoders 22
6.3. SinCos encoder 22

Chapter 7 - Motion control 24

7.1. General 24
7.2. Motion control – basic blocks 24
7.3. Motion control formulas and profiles 25
7.4. Motion profile 25
7.5. Position interpolator 25

Chapter 8 - Typical motion functions 26

8.1. Positioning 26
8.2. Absolute positioning 26
8.3. Relative positioning 26
8.4. Synchronization 27
8.5. Rollover axis 28
8.6. Dynamic limiter 28
8.7. CAM disk 28
8.8. Homing 29
8.9. Cyclic corrections 31
8.10. Encoder gear functions 32
8.11. Virtual master/axis 33

Chapter 9 - Application examples, distributed control 34

9.1. Cyclic correction for material handling. 34
9.2. Constant gap maintaining 35
9.3. Cut to length 36
9.4. Rotary knife 37
9.5. Cyclic correction, packing application 38
9.6. Flying shear, angled 39
9.7. Flying shear, parallel 40
9.8. Lathe 41
9.9. Material filling 42
9.10. Slitter 43
9.11. Picking and stacking 44
9.12. Warehouse automation 45
9.13. Winding 46
9.14. Wrapping 47

Chapter 10 - Motion control – *Glossary of terms 48

Chapter 11 - Index 62

Chapter 1 - Introduction

This guide aims to give users an overview of high performance drives and motion control. Although written in a simple style to make it relevant to most applications, readers need to have a basic understanding of AC drive technology to benefit from this guide.

When considering a motion control application it is important to consider all elements in the system including drives, motors, mechanical power transmission components, software, etc.

A high performance system has one or more of the following characteristics:

– high dynamic performance
– high accuracy reference following and repeatability
– high accuracy motion functions
– capability to run different motor types

1.1. Motion control versus speed control

Standard variable speed drives normally control the motor by giving a speed command. The system typically has no feedback and speed reference is preset speeds, 0 to 10 Volts, 4 to 20 mA, or fieldbus.

With motion control, there is always feedback of the real position. This is compared to the reference value and the difference is corrected continuously by the motion controller's profile generator.

Positioning is a good example that highlights this difference. If a standard drive is used for positioning, the motor normally runs at high speed, then decelerates to a lower speed and stops. Alternatively, the drive can follow an analog signal. Either way, no reference profile is followed, compared for errors or corrected. This results in low accuracy.

Accuracy can be improved if the controller is a high performance motion controller but in this case, the dynamics and the sample time (generally several milliseconds) of the standard drive become limiting factors.

1.2. Decentralized or centralized control

In a system with centralized control, one unit contains all the software and the drives just follow the reference value. There is no intelligence within the drive.



Figure 1.1 Simplified centralized system.

In a decentralized system, the field devices also have intelligence. This means that the cost of the control unit is reduced, as far less performance is required centrally.

Higher level commands

I/O

Figure 1.2 Simplified decentralized system.

1.3. Comparison between decentralized and centralized systems

Feature	Decentralized	Centralized	Benefits of decentralized control
Number of control wires	Low	High	Less cabling – lower cost Fewer potential faults wires
Cabinet	Less components, smaller size	More components installed	Labour and material cost saving
Programmable logic controller (PLC)	Control distributed	All control, additional hardware cost	Cost saving in PLC hardware
Time levels	Motion loop is closed in drive*	Motion loop is closed in controller	Good cost/ performance ratio
Drive-to-drive communication	Fast drive-to-drive communication improves communication	Not used	Less hardware

*This means that feedback is connected directly to drive. It does not go to PLC or motion controller for calculation which might cause delay.

More detailed information of motion control in chapter 7.

1.4. Main functional parts of machine

Machines using motion control and/or high performance drives consist of the following, all of which have a deciding influence on the performance of the system:

- Motion control hardware: this controls the operation of the system; it can be centralized or decentralized
- Motion control software: determines the functions of the machine by receiving input data and handling this according to the instructions set out in the software code
- Drive or amplifier – receives commands from the motion control software
- Motor – provides mechanical energy with the required speed and torque to drive the load in the specified way
- Mechanical power transmission components – belts, gear-boxes, clutches, ballscrews etc.



Figure 1.3 Constant gab maintaining.

1.5. Machine components

Figure 1.3 shows a basic setup. The distance between boxes on the conveyor belt varies and the purpose of the motion control software is to accelerate or decelerate the belt and space the boxes equally.

Main components:

- Drives and cables (power, feedback, control)
- Overriding control by PLC
- Motor encoder monitoring closed loop motor control and position information for cyclic correction
- Master encoder, giving speed reference of production line
- Fibre optic cable for communication between drives
- Fieldbus, encoder and drive-to-drive link
- Sensor giving 24 V on/off information to drive
- Synchronous encoder

Chapter 2 - Drive and motor combination

The drive and motor are normally supplied as a package to suit the application. The main drive, motor types and features are described here.

2.1. Brush-type DC

The basic principle is the same as in industrial high power DC drives, the main difference being that there is no magnetizing circuit. Instead, the motor carries permanent magnets on the stator side. Rotor current and voltage is supplied by brushes and a commutator.

Normally, it is not possible to use the supply voltage. Instead, a transformer is used to reduce the voltage. Some drives have a rectifier circuit, while others need an external voltage rectifier.

The electronics are relatively simple and only speed feedback is required for the speed controller. Brush-type DC drives is one of a small number of control platforms that actually use a tacho as a feedback device for the speed reference.

When this type of drive and motor combination is used in motion control, a pulse encoder is quite often fitted to the motor shaft. Pulses are sent to the motion controller for calculating the position.

The benefit of brush-type technology is the simple and inexpensive controller. The drawback is that the commutator and the brushes are mechanical components and have limited lifetime. Especially in applications where the motor always stops in the same position, the commutator gets worn in one particular place, thereby reducing its life even more.

The main players in the drives industry do not use this technology anymore. Typically these kinds of products are based on old analogue platform.

2.2. Brushless DC

The power circuit of a brushless DC servo drive is similar to that of an AC drive. Input current is rectified and filtered in a diode bridge with associated DC-link capacitance. The inverter unit consists of six power devices.

However, with a brushless DC drive the output voltage is not modulated to form sinusoidal current, unlike in an AC drive.

The other problem is phase delay in the amplifier circuit. As the frequency increases, the amplifiers tend to loose the original phase.



Figure 3.2 Amplifier's phase delay as a function of frequency.

3.2. How synchronous servo motors differ from induction motors

The main difference between synchronous servo motors and induction motors is in the motor shaft performance. With synchronous servo motors, rotor mass and diameter are minimized, leading to low inertia which in turn means the rotor does not need much torque to accelerate. Most of the torque produced can be used to run the load.

Typical features of synchronous servo motors:

- The motor efficiency is typically over 95 percent at full power.
- The motor has high power density – there is no rotor current and thus no build-up of heat in the rotor.
- The motors can run with high temperature rise, for example, at 40 degrees ambient, temperature rise/class H=125 ˚C is allowed.
- IP65 is the typical protection degree, compared to IP54 for standard induction motors.
- Standard AC induction motors are inexpensive. But for higher performance, additional feedback devices are needed and these can be costly.
- Other costs include encoders, fans making asynchronous servo motor a more attractive choice.
- High torque overload capability depends on the basic motor design and its magnetic materials. Generally, synchronous servo motor motors can deliver up to 2-5 times or more overload during short periods.
- Resolver, incremental encoder with commutation channels or various types of SinCos encoders can be used as feedback devices. Full digital feedback systems are also available.
- Recent development of drives and motion control systems, along with lower cost magnetic materials, has increased the market and number of applications for synchronous servo motor rapidly.

Chapter 4 - Synchronous servo motor – principle of operation

The synchronous servo motor does not have commutator or brushes. The drive (amplifier) maintains correct current distribution at the right vector angles and the right angular speed.

The rotor of synchronous servo motor is not symmetrical but has a magnetic polarity. The stator provides the three-phase sinusoidal current. The stator current forms the composite flux vector.



Figure 4.1 Magnetic fields at two positions.

The flux produced by permanent magnets and the flux produced by stator currents must be at exact opposites to maximize the repulsive and attractive forces of the magnetic fields.

These are the forces that build up torque and cause the motor shaft to rotate. This operation needs a feedback device that senses angular position of the shaft at all times, enabling the amplifier to set up sine output to the right angles.

4.1. Special conditions during start up

New motors can sometimes have a difference between the actual rotor position and that given by the feedback device. This needs to be corrected, otherwise inaccurate feedback results in the motor not being able to produce full torque and optimum performance.

The phase error can be resolved in different ways:

Initial startup:

- The drive features phasing error software which identifies the error during the commissioning run and uses its control algorithm to compensate for the error
- Error information from the motor manufacturer is entered as a parameter into the drive. This becomes important if a spare motor is installed and a non-load trial run is difficult to perform
- Some motor producers build in zero phase error during manufacture – this is the preferred option as it avoids the above tasks

Start up after power down:

- When powering up, the rotor position is known if the feedback device (such as resolvers and some SinCos encoders with communication bus) can give absolute position within one revolution.
- However, if an incremental encoder is used, then commutation channels are required. At start up, the motor is controlled in the trapezoidal manner, as long as the position is identified using the commutation signals. See also chapter 6, page 21 for feedback devices.

4.2. Traditional speed and current control

Figure 4.2 shows the basic principle of speed and current control.



Figure 4.2 Speed and current control loop.

The role of the servo drive or amplifier is to make sure that the motor speed and torque follows the reference value. The motor´s feedback gives actual speed to the speed controller. The speed controller is typically a PID controller comparing reference and feedback signals.

The error signal is passed to the current controller. The current controller, typically a PI amplifier, sets up the correct current so that the right torque is available to keep the speed at the reference level.

Chapter 5 - Typical servo motors data

5.1. Torque constant

The torque constant is an important measure given to the synchronous servo motor. It is expressed as Nm/A and determines how much torque is produced per ampere.

5.2. Back EMF

The permanent magnet motor acts like generator and builds up back EMF voltage which is related to angular speed. Back EMF is opposite to the supply voltage and is in direct relation to the angular speed.

Ke is voltage constant and is typically expressed in V/1000 rpm (voltage rms value).

5.3. Torque curve



Figure 5.1 Torque curves of a synchronous servo motor.

The picture shows a typical torque curve of an synchronous servo motor. It consists of a continuous torque curve and a short term overload curve. Typical values given as part of the motor data are:

- T stall which is nominal torque at zero speed
- T nominal which is nominal torque at nominal speed
- T peak which is maximum torque which is typically 2 to 5 times nominal torque.

Synchronous servo motors are normally selected so that the highest running speed is close to the nominal speed. One important limiting factor is back EMF.

When the speed increases, the back EMF increases. This means there is a limit where the back EMF would be equal to or higher than the drive's maximum output voltage.

Synchronous servo motors normally run at a voltage which is far lower than the drive's maximum output voltage. For example, 560 V may be used for the DC link drive and 300 V nominal for the motor. The reason is that the motor has to be able to recover from peak loads very quickly.

On the other hand there are technical solutions that make it possible to run synchronous motors in field weakening area.

This means that motor needs more current to the motor windings. This is achieved by increasing the voltage and thus there must be margin between nominal and maximum voltage. This is also the reason why maximum torque output starts to decrease when the speed becomes closer to nominal speed.

Synchronous servo motors do not typically have cooling fan. Some suppliers offer cooling fans as option. It increases the nominal and thus RMS torque, but not peak torque.

5.4. Typical motor data

This is a summary of typical nominal values and other motor data. The reference values are for ABB Servomotors series 8C.

Type	Continuous torque zero speed M_0 [Nm] (3)	Current at continuous torque I_0 [A] (1) (2) (3)	Rated torque M_N [Nm] (3)	Rated current I_N [A] (1) (2) (3)	Rated speed n_N [revi/min]	Mechanical rated power P_N [kW] (3)	Peak torque M_{max}	Current at peal torque $I_{ma}x$ [A] (1)	Motor current limit I_{limit} [A]
8C1.1.30	1.3	2.1	1.2	2	3000	0.38	4.6	8.1	13.8

Type	Torque constant K_{t0} [Nm/A] (1) (2) (3)	B.e.m.f. between phases at rated speed V [V] (1) (2) (3)	Resistance at terminals R_{UV} [W] (1) (3)	Inductance at terminals L_{UV} [mH] (4)	Moment of inertia of rotor J_m [revi/min]	Weight m [kg]	Curves (5)
8C1.1.30	1.05	190	20.8	47	0.9	3.1	501000

Chapter 6 - Feedback devices

High performance drives often use rotational feedback devices to give:

– speed feedback to the amplifier's speed controller
– position information to internal/external position control
– shaft position to the amplifier
– position information when acting as second encoder
– absolute position after black out

6.1. Resolver

A resolver is a rotational transformer. The most common type is a brushless resolver.

The resolver has a three coil arrangement. The reference signal, for instance an 8 kHz sine wave, is connected to the rotating part of the device via a transformer. This enables the coil carrying reference to rotate at the same speed as the shaft.

Two other coils are placed in 90 degrees phase shift. The rotational coil induces voltage in these coils. Output signals are fed to the amplifier and the speed and the position of the rotor is resolved by using these signals.

Frequently, resolver signals are converted to a pulse train for an external motion controller. In other words there is output that emulates encoder channels A, B and Z pulses. Read also encoder information.



Figure 6.1 The principle of a resolver.

6.2. Incremental encoders

Incremental encoders are widely used in various machine building applications.

The basic operation is based on a light source, a disk and a photo cell (sensor). The disk is installed between the light source and the sensor. The disk has a very fine mesh, enabling light to be visible or obscured to the sensor. The sensor output is digitized to form a square pulse when light is seen. When the disk rotates, the sensor produces a pulse train. The frequency of the pulse train is in relation to the speed of the axis and the receiving end can calculate this.

There are various specifications for encoders, but for motion control, two channels plus a zero channel is the most commonly used. Each channel is typically differential so that the output is A, A inversion, B, B inversion and Z, Z inversion.



Figure 6.2 Typical circuits and cables

6.3. SinCos encoder

The SinCos encoder operates in a similar way to the incremental encoder. It typically has three channels, A, B and Z. While the output from an incremental encoder is a digitized square wave, the SinCos encoder output is a number representing the full sine and cosine waves. The number of cycles can be, for example, 1024 full cycles, often also called “increments”. The receiving circuit of the drive calculates the increments and interpolates between these signals to improve the resolution. The interpolation depends on the sample time of the drive. For example, if the sample time is 250 us, a sample of sinus and cosine is taken every 250 us; the lower the speed, the higher resolution can be achieved (and visa versa). From a mathematical point of view, the angle is arctan ($\sin\alpha/\cos\alpha$).

Typically, the drive hardware outputs a quadrate signal of sine/cosine signals, so that what is seen is a pulse train input for calculation. The rising and falling edges of both channels can be utilized, giving four signals per cycle. This results in a number of signals that is four times higher than the number cycles specified in the encoder data.



Figure 6.3 Output of SinCos encoder with commutation channel.

The absolute position of the rotor is also needed at start up. This can be established by using a data link (next chapter) or by an additional sine/cosine channel. This channel provides one full sine and cosine cycle per revolution and makes it possible to find the rotor position. The Z-pulse position can be checked by ensuring that the Z pulse is “high” when the sine/cosine channels show zero position.



Figure 6.4 Interpolation within one cycle in SinCos encoder (1024 cycles per revolution)

SinCos encoders are also available with data bus. A data bus can give absolute position after power-down, a common requirement in today’s applications. This eliminates the need for homing routines after power-down. This makes the machine design simpler and increases the machine’s production time. Data of absolute position is also used at startup to identify the rotor position.

Chapter 7 - Motion control

7.1. General

Motion control covers many different functions. This chapter deals with basics of speed and motion and functional differences.

7.2. Motion control – basic blocks

Speed controlled drives change speed mainly in steps and the response is not very fast. Speed reference commands are given in certain levels and the drive frequently has its own ramp to move from one level to another. The drive does not follow a continuously changing reference track.

In motion control, the situation is different. The motor follows a continuously changing reference. The reference is created in a profile generator and this profile is compared to the feedback. P-amplifier compares signals and feeds the reference to the speed controller.



Figure 7.1 Motion control loop.



Figure 7.2 Position, speed and current control.

8.4. Synchronization

Synchronization means that a follower drive reads speed and positional reference from an external encoder or from the other drives. The gear ratio can normally be adjusted to suit the application. Synchronization can be absolute or relative and works for linear/rollover axes.



Figure 8.3 Relative synchronization.

Linear axis (Figure 8.3), relative synchronization: The follower drive starts to accelerate and continues to increase the speed to catch up with the speed of the master. When areas A and B are equal, the follower has caught up.



Figure 8.4 Absolute synchronization.

Linear axis, absolute synchronization: In this case, the reference is the total travel distance the master drive has to complete. The follower drive will run at a higher speed for long enough to catch up with the position of the master drive.

8.5. Rollover axis

Rollover axis mode is such that only one revolution is calculated and then calculation starts all over again.



Figure 8.5 Rollover synchronization.

The illustration shows how the follower drive catches up with the master drive's position.

8.6. Dynamic limiter

The picture shows a situation where the master speed is so high that a synchronization error is built up between the master and the follower drives. In this example, the error is corrected when a stop command is given. A dynamic limiter controls the speed of the follower until the positioning speed is reached and the follower runs to the position it should have according to parameter settings.



Figure 8.6 Dynamic limiter controls follower's speed.

8.7. CAM disk

Cam functions used to be achieved by mechanical means in the past. Traditionally, this method incorporates a rotational, non-symmetrical tool that forms a reference to another tool.

This type of system is not very flexible and contains mechanical parts that loose accuracy with wear.

In most cases these mechanical systems can be replaced by electrical CAM systems. The CAM profile is created in a CAM table where the user enters the values. Each master position has corresponding slave position.

The cam function is very useful in for example flying shears.

CAM disk table	
Master position	Follower position
0	0
20	20
40	20
60	40
80	40
100	60
120	90
140	120
160	150
180	180
200	150
220	120
240	90
260	60
280	40
300	40
320	20
340	20
360	0



Figure 8.7 CAM disk table values vs CAM profile.

8.8. Homing

Homing is required at start up and if position is lost due to power loss of system. If absolute encoder is used the real position is known as soon as power comes back. One way around is to use auxiliary power supply (typically 24 V).

What ever the system is home position has to be determined at start up. Following discuss applications without absolute encoder and explains some typical homing routines.

If there is only homing limit switch, software checks the status of switch. If switch is on the load must move towards positive speed until switch turns off and then load is at home position.



Figure 8.8 Homing started with homing switch on.

Vice versa if switch is off load must drive to negative direction until switch turns on and then back up slightly until switch turns off again.



Figure 8.9 Homing started with homing switch off.

The better result or say accuracy can be achieved by using zero pulse and pre latch function. This works in the following way:

- At commissioning the absolute position of zero pulse is know or can be set up
- The distance between proximity switch and zero pulse must be within one revolution
- As soon as proximity switch becomes active software starts to seek zero pulse and stops at zero pulse or to determined distance from it. The idea is that mechnical switch might be inaccurate, due to mechanical stress for example and thus gives rough positional information. Zero pulse is then very accurate and free of drift.



Figure 8.10 Homing with prelatch and zero pulse.

8.9. Cyclic corrections

Cyclic corrections are used in many applications where, due drift or material misplacement, the position needs to be corrected. This is valid for both roll over and linear movement.

Cyclic corrections always need latch information of position. This could come from an external sensor or Z-pulse of the encoder.

A few examples are the best way to show functionality.



Figure 8.11 Master/follower conveyor lines

In Figure 8.11, a master/follower set-up is described. The purpose is to make sure that cans on two conveyors have the correct distance between each other, 10 mm in this example.

The follower needs to know the speed of master. There are two ways to set this up:

1. Read the master´s speed from the encoder. This means that the follower has connections for two encoders. The master is running in open loop mode.

2. The other solution is to use communication between drives like fibre optical DDCS link. The master has a feedback connection (encoder) and this information is fed via optical link to the follower.

What ever the communication method, proximity switches are connected to the follower's (programmable) digital I/O. The follower compares the distance difference seen by the sensors and corrects the distance, in this example to be 10 mm.

8.10. Encoder gear functions

Motion control applications always need feedback. This can be connected to the motor, the load or both.



Figure 8.12 Motor encoder gear ratio to be used.



Figure 8.13 Load encoder gear ratio to be used.

If there is no encoder on the load side, load gear ratio has to be set up according to gear ratio, as the drive must control the actual position of the load, using feedback from the motor.



Figure 8.14 Both motor and load have an own encoder.

8.11. Virtual master/axis

Virtual master means that the reference values are applied to a model of a rotational axis that runs in the software. The virtual axis gives its speed reference to all its followers. The virtual axis gives full noise-free speed and positional signal in applications where two or more drives are synchronized.

Virtual axis is also very useful during system commissioning, as parts of machines can be tested without running the whole process.

Chapter 9 - Application examples, distributed control

This chapter briefly describes some typical motion control applications. Most of illustrations include a PLC the role of the PLC is to handle overriding control information. The control actions are executed in the distributed controlled drives.

9.1. Cyclic correction for material handling.



The purpose of this machine is to correct any angular error of the material. Two drives are used in a master/follower set-up. The master determines the main line speed. The follower receives a speed reference. Two sensors are connected to digital inputs. The follower calculates the error distance in number of pulses between two sensor signals. This error is corrected by increasing or decreasing the speed of the follower.

Depending on the application, different types of motors can be selected. Feedback will always be required.

9.2. Constant gap maintaining



This conveyor has a feed belt, an adjusting belt and a receiving belt. The boxes arrive with random spacing. The drive receives the line speed reference from the encoder. The sensor follows the rises and falls of the top line of the boxes. When the sensor detects a box, it follows the top edge of the box until length of the box is run. The dropping edge is seen by the sensor and the distance to the next rising edge is the actual gap between boxes. This is compared to the required gap and the software makes the necessary correction by altering the speed of the adjusting belt.

9.3. Cut to length



There are many methods to cut different materials to the required length. Here, we cover the most common methods. These are examples only; there are many other configurations.

In applications where the line is stopped to make the cut, both axes use the positioning feature of drive. The drive that is fed the material first runs a determined number of revolutions corresponding to the required material length. When the target position has been reached, the drive signals to the PLC that it is in the required position. The cutting motor runs the required number of revolutions to execute the guillotine operation. Its drive the gives the feed motor permission to run. As in other applications, the dynamic performance requirements of the system have to guide the motor selection.

9.4. Rotary knife



A rotary knife is used to cut material into required length or cut off unwanted material. The simplest rotary knives are synchronized to the line speed using an electrical gear. However, in many applications, this will not give satisfactory performance.

There are a number of considerations to take into account for rotary knife operations. Firstly, if the cutting length varies, it must be decided whether the tool should be at standstill or rotate continuously. Secondly, when the tool hits the material, it will in most cases need to have the same speed as the line. Thirdly, it is important to determine where to place the cut.

For more sophisticated applications, the knife must form a motion profile during the cycle. When the knife is at standstill and a cut command is given, it has to accelerate to reach the position and then decelerate to cutting speed. After cutting, the tool should return to the home position as fast as possible to be ready for the next cut.

In some cases, the tool may not be able to stop but has to start another cut “on the fly”. This means using two profiles that are added together. Cam profiles with flexible parameter setting are normally used in these situations.

9.5. Cyclic correction, packing application



From a software perspective, this is same operation as example 13.1, “Cyclic correction for material handling”. The difference is the physical set-up. In both examples, there is master-follower set-up and sensors for actual position checking and software correction. The system has two feeding conveyors. The items on them must be arranged to the correct distance between each other.

9.6. Flying shear, angled



A flying shear is a cutting machine that allows constant material flow during cutting. It is base on right-angle trigonometry. When the speed of the line and the speed of the saw are known, the angle of the cut can be calculated and adjusted accordingly. In this illustration, the angle means that blade moves in the direction of the line when the saw operates. Saw speed control is not critical; even an uncontrolled motor can be used; however the most practical solution would be to use a general machinery drive.

The cutting point can be indicated by a mark on the material or through rotational measurement by encoder. Typically, synchronizing or CAM functions are used.

This setup is often used in applications where the material must be cut by a saw rather than a knife/guillotine.

9.7. Flying shear, parallel



This is another version of the flying cut. As described earlier, the cut point is read from a mark or an encoder. The carriage waits for a “cut” command. When the command is given, the carriage accelerates to line speed whilst synchronizing itself to the cutting point. Typically, synchronizing or CAM functions are used and a guillotine performs the cutting. The illustration shows a system with two motors. Both drives run at synchronous speed using the master/follower function. There are also systems using only one motor.

9.8. Lathe



Although this illustration is very simplified, it shows the three main motion functions of a lathe.

The line speed must be constant. This means the speed of the spindle motors must be controlled and adjusted in relation the changing diameter of the material. This can be controlled by a PLC or distributed to a drive with winding software.

The two main motors run as master at master follower set up. This is particularly critical in plywood manufacturing, where the spindle heads are connected to the material on a screw thread. If the motors run at different speeds, one of two screw heads will begin to open until eventually, the log flies off.

The carriage with the blade is running in synchronous mode. The gearing ratio is set up in relation to the material thickness. It is very easy to set up the required thickness just by adjusting the gear ratio parameters; these are typically converted so that user can specify units in millimeters from the HMI.

9.9. Material filling



This application is very similar to the one described in chapter 13.3, “Cut to length”, although in this case, the follower drive runs dosing unit.

This is only one of many possible configurations; there are several other ways of filling packets and bottles.

9.10. Slitter

This illustration describes the cutting and winding part of a slitter, showing the operation of the cutting tools. Each tool is individually connected to the screw. When a tool is engaged, the PLC sends the address to the drive. The distributed control system ensures correct positioning.

9.11. Picking and stacking



This application uses distributed control in three shafts. The overriding controller gives commands to each shaft to make the material flow of the plates fluent. The plates are picked up with the picking tool using position control. The plate, still in position control, is moved forward to the stacking place. Finally the plate is positioned down to build up the stack. The plates feeding conveyor can run in continuous speed or position control mode.

9.12. Warehouse automation



Warehouse automation applications can be configured very cost-effectively using distributed control. The overriding control system is part of the full factory automation system and knows where the pallets need to go.

In most cases, high speed and torque performance is needed at and from zero speed. This means that closed loop control is required.

System dynamic requirements differ between applications and motor selection ranges from standard AC motors with feedback to AC brushless induction or permanent magnet servo motors.

This type of systems can have large physical dimensions and motor feedback will not be sufficiently accurate for position control in all cases. This is overcome by using a second encoder that monitors the actual position.

9.13. Winding



The application picture here is much simplified. The purpose is to show the main principle of traverse control. Traverse control is an electronic gear function where the gear ratio is set up so that traverse linear movement is locked to the build-up of material. The illustration does not show the limit switches that typically control the turning point action.

Winding and unwinding are well-established applications and there are many dedicated software packages commercially available.

9.14. Wrapping

The illustration shows a simple packaging application. The electrical gear is formed between two motors.

Chapter 10 - Motion control – *Glossary of terms

Acceleration

The rate of increase of velocity, usually expressed as meters per second per second, or meters per second^2 (m/s^2).

Accuracy

The measured value compared to the desired value. In motion control, this will most often refer to a position description, defined in terms a plus or minus deviation from the commanded value, or in terms of a range of values around the set point.

Active front end

A front end processor which receives data from both upstream and downstream equipment and makes changes without reference to external controls.

Actual position

The position of an axis compared to the desired position. This can be either the final position at the end of the move or the lag between the commanded position and the measured position at any point during the move. The latter is commonly known as following error.

AC servo

A motor drive that generates sinusoidal shaped motor currents.

Alarm

A warning that a parameter has moved out of acceptable or defined limits or an indication that a component has failed or is malfunctioning. It can either warn or advise an operator or be in the form of an output signal that can initiate corrective action or switch a process off.

Analog servo

Most commonly found in hydraulic and similar systems, an analog servo uses analog control and feedback systems such as voltage variation and changes in pressure.

Analog signal

A signal that varies in step with the parameter being measured. Typical examples include a 0-10 volt motor control signal and a pneumatic control pressure.

Axes of motion

The major directions along which controlled movement of a machine part or component occurs. These axes are usually defined as follows:
X: Linear motion in positioning direction
Y: Linear motion perpendicular to positioning direction
Z: Vertical linear motion
A: Angular motion around X (roll)
B: Angular motion around Y (pitch)
C: Angular motion around Z (yaw)

Axis

The main directions along which a tool, component or workpiece will move.

Brushless servo

A servo drive which uses electronic commutation of the current rather than achieving it through mechanical brushes and a commutator.

Bus

A series of conductors acting as path to send information between control elements and components.

Centralized control

A system with the software located in one physical unit. All input information from sensors and feedback devices are connected to this unit and control commands are sent from it.

Circular interpolation

A process of moving a component in a circle by moving along two axes in a series of straight lines generated by software.

Close motion loop

The reference signal is compared to the feedback signal and the discrepancy is corrected in an amplifier circuit.

Collision detection

Describes the process of using sensors to detect a possible collision between parts or components. The sensors can produce alarms to stop the movement or slow it to produce a low speed mating of the components.

Commutation

Ensuring that the correct motors phase receive the correct currents or voltages. It can be done electromechanically via the brushes and commutator as in brush type motors, or electronically as used in brushless motors.

Converter

Changing AC to DC or DC to AC, most often with a diode rectifier or thyristor rectifier circuit. The term “converter” may also refer to the process in an adjustable frequency drive. This consists of a rectifier, a DC intermediate circuit, an inverter and a control unit.

Co-ordination

Integration two or more axes of motion to produce an otherwise impossible motion. Sensors and other internal or external commands may also be used to assist the movements.

Current controller

An electronic function which gives the proper instant current needed by the load. The current is controllable to limit the maximum current and reduce the danger of overloads damaging the motor.

Cut to length

An algorithm that feeds material a set distance so that a process can be performed on a correctly sized length. Feedback systems are usually used to ensure that the selected length is repeated accurately.

DC bus

A common communications circuit that uses a DC voltage as reference. The term may also refer to a power distribution system shared by several components.

Deceleration

The rate of decrease of velocity. Usually measured in units of velocity change for each unit of time, ie, meters/sec/sec or, meters/sec^2.

Decentralized control

A control method made up of separated control elements distributed over an area or process. The individual elements are essentially independent of each other, although they will have some means of communicating.

Deterministic scan time

The frequency at which a programmable logic controller (PLC) executes a program. Normally measured in milliseconds this will include the time required to read a specific set of instructions and return to the initial instruction.

Device level network

A common network cable that eliminates individual links between the PLC and each device.

Diagnostic code
A code displayed on an operator interface or in a program, used to indicate a fault condition as well as usually its position.

Digital motion control
A motion control system that uses binary code for calculating.

Digital servo
A servo motor that uses binary code for all calculations and feed back.

Digital signal
A signal in the form of binary pulses if information, based on voltage levels that represent the values 0 and 1.

Drive
An electronic device that controls the electric current supplied to a motor.

Efficiency
The efficiency of a motor compares the mechanical output to the electrical input and is a measure of how well the motor turns the electrical energy it receives into a useful mechanical output.

Electronic cam profiles
A technique that replaces mechanical cams with electronics to perform non-linear motion.

Electronic clutch
A method of using electronic cams or gearing functions to produce a slave profile based on a master position.

Electronic gearing
Simulating mechanical gears by electrically synchronizing one closed loop axis to a second.

Electronic line shaft
A virtual axis which synchronizes other axes either through using electronic gearing or camming profiles.

Encoder
A feedback device that translates mechanical motion into electrical signals that indicate position. Incremental and absolute encoders are used to indicate incremental or absolute changes of position respectively.

Encoder resolution

The number of electrically identified positions in a 360 degree rotation of a shaft.

EnDat

A standard interface for serial data transfer, particularly for position and parameters.

EMC/CE

European Directive that sets standards and limits for conducted and radiated emissions. Drives may need line filters or other components to conform to the directive.

Emergency stop

An emergency stop function must meet all of the following requirements:

- It must override all other functions and operations under all conditions
- Power to machine actuators that can cause hazard must be interrupted as quickly as possible without creating other hazard
- Reset must not initiate a restart
- The emergency stop shall be either a Category 0 or a Category 1 stop. The choice of emergency stop must be decided in accordance with the requirements of the application

Ethernet

A very widely used open networking standard. Normally used for office automation and operating at a communications speed of 1.5 megabits/sec, newer versions are capable of up 100 megabits/sec.

Event

When an input parameter changes state, such as at the triggering of a limit switch or proximity sensor.

Fault

A condition a drive or control is in having attempted an illegal process and becoming disabled.

Feedback

When a controlled machine sends a signal to inform that it has responded to a control signal.

Feedback device

Give information of the actuators' real speed and position to the motion controller.

Feed forward
A method that compensates for known errors in a control loop. It depends only on the command, not the measured error.

Fiber optic
A glass or plastic fiber guide that transmits light that is translated into current or used to determine the open/close state of a current path.

Fieldbus
A local area network, as defined by ISA standard S50.02 and which is used to connect control elements and sensors to each other.

Flying restart
When a motor is restarted while spinning, normally done by sampling the motor speed, encoder input, or back EMF.

Flying virtual master
The ability of a motion controller to switch from one virtual encoder to another instantaneously. This feature makes it possible to use advanced synchronizing features.

Following error
The difference between the commanded position of an axis and its actual position, a difference that varies with the speed of the axis.

Frameless motor
A motor consisting of only the stator and rotor. This allows a manufacturer to incorporate it into a machine directly, cutting the need for any shafts or other mechanical transmissions.

Gantry
An overhead framework that can move in the X, Y, and/or Z axes, carrying a variety of tools or devices to perform tasks.

G code
Software used for programming machining processes, such as 3-axis milling and 2-axis wire cutting.

Hard, real-time control
The ability of a controller to respond to an event immediately. PLCs are designed for this, though PCs pose more of a problem.

Hardware limit switch
A switch that alters the electric circuit associated with the machine or equipment and which is operated by some part or motion of a power-driven machine or equipment.

Holding brake
A friction device which sets a brake when power is removed.

Home position
A position which acts as a reference for all absolute positioning movements. It is normally set at power-up and remains valid as long as the control system is operational.

Homing
The act of calibrating axes by finding a unique reference position, usually at power up.

Human-machine interface (HMI)
A console which displays data and receives commands, allowing the operator to control the drive.

IGBT insulated-gate bipolar transistor
The IGBT is usually used in switching power supplies and in motor control applications and forms the basis of the most modern and capable variable speed drives.

Inching
Advancing a motor in small steps through repeated closure of a switch.

Indexer
An electronic device that allows a PLC to control the movements of a stepping motor.

Indexing
An axis or axes moving to a pre-programmed position.

Inertia
A property of matter in which a body continues in a state of rest or uniform motion unless acted on by an external force.

In position window
A range of acceptable positions around the commanded position point.

Interpolation
When two or more axes move in a co-ordinated way to produce a linear or circular motion.

Inverter
A device that converts DC power to AC power. Typically used as a part of the frequency converter.

Jerk limitation
A feature that limits the rate of change of acceleration with the aim of eliminating mechanical jerking during speed changes.

Jitter free synchronization
The process of matching the acceleration and deceleration of a driven slave drive to the master drive to provide a smooth transition.

Jog
An axis moving at a fixed velocity and acceleration/deceleration rate, in a chosen direction, but with no specific destination.

KP
Velocity Loop Proportional Gain. Determines how much velocity error the servo system will allow during a move. See also: Tuning

KV
Position Loop Gain. Determines how much positioning error, or following error, will be allowed by the servo system during a move. See also: Tuning

Length units
The linear units for programming and configuring an axis, often defined in inches, feet, meters, or millimeters.

Linear
Where the output varies in direct proportion to the input.

Loop update times
The time required to calculate the process variable from the following error.

Motion control
Any tool or actuator controlled by motion software. The system can be hydraulic, pneumatic, electronic or any combination of these. Whatever the system, the profile for movement is written into the software code and the actuator has to follow this as accurately as possible. The actual movement and the reference are always compared by feedback devices and the motion controller aims to minimize the discrepancy.

Modulo Value
The position increment at which a rotary axis position returns to 0, ie, 360 degrees.

Noise

An unwanted electrical signal, usually the result of radio frequency or electromagnet ie, interference from devices such as AC power lines, motors, generators, transformers and radio transmitters.

Offset

Distance between the actual zero reference point and a programmed zero reference point.

Open architecture

Hardware and/or software with standard features that numerous vendors can incorporate into their own products, which can then connect to each other and work together easily.

Open loop/close loop

Open loop control is where a control system has no external references with which to govern its speed or position. A closed loop control system is one which uses signals fed back from external sensors in order to correct the position or velocity and make it conform to the commanded value.

Overcurrent

A current above the rated current of the drive, applied to maintain a set position or move to a new position.

Override

The act of forcing an axis to move during a fault condition. It is often used to force an axis to move away from an overtravel limit switch.

Overshoot

Where the output of a system goes beyond the desired value.

Over temperature

A warning or alarm that indicates that a motor or drive is too hot, most often the result of too high current demand.

PC

Personal computer

Phasing

Adjusting the position of one axis with respect to others, to correct for small registration problems, usually done while the axes are moving.

PLC

Programmable logic controller. A computer that uses fast, repeatable deterministic scan times to control equipment.

PLS

Programmable limit switch. A device that converts the rotary motion of a shaft into digital signals. It is typically used to improve positioning accuracy.

Point-to-point wiring

Wiring each drive directly to the PLC. The method cuts out the communication delays introduced by a network.

Position error

Error caused when the difference between the actual position and the command position is greater than a set amount.

Positioning

When a move is specified by target position, velocity and acceleration. The target position can be an absolute position, or one relative to the current position.

Position loop

Signals that generate position information based on position feedback.

Printmark synchronization

A method of controlling speed by comparing the position of a mark on a product with its expected position and then compensating for the difference.

Profile

A graphical representation of movement, with axes of position vs. time, velocity vs. time or torque vs. time.

Programmable limit switch

See PLS

Programming language

A stylized communication method for controlling the behavior of a machine.

Protocol

A specified method of encoding information for transmission.

Pulse width frequency

The switching rate of an IGBT.

Pulse-width modulation

A switch-mode control method based on varying on/off times of the voltage pulses applied to the transistors.

Quadrature
A technique used to detect direction of motion based on separating signal channels by 90’ (electrical).

Ramp function generator
Device or mathematical model that produces a square, triangular or sinusoidal wave output.

Rated speed
The maximum speed at which a motor can rotate.

Real master
Feedback that provides position information for a synchronized axis.

Rectifier
A device that converts AC power into DC for use by converter drives.

Referencing
The setting of a feedback device relative to the real world.

Regen
A motor /drive system can produce regenerative power during deceleration, power that can be fed to other machines on the network.

Resolver
A type of position transducer that uses magnetic coupling to measure absolute shaft position.

Rollfeed
A function that keeps the linear speed of the feed material constant as the diameter of the rotary axis changes.

Rotary
Moving in a circular way, with measurement of position based on degrees.

Safe off
A method of ensuring that power will not travel from the drive to the motor.

SCADA
Supervisory Control & Data Acquisition.
A system of software and hardware that controls a production process and collects data on its efficiency.

S curve

A way of accelerating and decelerating a motor slowly to reduce mechanical shock. Although more sophisticated than linear acceleration, it does not have the performance of camming.

Sequence of operation

A series of steps that causes a machine to perform an action.

SERCOS

Serial Real-time Communications Standard. An open communications protocol for motion-control networks, with transmission speeds over a fiber-optic cable of up to 4 megabits/sec.

Serial communications

The transmission of digital 1s and 0s in a series over a single cable.

Servo mechanism

An automatic, closed-loop motion control system that uses feedback to control a desired output, for example position, velocity, or acceleration.

Servo motor

A motor that can be precisely controlled. The drive that powers it gets accurate feedback on the motor's position from a resolver or encoder.

Shielded cable

A cable that has a metallic sleeve encasing the conductors at its centre The metal sleeve is grounded to prevent electrical noise affecting the signals on the cable.

SinCos

An encoder used in servo control. It outputs both digital and high resolution analog signals.

Software limit switch

A switch based on software rather than a physical object. It is used to turn physical outputs on and off, depending on the level of a particular input, from devices such as servo motors, resolvers or encoders.

SSI

Acronym for serial synchronous interface. A type of multi-turn absolute encoder that sends position information as a serial string in Gray code format.

Synchronization
When several functions of a machine follow a common control signal.

Tachometer
An electromagnetic feedback transducer that provides an analog voltage signal proportional to the rotational speed of a motor.

Task
A software system control that determines the execution rates and priority levels for software modules running in a drive or PLC.

TCP/IP
Transmission Control Protocol/Internet Protocol. A method of encoding data into a series of “packets” for transmission over a network, initially designed for the Internet but now often used in production control.

Teach position
The position of an axis that is “taught” into the motion control program. Once the axis is moved to the desired position, the “teach position” is entered into the motion program automatically by the control.

Telegram
A data packet used to communicate between controller and device.

TeleService
A feature that allows a controller or PLC to be serviced.

TN
Velocity Loop Integral Action Time. Associated with KP. When the measured velocity moves beyond the tolerance value set in KP, TN determines how quickly the drive will bring the velocity back within the specified tolerance. See also: Tuning

Torque limitation
A servo function that allows the current supplied to a servo motor to be monitored and limited.

Tuning
Adjusting the servo drive’s internal characteristics to give it the ability to control the reflected inertia and give the axis a smooth position/velocity profile.

Twisted pair

Two wires twisted together with the aim of eliminating electrical noise.

VxWorks™

VxWorks™ is a real-time operating systems that guarantees an absolutely deterministic response. Its benefits include real-time behavior, stability, operating time and an efficient memory efficiency.

Velocity

The speed at which a motor or mechanical system runs.

Velocity loop

A servo control function that adds a velocity command signal to a speed feedback signal. The resultant signal is output as a torque command signal.

Virtual master

An encoder signal created in software of a motion control to allow several servo systems to be synchronized.

Warning

An error condition received from a drive or a controller, indicating that a fault will occur if the problem is not rectified.

Wintel

Microsoft's Windows™ operating system running on Intel's microprocessors, an industry standard for PCs.

Zero point of feedback

The point at which the encoder position and the physical position of a servo motor line up.

* Glossary of terms resource list:
OMAC Motion for Packaging Working Group, Education Subcommittee, Glossary of Motion Control Terms, August 2001.

Chapter 11 - Index

A
absolute positioning 54
acceleration 12, 25, 55, 57, 59
AC drive technology 7
algorithm 12, 14, 17, 50
analogue 11
asynchronous 12, 14, 15
asynchronous servo motor 15

B
back EMF 12, 19, 20, 53
brushes 11, 16, 49
brushless 11, 49
brushless DC 11, 12

C
CAM functions 39, 40
centralized control 8
centralized system 8
centrally 8
coils 21
commutator 11, 16, 49
composite flux vector 16
computing power 12
control system 10, 43, 45, 51, 54, 56, 59
control unit 8, 50
cyclic correction 10

D
DC-link capacitance 11
decentralized control 9
decentralized system 8
distance 10, 25, 27, 30, 31, 34, 35, 38, 50
DTC control 12
dynamic 7, 13, 28, 36, 45

E
efficiency 15, 51, 58, 61
electronic 46, 49, 51, 54, 55
encoders 15, 17, 22, 31, 51, 59

F
fans 15, 20
feedback 7, 9, 10, 11, 12, 13, 15, 16, 17, 18, 21, 24, 31, 32, 45, 48, 49, 51, 55, 57, 58, 59, 60, 61
fieldbus 7
flux 16
flying shear 39

H
hardware 9, 58
heat 15
high performance drives 7, 9, 12
high power DC drives 11

I
induction 12, 14, 15, 45

J
jerk 25

L
lathe 41
linear and roll-over positioning 26

M
magnetizing circuit 11
magnetizing current 14
material handling 34, 38
motion control 1, 3, 7, 9, 10, 11, 15, 22, 24, 34, 48, 51, 59, 60, 61
motion control application 7
motion controller 7, 9, 11, 21, 52, 53, 55
motion loop 49

O
overload 15, 19

P
packing application 38
performance 7, 8, 9, 12, 13, 14, 15, 17, 21, 36, 37, 45, 59
permanent magnets 11, 16
phase 13, 15, 16, 17, 21, 49
phase delay 15
phasing error 17
PLC 9, 10, 34, 36, 41, 43, 50, 54, 56, 57, 60
poles 14
position 7, 10, 11, 12, 13, 16, 17, 21, 24, 25, 26, 27, 28, 29, 30, 31, 32, 36, 37, 38, 45, 48, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61
position control 21, 45
positioning 7, 26, 28, 36, 43, 49, 54, 55, 57
position interpolator 25
profile generator 7, 24
pulse encoder 11

R
reference profile 7
reference value 7, 8, 18
resolver 12, 21, 59
rotary knife 37
rotor 12, 13, 15, 16, 17, 20, 21, 53
rotor current 15
rotor position 12, 17

S
sample time 7
second encoder 21, 45
sensor 12, 22, 31, 34, 35, 52
servo 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 45, 48, 49, 51, 55, 59, 60, 61
sinusoidal 11, 12, 14, 16, 48, 58
slip 12
slitter 43
speed controller 11, 12, 17, 18, 21, 24
synchronous servo motor 13, 15, 16, 19
synchronous servo motors 15

T
temperature rise 15

V
vector 12, 16
velocity 25, 48, 50, 55, 56, 57, 59, 60, 61

W
winding 14, 21, 41, 43

Z
zero pulse 30

Contact us

For more information contact
your local ABB representative or visit:

www.abb.com/drives
www.abb.com/drivespartners

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.

3AFE68695201 REV B EN 6.5.2011 #115652

Power and productivity
for a better world™

ABB drives

Technical guide No.10
Functional safety

Power and productivity
for a better world™

Technical guide No. 10
Functional safety

10

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.
3AUA0000048753 REV D EN 30.3.2011 #15511

Contents

About this document **7**

Part 1 – Theory and background **8**

Safety and functional safety 9
Machinery Directive 9
Changes in the new Machinery Directive 11
Hierarchy of the European harmonized standards system 12

Part 2 – New approach **14**

Two standards – IEC and ISO 15
Standards for risk minimization 16
Standards for electronic safety systems 16
Product-specific safety standards (type-C standards) 18
Specific standard for safety-related drive systems 18
Standardized safety functions 19

Part 3 – Steps to meet Machinery Directive requirements **22**

STEP 1: Management of functional safety 23
STEP 2: Risk assessment 24
STEP 3: Risk reduction 26
STEP 4: Establishing safety requirements 28
STEP 5: Implementing functional safety system 32
STEP 6: Verifying a functional safety system 33
STEP 7: Validating functional safety system 37
STEP 8: Documenting functional safety system 37
STEP 9: Proving compliance 38

Glossary **40**

Index **42**

10

Disclaimer

This document is an informative guide intended to assist the users, specifiers and manufacturers of machinery and the related people in achieving a better understanding of the requirements of the EU Machinery Directive, and the measures required to achieve conformity with the directive and the harmonized standards under it.

This document is not intended to be used verbatim, but rather as an informative aid.

The information and examples in this guide are for general use only and do not offer all of the necessary details for implementing a safety system.

ABB Oy Drives does not accept any liability for direct or indirect injury or damage caused by the use of information found in this document. The manufacturer of the machinery is always responsible for the safety of the product and its suitability under the applicable laws. ABB hereby disclaims all liabilities that may result from this document.

About this document

This document introduces the Machinery Directive and the standards that must be taken into account when designing a machine, in order to ensure operational safely.

The aim of the document is to explain, in general terms, how the process for meeting the requirements of the Machinery Directive is carried out and CE marking is obtained. CE marking indicates that the machinery conforms to the requirements of the Directive.

Note:
This document gives only an overview of the process for meeting the essential requirements of the Machinery Directive. The manufacturer of the machinery always remains ultimately responsible for the safety and compliance of the product.

The document is divided into three parts:

- Part 1 – Theory and Background – introduces the idea behind functional safety and how to comply with the Machinery Directive. It also presents the upcoming changes in the new Machinery Directive and explains the hierarchy of the European harmonized standards system.
- Part 2 – New Approach – presents the new Machinery Directive related standards that are replacing old standards. It also introduces the two standard systems and lists a number of safety relevant standards and safety functions.
- Part 3 – Steps to Meet Machinery Directive Requirements – introduces nine steps that help in the process of fulfilling the essential requirements of the Machinery Directive.

Part 1 – Theory and background

The national laws of the European Union require that machines meet the Essential Health and Safety Requirements (EHSR) defined in the Machinery Directive and in the harmonized standards under the Directive. This means that all new machinery must fulfill the same legal requirements when supplied throughout the EU. The same standards are also recognized in many areas outside Europe, for example through equivalency charts, which facilitates machinery trade and machine shipments between countries within and even outside the EU.

Why must machinery meet these requirements? Because conformity helps to prevent accidents and consequent injury. Furthermore, by complying with the Machinery Directive and the relevant harmonized standards, machine manufacturers can rest assured they have met their obligations to design and deliver safe machines that comply with national laws.

For manufacturers, new and improved safety strategies are becoming a way of improving their productivity and competitiveness in the market. The aim of conventional safety systems has been to achieve comprehensive operational safety and meet legal obligations. This has been done by using add-on electrical and mechanical components, even at the cost of productivity. Operators can, in certain circumstances, override these systems when attempting to improve productivity, which can lead to accidents.

With modern safety systems, the safety of the processes and the operator can be taken into account while maintaining productivity. One example of this is keeping the machine running but at a lower speed to maintain safe operation. With modern safety solutions, safety can be an integrated part of machine functionality, and safety solutions are not just afterthoughts, added in order to meet regulations.

Safety systems can be implemented effectively through defined processes, to achieve specific safety performance and use certified subsystems as building blocks for safety systems. Meeting safety standards is expected in the industry, and certified subsystems such as drives are becoming a must in the marketplace. Machine safety is one of the most rapidly growing areas of importance in industrial automation.

Safety and functional safety

The purpose of safety is to protect people and the environment from accidents and, in this case, from machinery. Functional safety systems do this by lowering the probability of undesired events, so that mishaps are minimized when operating machinery. Safety standards define safety as freedom from unacceptable risk. What is acceptable is defined by society. Machine builders should always use the same (the most stringent) acceptability criteria for all market areas, regardless of regional differences.

The most effective way to eliminate risks is to design them away. But if risk reduction by design is not possible or practical, safeguarding through static guards or functional safety is often the best option. When machines are stopped quickly and safely or operated at a reduced speed during specific times, in order to reduce risk, higher machine productivity, uptime and less abrupt safety system behavior can be achieved. At the same time, the legal obligations are met and the safety of people and the environment is ensured.

Functional safety in machinery usually means systems that safely monitor and, when necessary, take control of the machine applications to ensure safe operation. A safety-related system is a system that implements the required, necessary safety functions. Functional safety systems are designed to detect hazardous conditions and return operation to a safe state, or to ensure that the desired action, such as safe stopping, takes place.

Monitoring can include speed, stopping, direction of rotation, and standstill. When the safety system is executing an active safety function, for example monitoring a crawl speed, and the system behavior deviates from that which is expected (for example, the system runs too fast), the safety system detects the deviation and actively returns machine operation to a safe state. This can be done, for example, by stopping the machine safely and lowering the torque of the motor shaft.

A safety system is not part of standard machine operation, but any failure in the safety system will immediately increase the risks related to machine operation.

Machinery Directive

The Machinery Directive, with the harmonized standards listed thereunder, defines the Essential Health and Safety Requirements (EHSR) for machinery at European Union level. The EHSR are listed in Annex I of the Machinery Directive.

The idea behind the Machinery Directive is to ensure that a machine is safe and that it is designed and constructed so that it can be used, configured and maintained throughout all phases of its life, causing minimal risk to people and the environment.

The EHSR state that when seeking solutions for designing and building safe machines, machine manufacturers must apply the following principles in the given order (also known as the 3-step method):

1. Eliminate or minimize the hazards as much as possible by considering safety aspects in the machine design and construction phases.
2. Apply the necessary protection measures against hazards that cannot be eliminated.
3. Inform users of the risks that remain despite all feasible protection measures being taken, while specifying any requirements for training or personal protective equipment.

Complying with the EHSR of the Machinery Directive allows the machine manufacturer to affix the CE marking on the machine. With CE marking the manufacturer guarantees that the product meets all regulations on the free movement of goods, as well as the essential requirements of the relevant European Directives, in this case the Machinery Directive.

Note:
There might also be other directives that apply, eg, low voltage directive and EMC directive. Only Machinery Directive requirements are covered in this guide.

Note:
CE marking according to the Machinery Directive is affixed only on a complete machine, not to the components of which it consists. Thus, the manufacturer of the product, or the representative of the manufacturer, is responsible for CE marking, not the manufacturer of the component that is included in the final product.

The machine manufacturer is responsible for carrying out the related risk analysis, following through the steps presented in Part 3, and ensuring compliance with the requirements. The component manufacturer is responsible for realizing the safety performance (SIL / PL level) of the said component's safety function, when the component is appropriately used. A component in this case could be a safety relay, or an AC drive with integrated safety functionality.

Changes in the new Machinery Directive

A new Machinery Directive 2006/42/EC, replaced the old Directive 98/37/EC, from December 29, 2009 onward.

There are no dramatic changes between the old and the new, revised Directive. The aim of the new Directive is to reinforce the achievements of the old Machinery Directive on the free circulation and safety of machinery and to improve its application.

Highlights of the changes in the current Machinery Directive are compared to the previous directive as follows:

- **Changes in how conformity is evaluated for dangerous machines listed in the Machinery Directive's Annex IV.**
  Along with the new directive, the manufacturer can carry out self-certification without a recognized test center. In order to do this, the manufacturer must have a quality assurance procedure that has been implemented according to the requirements presented in the Machinery Directive's Annex X.

- **Changes in the Essential Health and Safety Requirements that are presented in the Machinery Directive's Annex I.**
  The manufacturer must now carry out a risk assessment on the EHSR.

- **Changes in proving the safety of different products.**
  The same machine regulations will apply to machinery, exchangeable equipment, safety components etc. The products must include CE conformity assessment, declaration of conformity and the requisite user information.

- **Changes in the requirements for part or incomplete machines.**
  A part or an incomplete machine is a component or a series of components that cannot, by themselves, perform a specific function. Such a part is attached to other parts, incomplete machines or machines to form a machine according to the definition in the Machinery Directive.

  In addition to the manufacturer declaration, the manufacturer must now also supply a declaration of incorporation that defines which requirements of the directive apply to the part or incomplete machine and have been complied with. Product documentation must also include installation instructions.

- **Changes concerning the Low Voltage Directive.**
  The scope of the Low Voltage Directive is now related to a product instead of a risk. There is also now a clearer differentiation between the Machinery Directive and the Low Voltage Directive.

– **Changes in hazard analysis.**
  The hazard analysis is replaced by mandatory risk assessment and risk evaluation.

– **Changes in production control.**
  Series machines have now internal production controls, specified in the Machinery Directive's Annex VIII.

– **Changes in the validity of EC Type Examination certifications.**
  A recognized test center must inspect the certifications every five (5) years. Manufacturers and test centers must retain the relevant technical documents for 15 years.

Hierarchy of the European harmonized standards system

The European Committee for Standardization, CEN, and the European Committee for Electrotechnical Standardization, CENELEC draw up the harmonized standards. All harmonized standards carry the prefix "EN".

A list of the harmonized standards can be found on the European Commission Internet pages, http://ec.europa.eu.

The majority of harmonized standards are referenced by one or more Directives. To ensure that the essential requirements of the Machinery Directive are followed, it is advisable to apply the appropriate harmonized European standards. By designing machines according to these standards, manufacturers can demonstrate that they comply with the Machinery Directive and, generally, do not require certification by a third party.

Note:
Exceptions for the machines listed in Annex IV of the Machinery Directive must be noted.



Figure 1-1 Hierarchy of European harmonized standards

– Type-C standards are specific to a machine or class of machine. If there is a type-C standard for a machine, the associated type-B and possibly also type-A standards become secondary. When designing safety functions, type-C standards define additional, mandatory requirements for the machines they are intended for. However, if no type-C standard exists for the machine, type-B and type-A standards offer help in designing and constructing machines that meet the requirements of the Machinery Directive.
– Type-B standards deal with safety requirements that are common to the design of most machines. These standards give information on possible risks and how to handle them, with the help of a risk reduction process. Type-B standards can be divided into two groups, B1 and B2. Type-B1 standards deal with specific safety aspects and type-B2 standards handle safety-related equipment in general. Type-B1 standards are, for example, EN 62061:2005 and EN ISO 13849-1:2008. Type-B2 standards include standards for defining emergency stops, such as EN ISO 13850:2008.
– Type-A standards handle design principles and basic concepts for the machine. One example of a type-A standard is the basic safety standard EN ISO 12100-1.

Note:
It is not mandatory to apply the standards, but they offer recommendations and guidance for meeting the requirements of the Machinery Directive, which must be conformed to.

Part 2 – New approach

Note:
The old standard EN 954-1 has been superseded by standards EN ISO 13849-1 and EN 62061 in 2006. However, the EN954-1 still provides the presumption of conformity in parallel with the new standards EN ISO 13849-1 and EN 62061 during a transition period, which ends on December 31, 2011 (original three year transition period from 2006 to 2009 was extended by two years, until the end of 2011).



Figure 2-1 Transition period from old to new standards

Replacing the EN 954-1 standard with EN ISO 13849-1 and EN 62061 (which is applicable only to electrical control systems) is a shift from a deterministic approach, where cause-effect relationships were well known, towards a probabilistic or reliability approach in safety-related systems. The new standards take account of the probability of failure for the entire safety function, not only of its components. Unlike the old standard EN 954-1, these new standards also allow the use of programmable safety systems.

The new approach continues to use the designated architectures (categories) concept of EN 954-1, and additionally introduces new concepts, such as life-cycle thinking, quantification – component reliability and test quality – and common cause failure analysis.

Note:
Standard EN ISO 13849-1 has maintained the categories introduced in EN 954-1. It provides methods for design and verification based on the said categories. Standard EN 62061 includes similar designated architectures and methodology.

EN 954-1 has been a relatively simple standard that has offered a straightforward and quick process for determining a safety category for a machine. The process in standard EN ISO 13849-1 is similar, but somewhat more complex because, in addition to determining the category or architecture of the system, the machine manufacturer must now also ensure the safety of the machine by performing assessments and calculations. Using certified subsystems for building safety is recommended, as they make specifying the process quicker and require fewer calculations.



Figure 2-2 Introducing standards

Two standards – IEC and ISO

There are two alternative standards that can be followed when implementing functional safety systems in compliance with the Machinery Directive: The International Organization for Standardization (ISO) standard and the International Electrotechnical Commission (IEC) standard.

Following either of the standards leads to a very similar outcome, and their resulting safety integrity levels (SIL) and performance levels (PL) are, in fact, comparable. For more information, see the comparison table in Part 3, step 6.

A table explaining the suitability of the two new standards for designing systems with particular technologies can be found in standards EN ISO 13849-1 and EN 62061.

Note:
It is up to the machine manufacturer to decide which – if any – safety system creation standard is to be used (EN ISO 13849-1 or EN 62061), and then they must follow the same, chosen standard all the way from beginning to end to ensure congruity with the said standard.
CEN standards are based on ISO standards and are basically for mechanical equipment – new standards have numbers in the 10,000 series, while CENELEC standards are based on IEC standards – new standards have numbers in the 60,000 series.

Note:
EN ISO standards are presented in this document using the "ISO" mark. However, EN IEC standards are presented without "IEC" mark, according to the convention used in the harmonized standards list.

Standards for risk minimization

Basic safety standards for risk minimization include:

- **EN ISO 12100-1:2003**
  (Safety of machinery – Basic concepts, general principles for design) and
- **EN ISO 14121-1:2007**
  (Safety of machinery – Risk assessment).

EN ISO 12100 gives designers a general framework and guidance, providing a strategy for risk reduction (the three-step method). EN ISO 12100-1 defines the basic terminology and methodology used in achieving machine safety.

EN ISO 14121-1 is a new standard for risk assessment used in the risk reduction process, which is presented in the EN ISO 12100 standard. EN ISO 14121-1 has replaced the EN 1050:1996 standard, which expired on June 24, 2008.

Note:
All other references to these standards in this document always apply to the above mentioned versions of the standards.

Standards for electronic safety systems

The standards for electronic safety systems are as follows:

- **EN ISO 13849-1:2008** (Safety of machinery – Safety-related parts of control system – Part 1: General Principles for design),
- **EN ISO 13849-2:2008** (Safety of machinery – Safety-related parts of control system - Part 2: Validation)

- **EN 62061:2005** (Safety of machinery – Functional safety of safety-related electrical, electronic and programmable electronic control systems),
- **IEC 61508 ed. 2.0:2010** (Functional safety of electrical / electronic / programmable electronic safety-related systems), and
- **EN 60204-1:2006** (Safety of machinery – Electrical equipment of machines – General requirements).

Note:
All other references to these standards in this document always apply to the above mentioned versions of the standards.

EN ISO 13849-1 is a standard that provides instructions to designers to make machines safe. These instructions include recommendations for the design, integration and validation of the systems. It can be used for the safety-related parts of control systems and various kinds of machinery, regardless of the technology and energy it uses. The standard also includes special requirements for safety-related parts that have programmable electronic systems. This standard covers the entire safety function for all devices included (a complete safety chain, for example sensor–logic–actuator).

The standard defines how the required Performance Level (PL) is determined and the achieved PL verified within a system. PL describes how well a safety system is able to perform a safety function, under foreseeable conditions. There are five possible Performance Levels: a, b, c, d and e. Performance Level “e” has the highest safety reliability, while PL “a” has the lowest.

EN ISO 13849-2 specifies the validation process for safety functions designed according to EN ISO 13849-1.

EN 62061 is a standard for designing electrical safety systems. It is a machine sector specific standard within the framework of IEC 61508. EN 62061 includes recommendations for the design, integration and validation of safety-related electrical, electronic and programmable electronic control systems for machinery. The entire safety chain – for example sensor–logic–actuator – is covered by this standard. Individual subsystems need not be certified, as long as the entire safety function fulfills the defined requirements. However, using certified subsystems as building blocks is still strongly recommended, as this will potentially save considerable effort in the design process.

Note:
Unlike EN ISO 13849-1, EN 62061 does not cover requirements for non-electrical safety-related control equipment for machinery.

This standard defines how a Safety Integrity Level (SIL) is defined. SIL is a representation of the reliability of the safety functions. There are four possible safety integrity levels: 1, 2, 3, and 4. “SIL 4” is the highest level of safety integrity and “SIL 1” the lowest. Only levels 1-3 are used in machinery.

IEC 61508 is a basic functional safety standard. It covers the lifecycle of systems comprised of electrical and/or electronic and/or programmable electronic components that are used to perform safety functions. IEC 61508 is not a harmonized standard, but it is the main standard that outlines the requirements and methods for designing safety related control systems with complex hardware and software. IEC 61508 is generally used when designing certifiable safety subsystems. Standards EN ISO 13849-1 and EN 62061 are based on the principles set in IEC 61508.

EN 60204-1 offers recommendations and requirements for the electrical equipment of machines in order to enhance safety and usability.

Product-specific safety standards (type-C standards)

Product-specific safety standards, known as type-C standards, handle a specific machine or class of machines and are based on a presumption of conformity with respect to the EHSR covered by the standard.

It should be noted that:

- The requirements specified in the type-C standards generally overrule the requirements set by the general safety standards (EN 62061, EN ISO 13849-1, etc.).
- Type-C standards may have set SIL / PL requirements for some safety functions. At least these requirements must be met, regardless of the results of the risk analysis.

Note:
Even if the lists of hazards possibly affecting the machine, composed during the risk assessment, and the type-C standard are identical, the standard may not take account of all of the relevant EHSR. The standard must always be inspected thoroughly to determine what hazards might have been excluded from the list.

Specific standard for safety-related drive systems

A specific standard for safety-related drive system is:

- **EN 61800-5-2:2007** (Adjustable speed electrical power drive systems - functional safety requirements).

Note:
All other references to this standard in this document solely apply to the above mentioned version of the standard.

EN 61800-5-2 gives specifications and recommendations for power drive systems used in safety-related applications. It is a product standard that presents safety-related aspects in terms of the framework of IEC 61508, and introduces requirements for power drive systems when used as subsystems in safety systems.

Standardized safety functions

Standard EN 61800-5-2 includes definitions for numerous safety functions. A drive may offer one or more of these functions. Here are some examples:

Safe torque-off (STO)
This function brings the machine safely into a no-torque state and / or prevents it from starting accidentally.



Safe stop 1 (SS1)
This function stops the motor safely, initiating the STO function below a specified speed or after a defined time limit.



Safe stop 2 (SS2)
This function stops the motor safely, initiating the SOS function below a specified speed or after a defined time limit.

Safe operating stop (SOS)
This function keeps the motor in a safe standstill while holding the motor torque.

Safely-limited speed (SLS)
This function prevents the motor from exceeding the defined speed limit.



Safe direction (SDI)
This function prevents the motor shaft from moving in an unwanted direction.



Safe brake control (SBC)
This function provides a safe output for controlling external (mechanical) brakes.

Safe speed monitor (SSM)
This function provides a safe output indicating that the speed is under the specified speed limit.



See standard EN 61800-5-2 for more examples of safety functions.

Emergency operations
Standard EN 60204-1 introduces two emergency operations, emergency switching-off and emergency stop.

Emergency switching off
The emergency switching-off function disconnects power to a system or part of it should the risk of an electric shock arise.

This function requires external switching components, and can not be accomplished with drive based functions such as **Safe torque-off (STO).**

Emergency stop
An emergency stop must operate in such a way that, when it is activated, the hazardous movement of the machinery is stopped and the machine is unable to start under any circumstances, even after the emergency stop is released. Releasing the emergency stop only allows the machine to be restarted.

The emergency stop can stop hazardous movement by applying the following actions:
– optimal deceleration rate until the machine stops
– by using one of the two emergency stop categories, 0 or 1, or
– by employing a predefined shutdown sequence.

Emergency stop category 0 means that the power to the motor is cut off immediately. Stop category 0 is equivalent to the **Safe torque-off (STO)** function, as defined by standard EN 61800-5-2.

Emergency stop category 1 means that the machine speed is brought to a standstill through controlled deceleration and then the power to the motor is cut off. Stop category 1 is equivalent to the **Safe Stop 1 (SS1)** function, as defined by standard EN 61800-5-2.

When actuated, the emergency stop function must not create any additional hazards or require any further involvement by the machine operator.

Note:
The principles for the design of an emergency stop function are introduced in standard EN ISO 13850:2008.

Prevention of Unexpected Startup
Ensuring that a machine remains stopped when persons are present in danger area is one of the most important conditions in safe machines.

The **Safe torque-off (STO)** function can be used to effectively implement the prevention of unexpected startup functionality, thus making stops safe by preventing the power only to the motor, while still maintaining power to the main drive control circuits. Prevention of unexpected startup requires for example a lockable switch in addition to the STO function.

The principles and requirements of the prevention of unexpected startup are described in the standard EN 1037:1995+A1.

Part 3 – Steps to meet Machinery Directive requirements

The Machinery Directive requires machinery to be safe. However, there is no such thing as zero risk. The objective is to minimize the risk.

Compliance with the Machinery Directive can be achieved:

- by meeting the requirements set by the harmonized standards or
- by having a machine acceptance investigation carried out by an authorized third party.

The process for fulfilling the EHSR of the Machinery Directive using harmonized standards can be divided into nine steps:

- **Step 1: Management of functional safety** – managing functional safety during the lifecycle of the machine.
- **Step 2: Risk assessment** – analyzing and evaluating risks.
- **Step 3: Risk reduction** – eliminating or minimizing risks through design and documentation.
- **Step 4: Establishing safety requirements** – defining what is needed (functionality, safety performance) to eliminate the risk or reduce it to an acceptable level.
- **Step 5: Implementing functional safety system** – designing and creating safety functions.
- **Step 6: Verifying functional safety system** – ensuring that the safety system meets the defined requirements.
- **Step 7: Validating functional safety system** – returning to the risk assessment process and making certain that the safety system actually succeeded in reducing risks as specified.
- **Step 8: Documenting** – documenting the design, producing user documentation.
- **Step 9: Compliance** – proving the machine's compliance with EHSR of the Machinery Directive through compliance assessment and a technical file.

Each of these steps is explained in more detail in the following chapters.

Updating existing machinery
The following issues must be considered when updating safety requirements for existing machines:

– For machines that already have a CE marking – new components that are added to the machine must also have a CE marking. It must be case-specifically defined how the new components are applied to the old system according to the Machine Directive.
– For machines that do not have a CE marking – the safety level of the machine can be maintained by replacing components with new ones that have a CE marking. In this case, the Declaration of Incorporation is not delivered along with the machine. Directive 89/655/EEC and Amendment 95/63/EC must be fulfilled.

Ultimately, it is the relevant authority's decision as to whether the change was extensive enough to require an update of the safety level.



Figure 3-1 Process flow for meeting Machinery Directive requirements

STEP 1: Management of functional safety

To achieve the required functional safety, it is necessary to implement a project management and quality management system that is comparable to, for example, IEC 61508 or ISO 9001 standards. This management system can be specified in the form of a safety plan.

Safety plan

Standard EN 62061 specifies a safety plan for the process for meeting the requirements of the Machinery Directive. This plan needs to be designed and documented for each safety system and updated, when necessary.

Safety plan:

- identifies all relevant activities,
- describes the policy and strategy for fulfilling functional safety requirements,
- identifies responsibilities,
- identifies or establishes procedures and resources for documentation,
- describes strategy for configuration management, and
- includes plans for verification and validation.

Note:
Even though the activities listed above are not particularly specified in EN ISO 13849-1:2008, similar activities are needed to fully meet the requirements of the Machinery Directive.

When the safety plan (according to EN 62061) has been created, risk assessment starts.

STEP 2: Risk assessment

The risk assessment is a process whereby risks are analyzed and evaluated. A risk is a combination of the consequence of harm and the probability of the harm occurring when exposed to a hazard.

Note:
According to the new Machinery Directive 2006/42/EC, it is mandatory to perform a risk assessment for a machine.

The Machinery Directive 2006/42/EC requires that manufacturers perform risk assessments and take the results into account when designing a machine. Any risk considered as “high” must be reduced to an acceptable level using design changes or by applying appropriate safeguarding techniques.

The risk assessment process provides the machinery designer with requirements on how to design inherently safe machinery. It is very important to assess risks at the design phase, because it is generally more effective than providing user instructions on how to operate the equipment safely.

The risk assessment process according to EN ISO 12100-1 consists of two parts: risk analysis and risk evaluation. Risk analysis means identifying and estimating the risks and risk evaluation means deciding whether the risk is acceptable or risk reduction necessary.

Risk evaluation is carried out based on the results of the risk analysis. Decisions on the necessity of risk reduction are made according to the risk evaluation procedure.

Note:
Risk evaluation must be carried out separately for each hazard.

Four steps of risk analysis:
1. Determine the limits and intended use of the machine.
   These limits include:
   - limits of use
   - spatial limits
   - ambient or environmental limits
   - lifetime limits

2. Identify the hazards that might be generated by the machine.

3. Estimate identified risks one at a time.
   - Severity of the risk (potential consequences)
   - Probability of the risk (Frequency, Probability, Avoidance)

4. Evaluate the risk: Is risk reduction necessary?
   - **YES:** Apply risk reduction measures and return to step 2 in the risk analysis.

     The 3-step method for risk reduction according to EN ISO 12100-1 is presented in the next chapter.

   - **NO:** Risk reduction target is met and risk assessment process ends.

Document the risk assessment process and its results for each individual hazard.



Figure 3-2 Risk assessment and evaluation according to EN ISO 14121-1

After the risk assessment has been carried out, there are two options, depending on the outcome of the assessment:

Option 1
If the assessment reached the conclusion that risk reduction was not needed, the machine has reached the adequate level of safety required by the Machinery Directive.

Note:
In order for the machine to be approved and CE marking affixed, the remaining risks must be documented in the appropriate operation and maintenance manuals. There is always some residual risk.

Option 2
If the assessment revealed that the risk remains unacceptable, the process for risk reduction is started.

STEP 3: Risk reduction

The most effective way to minimize the risks is to eliminate them in the design phase, for example by changing the design or the work process of the machine. If this is not possible, one way to carry out the risk reduction process and ensure conformance with the requirements is to apply suitable harmonized standards under the Machinery Directive.

If the risk assessment process concludes that risk reduction is needed, a strategy for risk minimization is created. According to standard EN ISO 12100-1, risk reduction can be divided into three steps (the three-step method):

3-step method

1. Inherently safe design measures – creating a safer design, changing the process, eliminating the risk by design.

2. Safeguarding and complementary protective measures – safety functions, static guarding.

3. Information on use (residual risk management):
   - on the machine – warning signs, signals and warning devices – and
   - in the operating instructions.



Figure 3-3 The 3-step method for risk reduction according to EN ISO 12100-1

Residual risk is the risk that remains when all protective measures have been considered and implemented. Using technology, it is not possible to achieve a state of zero risk, since some residual risk always remains.

All residual risks must be documented in the operating instructions.

The user's part of risk reduction includes information given by the designer (manufacturer). Risk reduction measures for the machine user / organization are as follows:

- Risk reduction measures typically taken by the organization:
  - introducing safe working procedures
  - work supervision
  - permit-to-work systems
- Provision and use of additional safeguards
- Use of personal protective equipment
- Training users
- Reading operating and safety instructions and acting accordingly.

Designers should also seek valuable user input when defining protective measures.

When the risk reduction has been executed, it must be examined to ensure that the measures taken were adequate for reducing the risk to an appropriate level. This can be done by repeating the risk assessment process.

The following, remaining steps describe option 2 of the 3-step method: safeguarding through a functional safety solution.

STEP 4: Establishing safety requirements

After all the risk reduction that can be undertaken through design changes has been performed, additional safeguarding needs to be specified. Functional safety solutions can be used against the remaining hazards as an additional risk reduction measure.

Safety functions
A safety function is a function of a machine whose failure can result in an immediate increase in risk. Simply put, it comprises the measures that must be taken to reduce the likelihood of an unwanted event occurring during exposure to a hazard. A safety function is not part of machine operation itself. This means that if the safety function fails, the machine can operate normally, but the risk of injury from machine operation increases.

Defining a safety function always includes two components:

– **required action** (what must be done to reduce the risk) and
– **safety performance** (Safety Integrity Level - SIL or Performance Level - PL).

Note:
A safety function must be specified, verified (functionality and safety performance) and validated separately for each identified hazard.

Example of a safety function:
Requirement: An exposed rotating shaft may cause an injury if one gets too close to the shaft.

Action: In order to prevent personal injury from the shaft, the motor must stop in one (1) second, when the safety gate is opened.

After the safety function that executes the action has been defined, the required safety level is determined for it.

Safety performance / integrity
Safety integrity measures the performance of a safety function. It presents the likelihood of the safety function being achieved, upon request. The required safety integrity for a function is determined during the risk assessment and is represented by the achieved Safety Integrity Level (SIL) or Performance Level (PL), depending on the standard used.

The two standards use different evaluation techniques for a safety function, but their results are comparable. The terms and definitions are similar for both standards.

Determining the required SIL (EN 62061)
The process for determining the required safety integrity level (SIL) is as follows:

1. Determine the severity of the consequence of a hazardous event.
2. Determine the point value for the frequency and duration a person is exposed to the harm.
3. Determine the point value for the probability of the hazardous event occurring when exposed to it.
4. Determine the point value for the possibility of preventing or limiting the scope of the harm.

Example:
The parameters used in determining the point values are presented in the following example of an SIL assignment table.



Figure 3-4 Example of SIL assignment table

In this example, the hazard analysis is carried out for an exposed rotating shaft.

1. Severity (Se) = 3. The consequence of the hazard is permanent injury, possibly losing fingers.
2. Frequency (Fr) = 5. A person is exposed to the hazard several times a day.
3. Probability (Pr) = 3. It is possible that the hazard will take place.
4. Avoidance (Av) = 3. The hazard can be avoided.
   - 5 + 3 + 3 = 11, with the determined consequence, this equals SIL 2.

The tables used for determining the points are presented in the standard.

After the required SIL has been defined, the implementation of the safety system can begin.

Determining the required PL (EN ISO 13849-1)
To determine the required PL, select one of the alternatives from the following categories and create a “path” to the required PL in the chart.

1. Determine the severity of the damage.
The severity parameters are
S1 Slight, usually reversible injury
S2 Severe, usually irreversible injury, including death

2. Determine the frequency and duration of exposure to the hazard.
The frequency and duration parameters are
F1 Rare to often and/or short exposure
F2 Frequently to continuous and/or long exposure

3. Determine the possibility of preventing the hazard or limiting the damage caused by the hazard.
The hazard prevention and damage limiting parameters are
P1 Possible under certain conditions
P2 Hardly possible

Example:
The resulting performance level is represented by a, b, c, d and e in the following example of the PL risk graph.



Figure 3-5 Example of PL risk graph

In this example, the hazard analysis is carried out for an exposed rotating shaft.
– The consequence of the hazard is a severe, irreversible injury. Severity = S2.
– A person is exposed to the hazard several times a day. Frequency = F2.
– It is possible to avoid or limit the harm caused by the hazard. Possibility = P2.

The path leads to PL_r value d. The tables used for determining the points are presented in the standard. After the PL_r has been defined, the implementation of the safety system can begin.

STEP 5: Implementing functional safety system

When designing and constructing a safety function, the idea is to plan and construct the safety function in order to meet the required SIL / PL specified in the previous chapter. Using certified subsystems in functional safety systems can save the safety system designer a lot of work. Implementing safety functions becomes more convenient when some of the safety and reliability calculations are already made and subsystems are certified.

Note:
If certified subsystems are not used, it may be necessary to carry out safety calculations for each of the subsystems. Standards EN 62061 and EN ISO 13849-1 include information on the process and calculation parameters needed.

Implementation and verification processes are iterative and run parallel with each other. The idea is to use verification as a tool during implementation to ensure that the defined safety level is reached with the implemented system. For more information on the verification processes, see the next step.

Note:
The system is only as strong as its weakest link. This means that in order to fulfill the EHSR set by the Machinery Directive, all the subsystems of the functional safety system must meet at least the required SIL / PL value of the system.

There are several calculation software programs on the market designed for verifying functional safety systems. These programs make the whole process of creating and verifying the system more convenient.

The general steps for implementing a functional safety system include:

1. **Defining the safety requirements in a form of SIL and PL, according to standard EN 62061 or EN ISO 13849-1.**

2. **Selecting the system architecture to be used for the safety system.**
   EN 62061 and EN ISO 13849-1 standards offer basic architectures with calculation formulas.

– category B, 1, 2, 3 or 4, as presented in standard EN ISO 13849-1, or
– designated architecture A, B, C or D, as presented in standard EN 62061 for the subsystems and the whole system.

For more information on designated architectures, see the respective standards.

3. Constructing the system from safety-related subsystems – sensor/switch, input, logic, output, and actuator.

Either:
– by using certified subsystems (recommended) or
– by performing safety calculations for each subsystem.

The safety level of the complete system is established by adding together the subsystem safety levels.

4. Installing the safety system.

The system needs to be installed properly to avoid common failure possibilities due to improper wiring, environmental, or other such factors. A safety system that is not performing correctly due to careless installation is of little or no use, or even poses a risk in itself.

5. Verifying the functionality of the system.



Figure 3-6 Structure of a safety function

STEP 6: Verifying a functional safety system

Verification of the functional safety system demonstrates and ensures that the implemented safety system meets the requirements specified for the system in the safety requirements phase, and whether the safety function is viable.

Verification should not be carried out after the implementation process, but together with it, so that the implementation can indeed produce a system that will meet the specified requirements.

In addition to verifying the SIL or PL of the system, the correct operation of the safety system must also be verified by carrying out functionality testing.

Verifying SIL of safety system (EN 62061)
To verify safety integrity levels, it must be shown that the safety performance, in other words the reliability, of the created safety function is equal to or greater than the required performance target set during the risk evaluation. Using certified subsystems is advisable, because the manufacturer has already defined values for determining systematic safety integrity (SILCL) and random hardware safety integrity (PFH_d) for them.

To verify the SIL of a safety system where certified subsystems are used:

1. **Determine the systematic safety integrity for the system using SIL Claim Limit (SILCL) values defined for the subsystems.**

   SILCL represents the maximum SIL value the subsystem is structurally suitable for. SILCL is used as an indicator for determining the achieved SIL: the SILCL of the whole system should be no higher than the SILCL for the lowest subsystem.

2. **Calculate the random hardware safety integrity for the system by using the Probability of a dangerous Failure per Hour (PFH_d) values defined for the subsystems. Manufacturers of certified subsystems usually provide the PFH_d values for their systems.**

   PFH_d is the random hardware failure value that is used for determining the SIL.

3. **Use the Common Cause Failure (CCF) checklist to make sure that all the necessary aspects of creating the safety systems have been considered.**

   CCF checklist tables can be found in EN 62061 standard, Annex F.

   Calculating the points according to the list and comparing the overall score to the values listed in the standard EN 62061 Annex F, Table F.2 results to the CCF factor (β). This value is used for estimating the probability value of PFH_d.

4. **Determine the achieved SIL from the table for determining SIL.**

Example of verifying SIL:
Verifying the rotating shaft functional safety system:



Figure 3-7 Example verification of SIL

– Systematic safety integrity:
  $SIL\ CL_{sys} \leq (SIL\ CL_{subsystem})_{lowest}$ -> SIL Claim Limit 2

– Random hardware safety integrity:
  $PFH_d = PFH_{d1}+PFH_{d2}+PFH_{d3} = 2{,}5 \times 10^{-7} < 10^{-6}$

  = the system meets SIL 2.

Table for determining SIL according to PFH_d value obtained from the whole safety system (in high demand/continuous mode):

SIL	Probability of dangerous failures per hour (1/h)
SIL 1	$\geq 10^{-6}$ up to $< 10^{-5}$
SIL 2	$\geq 10^{-7}$ up to $< 10^{-6}$
SIL 3	$\geq 10^{-8}$ up to $< 10^{-7}$

Table 3-1 Table for determining SIL

Verifying PL of safety system (EN ISO 13849-1)
To verify the performance level, it must be established that the PL of the corresponding safety function matches the required PLr. If several subsystems form one safety function, their performance levels must be equal or greater than the performance level required for the said safety function. Using certified subsystems is advisable, because the safety performance values have already been defined for them.

To verify the PL of a safety system where certified subsystems are used:

1. **Determine the system's susceptibility to Common Cause Failure (CCF) using the CCF checklist.**

   CCF checklist tables can be found in EN ISO 13849-1:2008 standard, Annex I. The required minimum score is 65 points.

2. **Determine the achieved PL with the bar graph utilizing the established:**

   - Category
   - Mean Time To dangerous Failure ($MTTF_d$)
   - Diagnostic Coverage (DC)

   $MTTF_d$ is the average time it takes for a dangerous failure to occur. DC represents the number of dangerous failures that can be detected by diagnostics.

   More information on calculation details can be found in the EN ISO 13849-1 standard.

3. **Enter the resulting values into the PL graph diagram, from which the resulting PL can be determined.**

Example of verifying PL:
Verifying the rotating shaft functional safety system:



Figure 3-8 Example verification of PL

To achieve the PL_r defined in the earlier example:

– designated architecture is in Category 3,
– $MTTF_d$ value is high, and
– DC average value is low.

= the system meets PL value d.

Table for determining PL according to PFH_d value obtained for the whole safety system:

PL	Probability of dangerous failures per hour (1/h)
a	$\geq 10^{-5}$ up to $< 10^{-4}$
b	$\geq 3 \times 10^{-6}$ up to $< 10^{-5}$
c	$\geq 10^{-6}$ up to $< 3 \times 10^{-6}$
d	$\geq 10^{-7}$ up to $< 10^{-6}$
e	$\geq 10^{-8}$ up to $< 10^{-7}$

Table 3-2 Table for determining the PL

Comparing SIL and PL values

Although methods of evaluation differ between the two standards, the evaluation results can be compared on the basis of random hardware failure.

Safety integrity level SIL	Performance level PL
no correspondence	a
1	b
1	c
2	d
3	e

Table 3-3 Table for comparing SIL and PL

STEP 7: Validating functional safety system

Each safety function must be validated in order to ensure that it reduces risk as required in the risk assessment phase.

In order to determine the validity of the functional safety system, the system must be inspected against the risk assessment process carried out at the beginning of the procedure for meeting the EHSR of the Machinery Directive (see step 2 page 24). The system is valid, if it truly reduces the risks analyzed and evaluated in the risk assessment process.

STEP 8: Documenting functional safety system

The design of the machine must be documented and relevant user documentation produced before the machine fulfills the requirements set in the Machinery Directive.

Documentation needs to be carefully produced to serve its purpose. It has to be accurate and concise, but at the same time informative and easy for the user to understand. All residual risk must be documented in the user documentation, with proper instructions on how to operate the machine safely. The documentation must be accessible and maintainable. The user documentation is delivered with the machine.

For more information on the documentation required and its nature, see the EHSR in Annex I of the Machinery Directive.

STEP 9: Proving compliance

Before a machine can be placed on the market, the manufacturer must ensure that the machine is implemented in conformance with harmonized standards. It must also be proved that the combination for each safety function of the safety-related parts meets the defined requirements.

To prove the conformance with the Machinery Directive, it must be shown that:

- Machinery fulfills the relevant Essential Health and Safety Requirements (EHSR) defined in the Machinery Directive.
- Machinery fulfills the requirements of other possible Directives related to it.
- Conformity with these requirements can be ensured by following the relevant harmonized standards.
- The technical file is up-to-date and available.
  The technical file demonstrates that the machine is in accordance with the regulations presented in the Machinery Directive.

  Note:
  A missing technical file could provide reason to doubt the machine's compliance with the EHSR.

The technical file should cover the design, manufacture and operation of the machinery in so far as necessary to demonstrate compliance. For more information on the contents of the technical file, see Annex VII of the Machinery Directive 2006/42/EC.

– Conformity assessment procedures have been applied. Special requirements for machines listed in the Machinery Directive's Annex IV are met, where appropriate.
– The EC declaration of conformity has been produced and is delivered with the machine.

Once conformity has been established, a CE marking is affixed.

Machinery that carries CE markings and is accompanied by an EC declaration of conformity is presumed to comply with the requirements of the Machinery Directive.

Glossary

CE marking
A mandatory conformity mark on machinery and many other kinds of products placed on the single market in the European Economic Area (EEA). By affixing CE marking to the product, the manufacturer ensures that the product meets all of the essential requirements of the relevant European Directive(s).

CCF, Common Cause Failure
A situation where several subsystems fail due to a single event. All failures are caused by the event itself and are not consequences of each other.

DC, Diagnostic Coverage
Diagnostic Coverage (DC) is the effectiveness of fault monitoring of a system or subsystem. It is the ratio between the failure rate of detected dangerous failures and the failure rate of total dangerous failures.

EHSR, Essential Health and Safety Requirements
Requirements that machinery must meet in order to comply with the European Union Machinery Directive and obtain CE marking. These requirements are listed in the Machinery Directive's Annex I.

EN
Stands for "EuroNorm". This prefix is used with harmonized standards.

Harm
Physical injury or damage to health.

Harmonized standard
A European standard that has been prepared under the mandate of the European Commission or the EFTA Secretariat with the purpose of supporting the essential requirements of a directive and is effectively mandatory under the EU law.

Hazard
Potential source of harm.

IEC, International Electrotechnical Commission
A worldwide organization for standardization that consists of all national electrotechnical committees.
www.iec.ch

ISO, International Organization for Standardization
A worldwide federation of national standards member bodies. www.iso.org

$MTTF_d$, Mean Time To dangerous Failure
Expectation of the average time for a dangerous failure to occur.

PFH_d, Probability of dangerous Failure per Hour
Average probability of dangerous failure taking place during one (1) hour. PFH_d is the value that is used for determining the SIL or PL value of a safety function.

PL, Performance Level
Levels (a, b, c, d, e) for specifying the capability of a safety system to perform a safety function under foreseeable conditions.

PL_r
Required Performance Level (based on the risk evaluation).

Risk
A combination of how possible it is for the harm to happen and how severe the harm would be.

Safety function
A function designed for adding safety to a machine whose failure can result in an immediate increase in risk(s).

SIL, Safety Integrity Level
Levels (1, 2, 3, 4) for specifying the capability of an electrical safety system to perform a safety function under foreseeable conditions. Only levels 1-3 are used in machinery.

SILCL, SIL Claim Limit
Maximum safety integrity level (SIL) that can be claimed for an electrical safety system, taking account of architectural constraints and systematic safety integrity.

Subsystem
A component of a safety function that has its own safety level (SIL /PL) that affects the safety level of the whole safety function. If any of the subsystems fail, the whole safety function fails.

Index

A
Annex IV 11, 12, 39

C
CE marking 7, 10, 23, 26, 39, 40
CEN 12, 16
CENELEC 12, 16

D
documenting safety system 38

E
EHSR 8, 9, 10, 18, 22, 32, 37, 38, 40
emergency stop 13, 21
emergency switching off 20
EN 61800-5-2 18
EN 62061 13, 14, 16, 24, 29, 32, 34
EN ISO 13849-1 13, 14, 16, 24, 30, 32, 35

F
functional safety 9, 23, 28
functional safety system 32, 33, 37

H
harmonized standards 8, 12, 16, 22, 26, 38

I
IEC, International Electrotechnical Commission 15, 40
ISO, International Organization for Standardization 15, 41

M
Machinery Directive 8, 9, 11, 12, 22, 24, 26, 32, 37, 38
Machinery Directive 2006/42/EC 11, 24, 38
Machinery Directive 98/37/EC 11, 39

P
PL, Performance Level 15, 17, 29, 30, 35, 37, 41
proving compliance 40

R
residual risk 26, 27, 28, 38
risk analysis 10, 18, 24, 25
risk assessment 12, 16, 18, 24, 26, 27, 29, 37
risk reduction 9, 13, 16, 24, 25, 26

S
safe brake control (SBC) 21
safe direction (SDI) 20
safely-limited speed (SLS) 19
safe operating stop (SOS) 19
safe speed monitor (SSM) 20
safe stop 1 (SS1) 19
safe stop 2 (SS2) 19
safety functions 9, 10, 13, 14, 17, 18, 19, 27, 28, 32, 33, 37, 38, 41
safety performance 8, 10, 29, 34, 35
safety plan 23
SIL, Safety Integrity Level 15, 17, 29, 34, 37, 41

T
transition period 14
type-A standards 13
type-B standards 13
type-C standards 13

U
updating existing machinery 22

V
validating safety system 39
verifying safety system 35

Contact us

For more information contact
your local ABB representative or visit:

www.abb.com/drives
www.abb.com/drivespartners

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.

3AUA0000048753 REV D EN 30.3.2011 #15511

Power and productivity
for a better world™

Contact us

For more information contact
your local ABB representative or visit:

www.abb.com/drives
www.abb.com/drivespartners

© Copyright 2011 ABB. All rights reserved.
Specifications subject to change without notice.

3AFE64514482 REV F EN 17.6.2011 #15501

Power and productivity
for a better world™